

# Geologic Map of Colorado National Monument and Adjacent Areas, Mesa County, Colorado

By Robert B. Scott,<sup>1</sup> Anne E. Harding,<sup>1</sup> William C. Hood,<sup>2</sup>  
Rex D. Cole,<sup>3</sup> Richard F. Livaccari,<sup>3</sup> James B. Johnson,<sup>3</sup>  
Ralph R. Shroba,<sup>1</sup> and Robert P. Dickerson<sup>1</sup>

*Prepared in cooperation with the National Park Service and the  
Colorado National Monument Association*

**Geologic Investigations Series I-2740**  
**2001**

<sup>1</sup>U.S. Geological Survey, Denver, CO 80225

<sup>2</sup>515 Dove Court, Grand Junction, CO 81503

<sup>3</sup>Department of Physical and Environmental Sciences, Mesa State College, Grand Junction, CO 81502

**U.S. Department of the Interior  
U.S. Geological Survey**

# Contents

Description of map units .....	1
Introduction .....	1
Surficial units .....	3
Artificial-fill deposits.....	3
Artificial fill.....	3
Alluvial deposits .....	3
Alluvium.....	3
Flood-plain and stream-channel deposits.....	3
Valley-fill deposits .....	4
River-gravel deposits .....	4
Alluvial and colluvial deposits.....	5
Young fan-alluvium and debris-flow deposits.....	5
Younger alluvial-slope deposits .....	5
Older alluvial-slope deposits .....	6
Local gravel deposits .....	6
Colluvial deposits .....	7
Colluvium, undivided .....	7
Rockfall deposits.....	7
Younger landslide deposits .....	8
Older landslide deposits .....	8
Sheetwash deposits.....	8
Eolian deposits.....	9
Eolian sand.....	9
Eolian and colluvial deposits.....	9
Eolian sand and sheetwash deposits.....	9
Marsh deposits.....	9
Cienaga deposits .....	9
Bedrock units.....	10
Mancos Shale .....	10
Dakota Formation.....	11
Burro Canyon Formation.....	12
Morrison Formation.....	12
Brushy Basin Member.....	13
Salt Wash Member .....	14
Tidwell Member.....	14
Wanakah Formation .....	16
Entrada Sandstone .....	16
"board beds" unit.....	16
Slick Rock Member .....	17
Wanakah Formation and Entrada Sandstone, undivided.....	17
Kayenta Formation.....	17
Wanakah Formation and Entrada Sandstone and Kayenta Formation, undivided .....	18
Wingate Sandstone.....	18
Chinle Formation .....	19
Lamprophyre dikes.....	19
Meta-igneous gneiss .....	19
Migmatitic meta-sedimentary rocks .....	20


<b>Selected stratigraphic topics.....</b>	<b>21</b>
Alluvial fans.....	21
Bedrock contacts.....	21
<b>Geochronology.....</b>	<b>22</b>
<b>Geologic formation of Colorado National Monument .....</b>	<b>26</b>
Geologic History .....	26
Structural and tectonic issues.....	28
Interpretation of structures at Colorado National Monument .....	28
Late Cenozoic regional uplift.....	31
Pliocene arching at Unaweep Canyon.....	31
<b>Geologic hazards.....</b>	<b>33</b>
<b>Geologic resources.....</b>	<b>34</b>
<b>Acknowledgments .....</b>	<b>34</b>
<b>References cited.....</b>	<b>34</b>
<b>Glossary .....</b>	<b>37</b>

## Figures

Figure 1. Regional geographic features in western Colorado and eastern Utah.....	28
Figure 2. Geographic features near the map area .....	29

## Tables

Table 1. Grain sizes in metric and English units.....	1
Table 2. Factors for conversion of metric units to English units .....	1
Table 3. Definitions of divisions of geologic time.....	2
Table 4. $^{14}\text{C}$ laboratory and calibration ages for sediments.....	24



# Description of Map Units

## Introduction

This introduction provides information that makes the DESCRIPTION OF MAP UNITS easier to understand. Explanations are given for ages of surficial deposits. References are provided for publications that explain or define soil horizons, grain sizes, soil colors, bedrock colors, and igneous and sedimentary rock terms. Tables are included that show geologic grain sizes, conversion from metric to English units, and geologic time. Geologic terms used in this text that are not in Webster's New World Dictionary, Third College Edition, are italicized, and brief definitions of these terms are provided in the GLOSSARY at the end of the text.

Age assignments for surficial deposits are based chiefly on the degree of modification of original landform or surface morphology, height above stream level, and degree of soil development. Age assignments for units Qrg (river-gravel deposits) and Qlg (local gravel deposits) are based chiefly on a regional rate of stream downcutting or incision of about 0.14 m/ky (ky, thousand years), a minimum local rate of steam downcutting of about 0.16 m/ky, and on a local rate of stream downcutting of about 0.14 m/ky.

The regional incision rate of 0.14 m/ky is based on an average of three values for stream incision since deposition of the  $640 \pm 4$ -ka (M.A. Lanphere, written commun., 2000) (ka, thousand years old) Lava Creek B volcanic ash: (1) about 90 m of incision along the Colorado River near the east end of Glenwood Canyon (Izett and Wilcox, 1982), (2) about 88 m of incision along the Roaring Fork River near Carbondale, Colorado (Piety, 1981), and (3) about 80–85 m of incision along the White River near Meeker, Colorado (Whitney and others, 1983; J.W. Whitney, U.S. Geological Survey, oral commun., 1992).

The minimum local rate is based on about 1,600 m of downcutting by the Colorado River after eruption of the 10-Ma (Ma, million years old) basalt on Grand Mesa (Maryvin and others, 1966) near Palisade, Colorado, about 18 km east of the map area. The reason a minimum rate is proposed at Grand Mesa is because the timing of initial downcutting of Grand Mesa by the Colorado River is unknown.

The local rate of stream downcutting of 0.14 m/ky is based on the presence of the Lava Creek B volcanic ash about 91 m above the drainage at a site on the Harley Dome 7.5-minute quadrangle in Utah ( $39^{\circ}13.52'$  Lat.,  $109^{\circ}10.44'$  Long.) (Willis, 1994). This identification was reconfirmed by major-element analyses by Andrei Sarna-Wojcicki (U.S. Geological Survey, written commun., 2000) and by trace-element analyses by Jim Budahn (U.S. Geological Survey, written commun., 2000). Another ash sample collected by Rex Cole, Bill Hood, and Paul Carrara 1.8 km east of the Utah border ( $39^{\circ}20.166'$  Lat.,  $109^{\circ}01.770'$  Long.) on the Bar X 7.5-minute quadrangle could not be positively identified as Lava Creek B ash because of alteration. This ash is also about 91 m above the local drainage.

Sand, gravel, and other surficial deposits shown on the map are estimated to be at least 1 m thick. Where surficial deposits

are thin or discontinuous they were not mapped. Soil-horizon designations are those of the Soil Survey Staff (1975), Guthrie and Witty (1982), and Birkeland (1999). Most of the surficial deposits are calcareous and contain variable amounts of primary and secondary calcium carbonate; stages of secondary calcium carbonate morphology (referred to as stages I through III horizons in this report) are those of Gile and others (1966). Grain sizes given for surficial deposits and bedrock are based on field estimates and follow the modified Wentworth (1922) scale (American Geological Institute, 1982) (Table 1). In descriptions of surficial map units, the term "clasts" refers to the fraction greater than 2 mm in diameter, whereas the term "matrix" refers to the particles less than 2 mm in size. Dry matrix colors of the surficial deposits were determined by comparison with Munsell Soil Color Charts (Munsell Color, 1973). Colors of the surficial deposits correspond to those of the sediments and (or) bedrock from which they were derived.

Bedrock colors were determined by comparison with the Geological Society of America Rock-Color Chart (Rock-Color Chart Committee, 1951). Igneous rock terms follow that of the IUGS classification (Streckeisen, 1973). Sedimentary bedrock terms follow the classifications of Folk (1974) for sandstone and conglomerate, Dunham (1962) for carbonate rocks, and Picard (1971) for mudstone (we use "mudstone" in place of Picard's term "mudrock"). Bedding thickness terms follow those of Ingram (1954) and Potter and others (1980). Degree of sorting terms follow those of Pettijohn and others (1973) and Folk (1974). Grain shape terms follow those of Powers (1953). Sedimentary structure terms follow those of McKee and Weir (1953), Campbell (1967), Allen (1970), and Boggs (1995). Fossil and trace fossil terms follow those of Ekdale and others (1984) and Pemberton and others (1992).

Metric units are used in this report; a conversion table is provided for those more familiar with English units (Table 2). A review of the divisions of geologic time used in this report is also provided (Table 3).

**Table 1.** Grain sizes in metric and English units (American Geological Institute, 1982).

Clay	less than 0.004 mm	less than 0.00016 inches
Silt	0.004 to 0.062 mm	0.00016 to 0.0025 inches
Sand	0.062 to 2 mm	0.0025 to 0.08 inches
Granule	2 to 4 mm	0.08 to 0.16 inches
Pebble	4 to 64 mm	0.16 to 2.5 inches
Cobble	64 to 256 mm	2.5 to 10 inches
Boulder	greater than 256 mm	greater than 10 inches

**Table 2.** Factors for conversion of metric units to English units to two significant figures.

Multiply	By	To obtain
centimeters (cm)	0.39	inches
meters (m)	3.3	feet
kilometers (km)	0.62	miles


**Table 3.** Definitions of divisions of geologic time used in this report.

EON	ERA	Period	Epoch/Age <sup>2</sup>	Years
PHANEROZOIC	CENOZOIC	Quaternary	Holocene	0 to 10 thousand
			<sup>1</sup> Pleistocene	10 thousand to 1.65 million
		Tertiary		1.65 to 66.4 million
	MESOZOIC	Cretaceous	Late Cretaceous	66.4 to 97.5 million
			<b>Turonian</b>	88.5 to 91 million
			<b>Cenomanian</b>	91 to 97.5 million
		Early Cretaceous		97.5 to 144 million
			<b>Albian</b>	97.5 to 113 million
			<b>Aptian</b>	113 to 119 million
		Jurassic	Late Jurassic	163 to 144 million
	PROTEROZOIC		<b>Tithonian</b>	144 to 152 million
			<b>Kimmeridgian</b>	152 to 156 million
			<b>Oxfordian</b>	156 to 163 million
		Middle Jurassic		163 to 187 million
			<b>Callovian</b>	163 to 169 million
		Lower Jurassic		187 to 208 million
			<b>Pliensbachian</b>	193 to 198 million
	EARLY PROTEROZOIC		<b>Sinemurian</b>	198 to 204 million
			<b>Hettangian</b>	204 to 208 million
		Triassic	Late Triassic	208 to 230 million
			<b>Norian</b>	208 to 225 million
			<b>Carnian</b>	225 to 230 million
				1,600 to 2,500 million

After Hansen (1991) except for the Pleistocene.

<sup>1</sup>Subdivisions of Pleistocene time are informal and are as follows: late Pleistocene is 10–132 thousand years, middle Pleistocene is 132–788 thousand years, and early Pleistocene is 788–1,650 thousand years (Richmond and Fullerton, 1986). Subdivisions of the Cretaceous, Jurassic, and Triassic follow those of Geological Society of America (1999).

<sup>2</sup>Subdivisions of epochs are Ages, the smallest division of geologic time; Ages are shown in bold. These small subdivisions of time are most commonly used by paleontologists and stratigraphers.



Fallen rock, as viewed part way down the Ute Canyon Trail. View to the east. *Photograph by R.B. Scott, 1998.*

## Surficial Units

To make the descriptions of surficial units easier for the non-geologist to read, the first paragraph of each description provides a summary statement. More detailed technical information follows.

**Artificial-fill Deposits**—Artificial-fill deposits include compacted and uncompacted material composed mostly of silt, sand, and rock fragments placed beneath and adjacent to highways, an airstrip, stock ponds, and earthen dams.

**af Artificial fill (latest Holocene)**—Most of the artificial fill consists of compacted and uncompacted fill material composed of silt, sand, and rock fragments. The map unit was mapped beneath segments of the Interstate 70 overpass at the junction with U.S. Highway 6-50 and beneath segments of Rim Rock Drive, the road that follows the canyon rims in Colorado National Monument, particularly where road reconstruction required fill after the flash flood of 1968 in Fruita Canyon.

Small amounts of fill beneath the nearby tracks of the Denver and Rio Grande Western Railroad were not mapped. Artificial fill was also used in constructing the reservoir in lower Fruita Canyon and in many minor dams for stock ponds on private land. A dirt airstrip near the southern border of the map area is underlain in part by artificial fill. Generally the map unit is less than 10 m thick, but beneath Rim Rock Drive, artificial fill is locally greater than 50 m thick.

**Alluvial Deposits**—Alluvial deposits include silt, sand, and gravel in flood plains, stream channels, and terraces along the Colorado River and its tributaries.

**Qal Alluvium (Holocene)**—Alluvium consists chiefly of stream-channel deposits along streams that are tributaries of the Colorado River.

The map unit includes minor undifferentiated *colluvial deposits* such as young *fan-alluvium* and *debris-flow deposits* (Qfy), *debris-flow deposits* (not shown as a separate map unit), and *sheetwash deposits* (Qsw). Locally, the unit includes boulders as large as 2 m in diameter. Unit Qal typically consists of interbedded sand, pebbly sand, and pebble gravel and ranges from thin-bedded (0.1 to 0.5 cm) clayey, silty sand to thick-bedded (>1 m), poorly sorted, both *clast- and matrix-supported*, slightly bouldery, pebble and cobble gravel with a sand *matrix*. Little or no secondary carbonate is present.

Low-lying areas of the map unit are prone to periodic flooding and *debris-flow* deposition, particularly during and after major thunderstorms.

Associated flash floods pose a serious hazard in narrow, restricted canyons of Colorado National Monument. Significant potential for flash flood and debris-flow hazards also exists in and near stream channels between the highlands of the Monument and the Colorado River. The exposed thickness of alluvium is about 1 to 4 m.

### Qfp

**Flood-plain and stream-channel deposits (Holocene and late Pleistocene)**—Most of the flood-plain and stream-channel deposits consist of *clast-supported*, slightly bouldery, pebble and cobble gravel in a sand *matrix* deposited along the Colorado River.

The unit contains lenses of gravelly sand to sandy silt. A thin upper part is locally present and consists of gravelly sand or sandy silt. In the lower part, *clasts* are generally less than 40 cm in diameter, subrounded to well rounded, and poorly to moderately well sorted. *Clasts* were derived from bedrock units upstream along the Colorado River and its tributaries. The unit contains an assortment of *clasts* of Cenozoic, Mesozoic, and Paleozoic sedimentary rocks, which include the yellowish-gray- (5Y7/2) weathering “oil shale” of the Green River Formation and moderate-red (5R5/4) Maroon Formation. The *clasts* also include igneous rocks of several ages, which include granitic rocks as well as rhyolitic and basaltic volcanic rocks, numerous Proterozoic metamorphic rocks, and minor *hornfels* from contact metamorphism of the Morrison Formation. Sediments exposed in gravel pits (boundaries of pits are delineated by dashed lines) locally display *scour-and-fill structure*. Elongate *clasts* are inclined upstream forming an overlapping imbricate structure.

Unit Qfp is in low-lying areas and is subject to flooding, particularly during spring runoff from snow melt in mountainous areas upstream along the Colorado River and its tributaries. Gravel is an important resource that is becoming increasingly scarce in and near the map area. Drill-hole data for the area north of the Colorado River indicate that 3 to 15 m of *sheetwash deposits* (Qsw) overlie 3 to 7 m of Colorado River gravel in unit Qfp, which in turn overlies Mancos Shale (Km) (Ken Weston; U.S. Bureau of Reclamation, written commun., 1999; Phillips, 1986). These data, however, may not represent the entire thickness of unit Qfp, because it is difficult to distinguish in drilling records between *sheetwash deposits* (Qsw) and lenses of sandy silt in the upper part of unit Qfp. The thickness of unit Qfp locally may exceed 7 m.

<b>Qvf</b>	<b>Valley-fill deposits (Holocene and late Pleistocene)</b> —Valley-fill deposits that floor parts of many canyons of the Monument consist chiefly of sand and silt of stream-terrace alluvium and probably sandy <i>debris-flow deposits</i> , but also locally include stony colluvium on valley sides as well as minor deposits of eolian sand (Qe) and <i>sheetwash</i> (Qsw).	gravel lenses in the lower part can be traced only a few meters at most, are about 2 to 5 cm thick, and consist chiefly of small granules and pebbles.
	The valley-fill deposits can be subdivided into a thicker bedded (> 30 cm), slightly calcareous, upper part and a thinner bedded (< 30 cm), calcareous, lower part. Both parts consist mostly of sand and silt that contain small, discontinuous lenses of gravel. Cobbles are as large as 25 cm in diameter. Both parts locally contain several buried, weakly developed <i>paleosols</i> and common small (< 2 mm) charcoal fragments. Some of these <i>paleosols</i> are darker than the rest of unit Qvf because of the accumulation of organic matter; they contain abundant charcoal, presumably from burnt woody vegetation. Charcoal not associated with <i>paleosols</i> is concentrated at bedding breaks in the sediments, but charcoal also occurs within beds. The age of the valley-fill deposits, based on calibrated $^{14}\text{C}$ ages (Table 4), ranges from at least 1,180 to 6,200 years BP (before present, actually before 1954) in the upper part to at least as old as 10,360 years BP in the lower part (Scott, Hood, and others, 1999). The discovery in No Thoroughfare Canyon of a mastodon tooth, which was probably eroded from the undated lowest part of the unit, is consistent with a late Pleistocene age for the lower part of the map unit (for more information, see the text under SELECTED STRATIGRAPHIC TOPICS and GEOCHRONOLOGY).	Valley-fill deposits are best exposed in terrace scarps in the upper part of No Thoroughfare Canyon, but isolated remnants of the unit Qvf are widespread in most canyons throughout the Monument. The upper part is as thick as about 10 m, but it is thinner where it overlies bedrock near canyon walls. The top of the lower part of unit Qvf is commonly 10 m below the top of the unit, and the lower part of unit Qvf is commonly less than 10 m thick. Unit Qvf is locally as much as 30 m thick.
<b>Qrg</b>	<b>River-gravel deposits (late? and middle Pleistocene)</b> —River-gravel deposits are chiefly <i>clast-supported</i> , bouldery, cobble and pebble gravel in a sand <i>matrix</i> left as isolated remnants on hilltops on the south side of the Colorado River.	The <i>clasts</i> are generally less than 50 cm in diameter, subrounded to well rounded, and poorly to moderately sorted. Gravel and lenses of gravelly sand to sandy silt are exposed in gravel pits. These pits also reveal <i>scour-and-fill structures</i> as well as an imbricate <i>clast</i> fabric that is consistent with the westward flow direction of the Colorado River. <i>Clasts</i> include the diagnostic moderate-red Maroon Formation and the yellowish-gray Green River Formation among other rock types typical of those transported by the Colorado River that are listed in the description for unit Qfp. Secondary calcium carbonate coatings on <i>clasts</i> have stage I-II morphology.

The upper part of unit Qvf has beds that range typically from 0.1 to 2 m thick, is generally reddish brown (5YR5/4) to yellowish red (5YR5/8), contains minor charcoal fragments, and has a 0.5-m-thick surface soil. The upper part is weakly indurated by calcium carbonate. In the upper part, gravel lenses range from 0.1 to 0.7 m thick. *Clasts* consist of angular to subangular sandstone and minor sedimentary quartzite that range in size from 2-mm granules to 25-cm cobbles. They are coated with secondary calcium carbonate.

The lower part typically has beds 5 to 50 cm thick, is yellow (2.5Y7/6) to reddish yellow (7.5YR 6/6) and locally light olive brown (2.5Y5/4), has iron oxide staining, and contains more charcoal fragments and fewer gravel lenses than the upper part. The lower part is weakly indurated, due in part to secondary calcium carbonate in a stage II horizon. Thin beds of fine sand and silt in the lower part are slightly wavy and can be traced for more than 40 m along some exposures. The

Unit Qrg caps hills on the south side of the Colorado River and locally underlies unit Qaso. The tops of the river-gravel deposits are about 15, 35, 65, 75, and 110 m above the Colorado River. The heights of these deposits suggest that unit Qrg is equivalent in age to late and middle Pleistocene terrace alluvium (units Qty, Qto, and Qtt) outside the map area farther upstream along the Colorado River near Rifle and New Castle, Colorado (Shroba and Scott, 1997; Scott and Shroba, 1997). The presence of deposits of unit Qrg on or near the north-dipping Dakota Formation (Kd) suggests that as the Colorado River cut downward, it migrated northward, eroding the less resistant Mancos Shale (Km) rather than the more resistant underlying Dakota Formation (Kd). The lowest gravel is about 15 m above the Colorado River in a terrace mantled by unit Qaso. It is as much as 3 m thick and it can be traced in poor exposures in gullies in the Redlands area where it thins to about 1 to 2 m thick (indicated on the map by a single dashed line). The thickness of unit Qrg is 1 to 4 m.



Ute Canyon, view to the northeast. The canyon is floored by the resistant Proterozoic *migmatitic* meta-sedimentary rocks. The top of the cliffs have remnants of rocks younger than the Kayenta Formation. *Photograph by R.B. Scott, 1998.*

**Alluvial and Colluvial Deposits**—Alluvial and *colluvial deposits* are mostly silt, sand, and gravel in fans on flood plains, in alluvial-slope deposits on river gravel and bedrock, in remnants of tributary stream alluvium and *debris-flow deposits*, and in deposits of pebbly silty sand that locally mantle canyon bottoms.

**Qfy Young fan-alluvium and debris-flow deposits (Holocene)**—Young *fan-alluvium* and *debris-flow deposits* consist chiefly of well-sorted silty sand and subordinate, discontinuous lenses and layers of *clast-supported* gravel present on the south side of the Colorado River.

Beds of silty sand are chiefly massive ( $> 1$  m thick), but are locally present in beds as thin as 1.5 cm. Some of the silty sand may have been deposited as eolian sand, but much of it is probably reworked by water. Gravel layers are commonly 5 to 45 cm thick. Unit Qfy consists of material reworked from unit Qaso, silty eolian sand, and, locally, Colorado River gravel reworked from unit Qrg. Gravel *clasts* range from 2-mm granules to boulders greater than 1 m in diameter near active stream channels. These *clasts* are rounded to subrounded, moderately to poorly sorted, and were derived mostly from Proterozoic and Mesozoic

units exposed in the highlands to the south in the Uncompahgre Plateau. The gravel was probably deposited by streams and locally by *debris flows*. Colors of the unit, where silty sand dominates, range from yellowish red (5YR5/8) to reddish yellow (5YR6/6). The gravel lends a gray color to the unit. There is little or no secondary carbonate on *clasts* and in the *matrix*.

Unit Qfy forms a few small fans on flood-plain and stream-channel deposits (Qfp) along the south bank of the Colorado River. The base of unit Qfy is as low as 1.5 m above the river. The exposed thickness is about 1 to 4 m, and the maximum thickness is about 20 m.

**Qasy Younger alluvial-slope deposits (late Pleistocene)**—Younger alluvial-slope deposits consist chiefly of well-sorted silty sand and subordinate, discontinuous lenses and layers of *clast-supported* gravel and are found along the south side of the Colorado River.

Silty sand ranges commonly from 20 to 80 cm thick, but locally forms beds as thin as 1 cm that probably represent eolian material that was

reworked by water. Gravel layers are commonly 3 to 70 cm thick. Unit Qasy consists of material reworked from unit Qaso as well as primary and reworked silty eolian sand. Gravel *clasts* range from granules to boulders larger than 1 m in diameter near active stream channels. These *clasts* are poorly sorted and subrounded and were derived mostly from Proterozoic and Mesozoic units exposed in the highlands to the south in the Uncompahgre Plateau. The gravel was probably deposited by streams and locally by *debris flows*. Colors of the silty sand range from yellowish red (5YR5/8) to reddish yellow (5YR6/6); gravel lends a gray color to the unit. Secondary carbonate morphology on *clasts* and in the *matrix* is stage I-II.

Unit Qasy overlies Mancos Shale (Km) and Dakota Formation (Kd) on the south side of the Colorado River. The upper part of unit Qasy is partly covered by unmapped thin *sheetwash* (Qsw) and *colluvial* debris (Qc) derived from bedrock units upslope and by thin, unmapped deposits of eolian sand (Qe). The maximum thickness is about 15 m.

#### **Qaso Older alluvial-slope deposits (late Pleistocene)—**

Older alluvial-slope deposits consist chiefly of layers and lenses of poorly sorted, *matrix-* and *clast-supported* gravel and well-sorted silty sand and are found at the base of the mountain front.

The gravel *clasts* range in size from granules to boulders 1.5 m in diameter. These *clasts* are predominately metamorphic and igneous rocks derived from Proterozoic rocks and less abundant sandstone and limestone *clasts* derived from Mesozoic rocks to the south in the highlands in the Uncompahgre Plateau. The *matrix* of the gravel is silty sand. Gravel has light- to dark-gray colors from the *clasts* and a pink (5YR7/3-4) *matrix*. Gravely zones exceed 6 m in thickness, and silty sand beds are 0.2 to 6 m thick. Most *clasts* are subangular to subrounded, but some of the angularity of the *clasts* appears to be related to weathering after deposition. The gravel layers are massive to poorly bedded, and, locally, gravel forms discontinuous lenses in thick beds of silty sand. Zones of non-sorted to very poorly sorted bouldery deposits suggest deposition as *debris flows*; some gravel deposits are better sorted and were probably deposited by alluvial processes. In the upper 0.3 m of the unit, secondary calcium carbonate in the *matrix* and on *clasts* has stage II morphology; at a depth of 5 to 6 m, gravel is indurated by secondary calcium carbonate that has strong stage III morphology.

The silty sand layers are generally massive to weakly bedded and have colors that range from yellowish red (5YR5/8) to reddish yellow (5YR6/6). Where bedding is more distinct, the beds of silty sand are 0.1 to 0.5 m thick, and massive silty sand is locally as thick as 6 m. Eolian processes may have initially deposited much of this silty sand. Some of it was probably reworked by stream and *sheetwash* processes. Unmapped discontinuous eolian deposits (Qe) and locally thin sheet-wash deposits (Qsw) as much as 1 to 3 m thick partly mantle unit Qaso. Silty sand has stage I-II secondary calcium carbonate morphology at a depth of 6 m.

Map unit Qaso commonly overlies Colorado River gravel (Qrg) near the bluffs on the south side of the Colorado River. Unit Qaso is locally exposed in the area between the Colorado River and the faulted front of the Uncompahgre Plateau. The top of unit Qaso is about 10 to 65 m above the Colorado River. Exposed thicknesses are at least 6 m, and the maximum thickness suggested by topography is in excess of 20 m.

#### **Qlg**

#### **Local gravel deposits (late? to middle Pleistocene)—**

Local gravel deposits are poorly sorted, subrounded, *clast-* and *matrix-supported* pebble and cobble gravel that locally contains boulders as long as 2 m. Unit Qlg was deposited by streams tributary to the Colorado River, and it probably includes both stream alluvium (Qal) as well as *debris-flow deposits*. *Clasts* consist primarily of metamorphic and igneous Proterozoic rocks and secondarily of sedimentary rocks eroded from the adjacent highlands in the Uncompahgre Plateau. These deposits form isolated remnants on hilltops in the Redlands area.

Thin lenses of silty sand and scattered granules and pebbles are present locally in unit Qlg. In the upper 2 m of the unit, secondary calcium carbonate coats *clasts*, and the *matrix* consists of yellowish-red (5YR5/6), calcium carbonate-rich (stage II), silty sand and granules.

Unit Qlg probably consists of remnants of stream-channel and *debris-flow deposits* that accumulated below the mouths of canyons along the front of the Uncompahgre Plateau. Eroded remnants of these former valley floors are preserved on hilltops at different heights between about 6 and 67 m above modern intermittent tributary streams. Assuming an incision rate of about 0.14 m/ky for the Colorado River and its tributary streams, unit Qlg was deposited at different times between about 42 ka and 480 ka. Gravel locally fills channels as deep as 1 m that are cut in the underlying bedrock. At one locality, east of Riggs Hill in the eastern part of the map area, unit Qlg



Independence Monument to the northwest as viewed from the Monument Canyon Trail. An apron of rock-fall deposits partially rings the base.  
Photograph by R.B. Scott, 1998.

overlies Colorado River gravel (Qrg). This indicates deposition of tributary gravel on a former flood plain or terrace of the Colorado River. The weathering of *clasts*, as indicated by the angularity of Proterozoic metamorphic and igneous *clasts*, is greater with age of the deposit and therefore is greater with height above stream level. *Clasts* of biotite-rich schist are particularly susceptible to both disaggregation and spheroidal weathering. Thin, unmapped veneers of Holocene eolian sand (Qe) mantle most of unit Qlg. The thickness of unit Qlg is as much as 6 m.

**Colluvial Deposits**—Colluvial deposits include silt, sand, and rock fragments on valley sides and hill slopes that were mobilized, transported, and deposited by gravity and sheet erosion.

**Qc Colluvium, undivided (Holocene and late Pleistocene)**—*Colluvium*, undivided, consists mostly of *clast-supported* pebble, cobble, and boulder gravel with a *matrix* of silty sand, minor clayey silt, and, locally, gravelly silt and is found along the steeper slopes of the mountain front.

Rock type and colors of colluvium reflect the bedrock and surficial units from which the colluvium was derived. Unit Qc is commonly associated with rockfall deposits (Qr) at the base of cliffs of the Wingate Sandstone (Jwg). Locally, unit Qc includes *sheetwash* (Qsw), *debris-flow*, and *landslide* (Qlso and Qlsy) deposits. Colluvium derived from the Morrison Formation, contains *expansive clays*. Colluvium derived from the Chinle Formation (Tc) is silty and non-expansive. *Clasts* are angular to subangular and are as large as 2 m in diameter. Secondary carbonate coatings on *clasts* in the upper part of the unit are thin and have stage I morphology. The maximum thickness is about 5 m.

**Qr Rockfall deposits (Holocene and late Pleistocene)**—

Rockfall deposits include boulders and smaller debris deposited on slopes at the base of cliffs, particularly cliffs of the Wingate Sandstone (Jwg).

The *matrix* is probably non-calcareous to calcareous, *clast-supported*, sandy rubble. *Clasts* are typically 1 to 2 m in diameter, but some exceed 12

m in length. *Clasts* on younger rockfall deposits are unweathered and have light bedrock colors. *Clasts* on older rockfall deposits are weathered and coated with a brownish-gray to brownish-black *desert varnish*. The thickness of unit Qr is 1 m to greater than 3 m.

**Qlsy** **Younger landslide deposits (Holocene)**—Younger landslide deposits are mostly intact, active or recently active earth-block slides (Varnes, 1978). These slides commonly have crescentic headwall scarps and form where the south side of the Colorado River has locally cut steep slopes on the uppermost Dakota Formation (Kd) and the lower-most Mancos Shale (Km).

The sizes and rock type of the *clasts* and the grain-size distributions and colors of the matrices of these slides reflect those of the displaced bedrock units and surficial deposits. Landslide deposits are prone to continued movement or reactivation due to natural as well as human-induced processes.

Blocks capped by units Qasy and Qaso have been downdropped to form small grabens, open tension gashes, and a series of slide blocks that step down toward the Colorado River. Closer to the river, these slide blocks are more disrupted. Upslope from the main scarp, incipient landsliding is indicated by cracks as much as 80 m from the river, where future breakaways will form. The toes of the landslides are being removed by the Colorado River. The presence of these young landslides indicates slope instability, which poses a hazard to roads or structures built on bluffs close to the river. In the adjacent Grand Junction 7.5-minute quadrangle, young landslides have damaged a sewage treatment plant and an irrigation pump station. An active landslide was destroying a house near the eastern border of the map area south of the Colorado River as this map was being prepared. The thickness of unit Qlsy is at least 8 m and possibly as much as 35 m.

**Qlso** **Older landslide deposits (late to middle? Pleistocene)**—Older landslide deposits consist chiefly of unsorted and unstratified rock debris characterized by hummocky topography. Many of the landslides are complex (Varnes, 1978). All of them formed on unstable slopes that are underlain by the Brushy Basin Member of the Morrison Formation (Jmb). These landslide deposits include debris from the Brushy Basin Member of the Morrison Formation (Jmb), the Burro Canyon Formation (Kb), and the Dakota Formation (Kd), and are particularly abundant on the slopes of Black Ridge. Landslide deposits are prone to continued movement or reactivation due to natural as well as human-induced processes.

Most of the map unit lacks distinctive landforms such as crescentic headwall scarps and lobate toes, but the deposits have hummocky surfaces. Rejuvenated parts of unit Qlso have crescentic headwall scarps shown on the map by hachured lines. Unit Qlso includes debris-slide, rock-slide, debris-slump, rock-slump, slump-earth-flow, earth-flow, and *debris-flow deposits* as defined by Varnes (1978).

The sizes and rock types of the *clasts* and the grain-size distributions and colors of the matrices of these deposits reflect those of the displaced bedrock units and surficial deposits. Deposits derived from the Dakota Formation (Kd) and the Burro Canyon Formation (Kb) contain blocks of rock as long as 6 m. Landslide deposits derived from the Brushy Basin Member of the Morrison Formation (Jmb) are rich in clay. Brushy Basin-derived clay contains *expansive smectitic clay* and locally has high shrink-swell potential.

In the west-central part of the map area, landslides as long as 2.5 km flank the west, north, and east sides of Black Ridge. These landslides flowed over the rim of Monument Canyon and locally cover the Proterozoic rocks exposed on the canyon floor. The northeast-dipping Brushy Basin Member of the Morrison Formation (Jmb), the Burro Canyon Formation (Kb), and the Dakota Formation (Kd) have been involved in landslides that have moved toward the Colorado River. Housing or other development in this area may encounter landslide hazards. The exposed thickness is about 5 m, and the maximum thickness is possibly 20 m.

**Qsw** **Sheetwash deposits (Holocene and late Pleistocene)**—  
*Sheetwash deposits* consist chiefly of light-gray (10YR7/2 and 2.5Y7/2) sandy clay and silty clay. These *sheetwash deposits* form on a very gentle slope with a gradient of about 3 to 4 m/km north of the Colorado River where they were derived by erosion of the Mancos Shale (Km).

The upper 1 m of *sheetwash deposits* is more clay rich than the lower part. Both the upper and lower parts have weak sub-horizontal layering and are slightly calcareous. Unit Qsw commonly has vertical desiccation cracks that are partly filled with clay, which probably washed down from the upper part.

Extensive agricultural, industrial, and housing development has modified, covered, or partly removed the upper part of much of unit Qsw near the northeast corner of the map area. This unit description is based on observations of exposures in an eroded bank of a 4-m-deep agricultural drainage ditch located 3.2 km north and 0.2 km west of the intersection of H Road and 21 Road in the adjacent Fruita 7.5-minute quadrangle.

The presence of desiccation cracks suggests that the map unit contains *expansive clays* that may cause stability problems for roads and buildings. Our examination of construction excavations and records from numerous drill holes on the north side of the Colorado River (Ken Weston, U.S. Bureau of Reclamation, written commun., 1999; Phillips, 1986) indicates that *sheetwash deposits* are 3 to 8 m thick close to the river, but increase to nearly 15 m thick at the northeastern corner of the map area.

**Eolian Deposits**—Eolian deposits consist of silty sand that mantles level to gently sloping surfaces. Locally they include *colluvial* material.

**Qe      Eolian sand (Holocene and late Pleistocene)**—Eolian sand consists of silty, very fine to fine wind-blown sand that blankets upland areas of the Uncompahgre Plateau.

These deposits are commonly massive to weakly bedded and lack eolian sedimentary structures, which may have been obliterated by biotic processes. Deposits at depths greater than 1 m are typically weakly indurated by secondary calcium carbonate that has stage I morphology. Colors generally range from yellowish red (5YR5/8) to reddish yellow (5YR6/6). The sand is derived chiefly from weathering of the poorly cemented Slick Rock Member (Jes) and the “board beds” unit (Jeb) of the Entrada Sandstone and of the Wingate Sandstone (Jwg); lesser amounts are derived from sandstone of the members of the Morrison Formation (Jmt, Jms, and Jmb). Deposits of eolian sand at the base of bedrock exposures locally may contain a significant amount of *colluvial* debris. *Clast* sizes in *colluvial* debris range from granules to boulders. On slopes, eolian sand is subject to redeposition as *sheetwash*. Several *climbing dunes* are banked against bedrock and are as thick as 5 m.

Thin, discontinuous, unmapped deposits of eolian sand mantle other surficial deposits and bedrock on the upland areas of the Uncompahgre Plateau and in the Redlands area near the Colorado River. In the upland areas, deposits of eolian sand locally form subdued, stabilized dunes and blankets of eolian sand. Eolian sand on the uplands is locally stabilized by pinon and juniper trees and in other areas by sage, rabbitbrush, bunch grass, and cheat grass. Structures built on unit Qe commonly sustain minor damage that suggests slight settling, probably chiefly related to *hydrocompaction*. Deposits of eolian silt (loess) were not observed in the map area, although they are locally common further upstream along the Colorado River between Rifle and Glenwood Springs (Shroba, 1994). The thickness of unit Qe may locally be in excess of 8 m.

**Eolian and Colluvial Deposits**—Eolian and *colluvial* deposits include silty sand, which mantles level to gently sloping surfaces, as well as silt, sand, and rock fragments on valley sides and hill slopes, which were mobilized, transported, and deposited by gravity and sheet erosion.


**Qse      Eolian sand and sheetwash deposits (Holocene and late Pleistocene)**—Eolian sand and sheetwash deposits consist chiefly of silty, very fine to fine sand that commonly contains scattered granule- to cobble-size fragments from bedrock units that are exposed upslope, particularly between the mountain front and the Colorado River.

Unit Qse accumulated on gentle to moderate slopes with gradients between about 50 m/km and 100 m/km. Unit Qse is similar to unit Qe, but unit Qse contains more abundant *clasts* derived from local bedrock units. On steeper slopes near upslope bedrock exposures, unit Qse is likely to contain a significant amount of *colluvial clasts*. *Sheetwash* deposits in unit Qse contain discontinuous layers and lenses of poorly sorted *clasts*. Colors of the unit range from yellowish red (5YR5/8) to reddish yellow (5YR6/6). Where wind and *sheetwash* erosion have winnowed out sand and finer sediment, a *lag* of granules, pebbles, and sparse cobbles covers the surface. Unit Qse formed along the front of the Uncompahgre Plateau where it mantles unit Qaso and other units. The thickness of unit Qse may be about 5 m.

**Marsh Deposits**—Marsh deposits include wind- and (or) *sheetwash-deposited* sand and silt that accumulated in a wet environment.

**Qcg      Cienaga deposits (Holocene)**—*Cienaga* deposits consist of silty sand that has chiefly an eolian and (or) *sheetwash* origin; the deposits accumulated in marshy places in the Redlands area.

These marshy areas are fed by seeps, are generally well vegetated, and are upstream from constrictions formed by resistant beds of the Burro Canyon Formation (Kb) and the Dakota Formation (Kd). Unit Qcg largely overlies the relatively impermeable Brushy Basin Member of the Morrison Formation (Jmb). The deposits in unit Qcg are massive, well sorted, structureless, and lack gravelly layers. Locally they may contain some sandy stream alluvium. Colors are commonly light reddish brown (2.5YR6/4) to pale red (10R6/3) at a depth of 10 to 24 cm and red (2.5YR5/6) at a depth of greater than 40 cm. The upper 10 to 24 cm of unit Qcg is moderately indurated and slightly calcareous, whereas sediment below a depth of 40 cm is weakly indurated and very slightly calcareous.



View to the southeast from Artists Point. Cliffs in the distance expose from bottom to top, the Chinle Formation at the base, high cliffs of the Wingate Sandstone, a tree-covered bench of the Kayenta Formation, and small cliffs of the Entrada Sandstone, all capped by tree-covered slopes of the Wankah and Morrison Formations. *Photograph by R.B. Scott, 1998.*

Unit Qcg is soft when saturated with water, and the underlying Brushy Basin Member (Jmb) contains abundant *expansive clay (smectite)*. As a result, unit Qcg has low *bearing capacity* and poses a hazard to roads and structures built on it. In a few low areas where the water table is at or near the surface, evaporation leaves a dissolved load precipitate of alkali crust on unit Qcg. Areas that have this crust are designated on the map by a dotted perimeter and the symbol “a”. This alkali crust is commonly a few centimeters thick, white (5YR8/1), and mostly devoid of vegetation. The thickness of unit Qcg is 1 to 3 m.

### Bedrock Units

To make the bedrock unit descriptions easier for the non-geologist to read, the first few paragraphs of each describes general characteristics, modern-day analogs for depositional environments, and locations of good exposures. The remaining parts of the unit description provide more detailed technical information.

Km

**Mancos Shale (Upper Cretaceous; Turonian and Cenomanian)**—The Mancos Shale is chiefly a medium-dark-gray, dark-gray, brownish-gray, and brownish-black fissile shale that forms gentle slopes, which are broken at wide intervals by thin, brownish-gray sandstone ledges and sparse, white bentonite beds. Only the lowermost Mancos Shale is exposed along the northern boundary of the map area near the Colorado River. This lowermost Mancos was deposited in a shallow marine subtidal setting, similar to the modern Texas Gulf Coast.

Exposures of the Mancos Shale can be seen on the south side of the Colorado River, southwest of the Redlands Parkway bridge that has been constructed at the east boundary of the map area. This bridge is not shown on the topographic base map available for this quadrangle but is shown on modern street maps.

In addition to the dominant dark fissile shale that weathers light gray, the lowermost Mancos contains sparse beds of thinly laminated, fissile-weathering, partly *bioturbated*, calcareous and

carbonaceous siltstone and sandy siltstone, which contain sparse interbeds of sandstone. The unit is well defined by Cobban and others (1994). The sandstone is very fine to fine grained, well sorted, and calcareous and has beds that are typically less than 10 cm thick. The beds commonly exhibit *ripple lamination*, including both *oscillation* and *combined flow ripples*, and locally display hummocky *cross-lamination*. Several light-gray to yellowish-gray thin stringers and beds of volcanic ash have been altered to nearly pure, highly *expansive* bentonite and are as much as 20 cm thick.

The lowermost Mancos is fossiliferous, but pelecypods and cephalopods are generally found only in recent roadcuts and excavations because rapid weathering breaks up fossils. Marine trace fossil burrows are common. The base of the Mancos was mapped at the base of the nearly continuous dark fissile shale above the uppermost prominent set of thin sandstone beds and carbonaceous interbeds of the Dakota Formation (Kd). The map unit reaches a thickness in excess of 1,370 m in western Colorado; however, less than 20 m of the lowermost Mancos is exposed south of the Colorado River in the map area (Cole and Moore, 1994; Cole and others, 1999).

#### Kd

**Dakota Formation (Upper and Lower? Cretaceous; Cenomanian and Albian?)**—Sandstone and conglomerate of the Dakota Formation form prominent and resistant ledges and ridges, whereas mudstone and interbedded sandstone and shale of the Dakota generally form slopes. The Dakota Formation caps Black Ridge near the central western boundary of the map area and forms a series of low hogbacks in the Redlands area south of the Colorado River. Locally in the Redlands area, dinosaur tracks are preserved in the sandstone beds.

The sandstone and mudstone of the upper parts of the Dakota were deposited in estuaries, tidal channels, distributary channels, bays, lagoons, strandlines, and barrier islands, an environment similar to the Texas Gulf Coast today. *Bioturbation* is common throughout the map unit and includes plant roots and burrows. Burrows in the lower Dakota are terrestrial in origin, whereas those in the upper Dakota are marginal-marine. The lowest part of the Dakota, which is dominated by channel-form sandstone and conglomerate bodies, was deposited by slightly to moderately sinuous streams flowing across broad, well-defined flood plains that were densely vegetated and contained numerous abandoned channels that formed oxbow lakes. The carbonaceous mudstone and associated coal were deposited in freshwater swamp and marsh environments.

Good exposures of the Dakota Formation are not easily reached on public land in the map area. However, a trail up the south side of Riggs Hill leads from a parking area on South Broadway to the top of the hill, which is capped by the Dakota.

The unit consists of about 20 to 50% sandstone, 5 to 20% conglomerate, 40 to 60% mudstone, and less than 5% impure coal. There are four parts to the map unit: from top to bottom these are the interbedded sandstone and shale part, a sandstone part, a mudstone part, and a conglomeratic part. The interbedded sandstone and shale part is dominantly shale or shaley mudstone, thin sandstone beds, and stringers of coal. Shale in the uppermost part of the Dakota is interbedded with channel-form sandstone, is usually much less carbonaceous than elsewhere in the unit, and consists of brownish-gray to greenish-gray, thinly laminated, fissile-weathering, slightly carbonaceous, slightly calcareous, siltstone and clayey siltstone. This interbedded sandstone and shale part is *bioturbated* by roots and indistinct burrows. This upper part is transitional with the overlying Mancos Shale (Km).

The sandstone part contains predominately sandstone with subordinate conglomerate, stringers of coal, and minor mudstone. Sandstone is commonly light gray to pale yellowish orange, white, pinkish gray or very pale orange, very fine to fine grained, moderately to poorly sorted, *bioturbated*, locally argillaceous, and slightly calcareous to non-calcareous. The sandstone part is thickly bedded to very thinly bedded. Thicker sandstone bodies (1 to 5 m) have a channel-form geometry with associated *scour surfaces* and *lag gravels*, which include blebs of mudstone, chert, quartz, and rock fragments. Stratification consists of small- to medium-scale trough and *tabular-tangential cross-stratification*, *symmetric* and *asymmetric ripple lamination*, *horizontal lamination*, and contorted bedding.

The mudstone part is chiefly mudstone and subordinate impure coal. Mudstone consists of brownish-gray to grayish-black, medium- to thinly laminated, platy to fissile weathering, carbonaceous to very carbonaceous, *bioturbated*, silty claystone and clayey siltstone containing thin beds and lenses of very fine to fine-grained, quartz-cemented sandstone and white, altered volcanic ash. Fragments of plant fossils are very common. Impure coal seams and stringers, ranging in thickness from 5 to 40 cm, are found within the carbonaceous mudstone. The ash content in the coal is estimated at 15 to 35 percent.

Although the conglomeratic part is capped by sandstone, conglomerate predominates. The conglomerate part contains clasts that range in size from fine sand to pebbles and is typically light gray to white or pinkish gray, poor to moderately sorted, slightly argillaceous, slightly calcareous to non-calcareous, and friable. Also the conglomerate part has medium to very thick beds, blocky and slabby weathering, and contains minor sandstone interbeds. *Clasts* are commonly graded and consist of mud chips, chert, quartz, and other rock fragments. Stratification in conglomerate is generally indistinct, consisting of poorly defined low-angle (<15°) *scour surfaces*.

The map unit may rest *disconformably* on the underlying Burro Canyon Formation. The base of the Dakota Formation was arbitrarily defined during mapping as the first carbonaceous mudstone above the Burro Canyon Formation (Kb). The first thick sandstone interval above the carbonaceous mudstone of the Dakota Formation commonly has been bleached white in contrast to light yellow and orange elsewhere. The thickness of the map unit exposed at Black Ridge is about 31 m where the uppermost part of the unit has been removed by erosion, and the total unit thickness is estimated to be about 45 to 50 m (Cole and others, 1999).

**Kb Burro Canyon Formation (Lower Cretaceous; Albian and Aptian)**—In most localities, the upper part of the Burro Canyon Formation is dominated by mudstone and forms slopes, whereas the lower third to two-thirds of the unit is dominated by sandstone and forms cliffs.

The thick mudstone sequence at the top of the unit represents flood plain and lacustrine deposition. The sandy lower part of the Burro Canyon was deposited by *braided streams* on narrow flood plains. Modern rivers draining the Rocky Mountains, such as the parts of the South Platte and Rio Grande Rivers that are in the plains, are possible analogs for the depositional systems that deposited the Burro Canyon.

The Burro Canyon Formation can most readily be reached by following the same trail as that used to reach the Dakota Formation. Go part way up the trail on the south side of Riggs Hill from South Broadway to the first exposures of coarse conglomerate, which mark the base of the Burro Canyon.

The map unit consists of about 40 to 80% mudstone, 20 to 60% sandstone, and 0 to 15% conglomerate. Mudstone is typically medium to thinly laminated (platy to fissile weathering), slightly bentonitic to non-bentonitic, slightly

calcareous, and commonly *bioturbated* by roots and some burrows. Mudstone consists of pale-red, pale-olive to yellowish-green siltstone, clayey siltstone, and silty claystone and ranges from thin interbeds within channel-form sandstone bodies to discrete sequences more than 10 m thick. Thin (less than 1 m thick) *paleosol* horizons that are composed of white to light-gray, earthy carbonate nodules may be interbedded with mudstone in the upper Burro Canyon.

Sandstone intervals are laterally discontinuous. Sandstone forms channel-shaped bodies and is typically white to yellowish gray, thick bedded to thinly laminated, blocky to *flaggy* weathering, fine to medium grained, moderately sorted, and quartz-cemented. Locally the sandstone includes large amounts of petrified wood. Sandstone sequences contain numerous *laterally and vertically amalgamated scour surfaces* accentuated by thin *lag gravels*, which include green mudstone *clasts*, chert, quartz, petrified wood, and dinosaur bone. Medium-scale *trough* and *tabular-planar cross-stratification* is common in sandstone bodies; contorted bedding and bioturbation, including roots and elongate vertical burrows, are also present.

Locally, conglomerate beds are as much as 3 m thick near the base of the map unit; conglomerate is commonly yellowish gray, moderately sorted, well rounded, massive to poorly bedded, channel form, and discontinuous laterally. The conglomerate *clasts* consist mostly of chert and quartz pebbles but include minor petrified wood and dinosaur bone.

The base of the map unit is arbitrarily defined as the lowest thick sandstone or conglomerate bed above the mudstone of the Brushy Basin Member of the Morrison Formation (Jmb) (Aubrey, 1998). The thickness of the map unit is 29.3 m at Black Ridge (Cole and others, 1999).

**Morrison Formation (Upper Jurassic)**—The Morrison Formation consists of three members: a slope-forming upper member, the Brushy Basin Member; a cliff-forming middle member, the Salt Wash Member; and a slope-forming lower member, the Tidwell Member. The Morrison Formation is about 160 m thick based on the total measured thickness of the three members (Cole and others, 1999). However, individual members do not have laterally consistent thicknesses; therefore, the total thickness of the Morrison may be significantly different from place to place.



Typical exposures of mudstone of the Brushy Basin Member of the Morrison Formation in the Redlands. *Photograph by R.B. Scott, 1998.*

**Jmb**      **Brushy Basin Member (Tithonian and Kimmeridian)**—The multicolored mudstone of the Brushy Basin Member forms gentle rounded slopes. The Brushy Basin Member was deposited in a mud flat to saline lacustrine setting (Turner and Fishman, 1991) that was locally invaded by highly sinuous fluvial channels. Volcanic basins in New Zealand are possible modern-day analogs.

Like the Dakota and Burro Canyon Formations, the Brushy Basin Member of the Morrison Formation can be reached by following the trail from the parking area off South Broadway up Riggs Hill. The mudstone is partly covered by blocks of sandstone and conglomerate that tumbled from exposures of the Dakota and Burro Canyon.

The unit consists of 85 to 95% mudstone, 5 to 15% sandstone, and a trace of limestone. About 75% of the mudstone consists of bentonitic, variegated grayish-yellow-green, greenish-gray, yellowish-gray, brownish-gray, grayish-red, greenish-yellow, and grayish-orange-pink, medium to thinly laminated (platy to fissile weathering), mottled, *bioturbated* (?), earthy, slightly

calcareous, clay-rich siltstone, mudstone, and silty mudstone. The silty mudstone contains thin interbeds of very fine grained, well-sorted, *bioturbated* sandstone and gray, nodular, finely crystalline limestone (possible soil nodules?). Barite nodules and dinosaur bones are present. Bentonitic mudstone expands and dries to form a popcorn-like weathered surface. Bentonite, a rock consisting of swelling, mixed-layer, *smectitic clay* minerals, is derived from *diagenetic alteration* of volcanic ash.

The remaining 25% of the mudstone that is not conspicuously bentonitic consists of variegated pale-olive, reddish-brown, greenish-gray, grayish-yellow-green, yellowish-gray, yellowish-orange, and grayish-red, thickly to thinly laminated (*flaggy* to *fissile* weathering), partly *bioturbated*, slightly calcareous to non-calcareous siltstone, sandy siltstone, and silty mudstone. The silty mudstone also contains thin interbeds of very fine grained sandstone. Sandstone is most common in the lowermost and uppermost Brushy Basin Member and typically forms channels and ranges

in thickness from less than 1 m to more than 4 m. Sandstone is typically greenish yellow to dusky yellow green and greenish gray, very fine to coarse grained, poor to moderately sorted, slightly calcareous to non-calcareous, and locally *bioturbated* by burrows and roots and contorted by soft-sediment deformation. Sandstone has thickly laminated to medium bedding and slabby to *flaggy* weathering. The thicker channel sequences commonly have small-scale *trough cross-stratification* and *scour surfaces* accentuated by basal layers of pebble-size mudchips and granules of chert and quartz, whereas thinner sandstone beds are commonly *bioturbated*.

Because of its susceptibility to *mass wasting*, particularly landsliding, the Brushy Basin Member is one of the most poorly exposed units in the map area. The Brushy Basin Member underlies the K-1 unconformity (Peterson, 1994; Peterson and Turner, 1998) below the Burro Canyon Formation and rests *disconformably* above the Salt Wash Member (unnamed unconformity; R.G. Young, oral commun., Grand Junction, Colo., 1999). The Brushy Basin Member is about 95 m thick at exposures about 1 km east of the east boundary of the map area near Little Park Road in the adjacent Grand Junction 7.5-minute quadrangle (Cole and others, 1999).

#### Jms

**Salt Wash Member (Kimmeridgian)**—The Salt Wash Member is a sandstone-rich cliff-forming unit sandwiched between the mudstone-rich, slope-forming Brushy Basin and Tidwell Members of the Morrison Formation. The Salt Wash Member was deposited in a fluvial setting that included associated flood plains and shallow ponds. The architecture of the channel-form sandstone bodies suggests that the fluvial channels were relatively thin (1 to 7 m), narrow (5 to 30 m), and moderately sinuous. An analog for this depositional setting exists along the modern-day Texas coast where rivers empty into the Gulf of Mexico.

Some of the best exposures of the Salt Wash Member of the Morrison Formation can easily be seen in road cuts on Rim Rock Drive south of Highland View Overlook.

The unit consists of 30 to 80% sandstone, 20 to 70% mudstone, and traces of limestone; the unit is well defined by Peterson (1994). Sandstone typically is fine to medium grained, moderately sorted, slightly calcareous, and friable. Sandstone forms very pale orange, yellowish-gray and light-gray, channel-shaped bodies that range from 1 to 5 m thick, is very thinly to very thickly bedded, and has slabby to blocky weathering. Thicker sand bodies commonly exhibit small- to large-scale *trough*, *tabular-tangential*,

and *sigmoidal cross-bedding*, as well as *scour surfaces* accentuated by granule- to pebble-size *lag gravels* composed of red and green mudstone, quartz, and chert. Elongate, narrow burrows are common near the tops of the thicker sand bodies.

Mudstone intervals consist of pale-brown to greenish-yellow, grayish-red, and yellowish-gray, silty claystone, siltstone, sandy siltstone, and mudstone. Mudstone occurs as 0.1- to 1-m-thick interbeds between sandstone channels, but can also exist as sequences as much as 15 m thick where sandstone channels are poorly developed. These mudstone bodies are commonly thickly to thinly laminated, *flaggy* to fissile weathering, slightly calcareous, slightly bentonitic, and commonly *bioturbated* by insect burrows and plant roots. Well-cemented, mottled mudstone intervals weather to form nodules. Thicker mudstone sequences commonly have thin interbeds and lenses of very fine to fine-grained, well-sorted sandstone.

Minor limestone beds are very similar to the limestone beds in the underlying Tidwell Member, are usually light gray to light olive gray, slightly sandy to silty, mottled, *bioturbated*, finely crystalline, slightly fossiliferous, containing ostracodes and *charophytes*, and have the mud-matrix-supported fabrics of carbonate mudstone and *wackestone*. These beds are present as scattered discontinuous beds less than 0.3 m thick and as beds of nodules within mudstone.

The Salt Wash-Brushy Basin contact is commonly obscured because of *mass wasting*. The base of the Salt Wash Member was defined during mapping as the top of the uppermost major limestone bed of the Tidwell Member (Jmt) below the thick sandstone beds of the Salt Wash Member. The Salt Wash Member exhibits considerable lateral variation in thickness and rock type within the quadrangle; on the east side of the map area, the member becomes only a few meters thick and may be locally absent in the adjacent Grand Junction quadrangle. The thickness of the member is 31 m at Artists Point on Rim Rock Drive (Cole and others, 1999).

#### Jmt

**Tidwell Member (Kimmeridgian and Oxfordian)**—The mudstone-rich Tidwell Member forms slopes that are broken by relatively thin ledges of sandstone and limestone; with rare exception, this is the only limestone in the map area. Within the Tidwell Member, the character and thickness of mudstone, sandstone, and limestone change significantly laterally.

The *heterolithic* nature of the Tidwell indicates that it was deposited in several environments. The green mudstone sequences and all of the limestone were probably deposited in a fresh- to brackish-water lacustrine setting. Tabular

sandstone bodies characterized by horizontal stratification and *oscillation ripples* were deposited on beaches in lake-margin settings, whereas the channel-form sandstone bodies with *cross-stratification* were deposited by fluvial and distributary channel systems.


Excellent exposures of the Tidwell Member of the Morrison Formation can be seen in road cuts along Rim Rock Drive between Artists Point and Highland View Overlook.

The unit consists of laterally variable proportions of interbedded 50 to 70% mudstone, 10 to 40% sandstone, and 5 to 20% limestone; the unit is well defined by Peterson (1994). Mudstone typically consists of grayish-red to grayish-yellow-green sequences of mudstone, sandy siltstone, silty claystone, and siltstone, ranging in thickness from a few centimeters to more than 4 m. These sequences are commonly very thin bedded to thinly laminated, slabby to fissile weathering, mottled, *bioturbated* by roots and burrows,

and slightly calcareous to very calcareous. Calcareous mudstone intervals have a nodular weathering aspect.

Sandstone is light gray to light greenish gray, fine to medium grained, moderately to well sorted, calcareous, and locally *bioturbated* by roots and burrows. The sandstone has slabby to blocky weathering. Sedimentary structures in sandstone include *horizontal lamination*; discontinuous, wispy, bedding-parallel *lamination*; wavy, bedding-parallel, hummocky *lamination*; small- to medium-scale *trough* and *tabular-tangential cross-stratification*; and *asymmetric current* and *symmetric wave ripple stratification*. Sandstone beds range in thickness from less than 1 cm to about 2 m and exhibit both tabular and channel-form cross-sectional geometry.

The lowermost sandstone package that defines the base of the Tidwell is informally called “A” bed, rests on the J-5 unconformity (Pipiringos and O’Sullivan, 1978), and is continuous throughout



Above the cliffs of the Entrada Sandstone at Artists Point are the bare slopes of the mudstone of the Wanakah Formation overlain by tree-dotted slopes of the Tidwell Member of the Morrison Formation. *Photograph by W.C. Hood, 1998.*

the quadrangle. The “A” bed, which is approximately 1 m thick, has a basal *lag* composed of oversize (medium-grained to granule) chert and lithic grains; similar granule lenses also occur within this bed.

Between 2 and 7 limestone beds are present and are most abundant in the upper half of the Tidwell. Limestone is typically light gray to light olive gray, dense, hard, slightly sandy or silty, very fine to finely crystalline, and resistant to weathering, forming slabby to blocky exposures. Most limestone is mottled and *bioturbated* by burrows, although stromatolitic *lamination* produced by algal (cyanobacteria?) growth is locally present. Oncolites (algal biscuits) are also found. Fossils are sparse and consist of ostracodes, *charophytes*, and very small gastropods. Petrographically, the Tidwell limestone is classified as carbonaceous mudstone, and *packstone* (Dunham, 1962). Limestone beds range in thickness from several centimeters to about 1 m.

The Tidwell rests on the Wanakah Formation (Jw), which is below the J-5 unconformity (Peterson, 1994), whereas the upper contact with the overlying Salt Wash Member of the Morrison Formation is transitional. Because the map unit does not contain thin, parallel-bedded *gypsiferous* strata typical of the Summerville Formation south and west of the map area (Anderson and Lucas, 1998), the name “Tidwell Member of the Morrison Formation” is retained locally. The Tidwell Member is about 38 m thick at Artists Point along Rim Rock Drive (Cole and others, 1999).

#### Jeb

#### **Jw Wanakah Formation (Middle Jurassic; Callovian)—**

In Colorado National Monument, the mudstone-rich, slope-forming Wanakah is easily recognized by its distinctive green-over-red colors and by a noticeable reduction of vegetation. The depositional setting for the Wanakah is nonmarine mudflat and (or) shallow lacustrine environment.

The entire Wanakah Formation is exposed at Artists Point on Rim Rock Drive.

The Wanakah Formation consists of 80 to 90% interstratified mudstone, 5 to 15% sandstone and silty sandstone, 0 to 5% impure limestone, and traces of volcanic ash and gypsum. Mudstone consists of reddish-brown, grayish-red-purple, yellowish-brown, pale-olive, and greenish-gray siltstone, sandy siltstone, and mudstone. The greenish-gray mudstone is dominant in the upper half of the unit. Mudstone intervals are medium to thinly laminated and are platy, fissile and nodular weathering, mottled, *bioturbated* by burrows and roots, slightly calcareous, and non-bentonitic.

Sandstone, which occurs as very thin to thin, slabby weathering interbeds and discontinuous

lenses in mudstone, is typically light brown to light gray, very fine to fine grained, moderately to well sorted, silty, *bioturbated*, and calcareous. The sandstone displays discontinuous *horizontal lamination* and *asymmetric ripple lamination*.

Limestone forms gray to grayish-red and light-gray, sandy to silty, *bioturbated*, discontinuous nodules that are usually less than 5 cm in diameter.

Radiometric analysis shows a large positive gamma-ray anomaly approximately 5 m above the base that is associated with several light-grayish-green, volcanic ash laminae less than 1 cm thick (Cole and others, 1999). The Wanakah is truncated by the J-5 unconformity (Pipiringos and O’Sullivan, 1978), which shows minimal erosional relief throughout the map area. Beneath the unconformity, the upper several meters of the Wanakah have numerous well-developed root traces. The base of the Wanakah Formation is defined at the base of the red mudstone that rests on the very pale orange to very light gray sandstone beds of the upper informal “board beds” unit of the Entrada Sandstone. The map unit is 9.4 m thick at Artists Point on Rim Rock Drive (Cole and others, 1999).

#### **Entrada Sandstone (Middle Jurassic; Callovian)—**

The Entrada Sandstone consists of two parts, the prominent white cap of the upper unit, informally called the “board beds,” and the pale-orange, ribbon-like lower Slick Rock Member.

**“board beds” unit**—Interbedded resistant sandstone and less resistant mudstone form slabby exposures that resemble a stack of boards, giving the “board beds” unit its informal name. This unit was deposited in a wet sand-flat environment in a coastal setting. The western coast of Baja California, Mexico, at Guerrero Negro, may be a possible modern-day analog (Fryberger and others, 1990).

Good road cut exposures of the “board beds” unit of the Entrada Sandstone are found along Rim Rock Drive between Artists Point and Coke Ovens Overlook.

The “board beds” unit consists of 60 to 70% interbedded sandstone and 30 to 40% mudstone. Sandstone is very pale orange to very light gray, white, and pinkish gray, very fine to fine grained, moderately to well sorted, intensely mottled by *bioturbation*, and calcareous. The map unit is thin to thick bedded and has slabby to blocky weathering. Stratification is rare and consists of discontinuous, wispy *horizontal lamination* and small-scale sets of *tabular-tangential cross-lamination* of grain flow and wind ripple structures. Southwest of No Thoroughfare Canyon, sandstone beds locally contain gray petroleum residue (dead oil).

**Jes**

Mudstone is reddish brown to grayish red, thickly to thinly laminated, flaggy to fissile weathering and contains siltstone and sandy siltstone, which are typically *bioturbated*.

The base of the unit is defined as the top of the orange-pink, *cross-bedded* Slick Rock Member (Jes) of the Entrada. The thickness of the “board beds” unit is about 13 m along Upper Monument Canyon Trail (Cole and others, 1999).

**Slick Rock Member**—The Slick Rock Member of the Entrada Sandstone forms a conspicuous pale-orange, ribbon-like cliff or rounded bench that is almost totally free of vegetation below the white cap of the “board beds” unit.

The Slick Rock Member was deposited in a coastal eolian setting. Dunes were probably not large and had maximum heights of between 10 and 20 m. Sand transport was generally toward the south (Kocurek and Dott, 1983, Peterson, 1988). Wet sand flats, which were related to high water tables and interdune areas, were commonly associated with dunes. An analog for the Slick Rock eolian system can be found in Baja California, Mexico, at Guerrero Negro (Fryberger and others, 1990).

One of the best places to observe the Slick Rock Member of the Entrada Sandstone is the isolated hill by the north side of the roadway about 400 meters west of the Red Canyon Overlook on the north side of Rim Rock Drive.

The map unit consists almost entirely (99%) of *cross-bedded* sandstone. The sandstone is orange pink to pale reddish orange, very fine to fine grained, moderately to well sorted, commonly mottled by *bioturbation*, and calcareous. The map unit is very thinly to very thickly bedded, and has slabby to blocky weathering. Cementation is weak. Stratification, when present, consists of small- to large-scale sets of *trough*, *tabular-tangential*, *tabular-planar*, and *wedge-planar cross-stratification*, as well as discontinuous, wispy *horizontal lamination* structures. Cross-strata sets are mainly composed of *wind-ripple lamination*; *grain-flow lamination* is rare. Bioturbation increases upward and is commonly associated with first-order *bounding surfaces*.

This member rests on the reddish-orange, thinly bedded sandstone of the Kayenta Formation. The thickness of the Slick Rock Member is 34 m along Upper Monument Canyon Trail (Cole and others, 1999).

**Jwe**

**Wanakah Formation and Entrada Sandstone, undivided (Middle Jurassic)**—These undivided units are shown in cross sections only.

**Jk**

**Kayenta Formation (Lower Jurassic; Pliensbachian)**—The Kayenta Formation commonly forms resistant ledges above the cliff-forming Wingate Sandstone (Jwg) and also forms cliffs in several areas. Sandstone is present throughout the Kayenta, whereas conglomerate and mudstone are found mainly in the upper half.

The formation was deposited by high-energy *braided-river systems*. Sediment transport directions were to the west-northwest. Modern rivers draining the Rocky Mountains, such as the parts of the South Platte and Rio Grande Rivers that are in the plains, are good analogs for the depositional systems of the Kayenta Formation.

The ledge formed by the Kayenta Formation is followed by Rim Rock Drive in many areas; the Kayenta is particularly well exposed in road cuts south of the Monument Headquarters and above the tunnels uphill from the West Entrance of the Monument.

The Kayenta consists of 80 to 90% sandstone, 0 to 10% conglomerate, and 0 to 10% mudstone; the unit is well defined by Peterson (1994). Sandstone is typically reddish orange, grayish orange pink, light greenish gray, or white, fine to medium grained, moderately to well sorted, and cemented by a mixture of carbonate and quartz. The sandstone is thin to very thinly bedded and has slabby bedding. Sandstone sequences in the Kayenta contain numerous amalgamated *scour surfaces* that commonly have *lag gravels* consisting of mudstone *clasts*.

Conglomerate is found in channel-form sequences composed of granule- to cobble-size *clasts* of reddish-orange mudstone in a matrix of medium-grained, moderately sorted, light-greenish-gray sandstone; *clasts* are typically graded.

Mudstone consists of reddish-brown to grayish-red, thinly laminated, fissile-weathering, moderately to well-sorted siltstone and sandy siltstone; mudstone may be locally *bioturbated*.

Stratification is well developed in the Kayenta Formation and consists of small- to medium-scale sets of low-angle, *even-parallel lamination*, *tabular-tangential cross-stratification*, and *trough cross-stratification*; *streaming* and *parting lineations* are also common. The base of the Kayenta Formation is marked by the sharp break from small- to medium-scale *cross-beds* of siliceously cemented sandstone and mudstone to the more massive, large-scale sets of *cross-stratification* of the sandstone of the Wingate Sandstone. The Kayenta Formation is about 23.5 m thick along Upper Monument Canyon Trail (Cole and others, 1999).



View to the east in Fruita Canyon. The strata in the *monoclinal fold* dip to the northeast and show the Proterozoic basement rocks overlain by the Chinle Formation and the Wingate Sandstone. *Photograph by R.B. Scott, 1998.*

**Jwek Wanakah Formation and Entrada Sandstone (Middle Jurassic) and Kayenta Formation (Lower Jurassic), undivided**—At localities along the mountain front where these steeply *dipping*, thin map units are exposed, the units are undivided.

**Jwg Wingate Sandstone (Lower Jurassic; Pliensbachian? and Hettangian)**—The Wingate Sandstone typically forms 100-m-high, reddish-orange cliffs and monuments that give the Colorado National Monument its most spectacular scenery.

The map unit was deposited in an eolian setting that was on the northeast margin of a large dune area, or erg, that occupied most of the Four Corners area in Late Triassic and Early Jurassic time (Peterson, 1994). During periods of aridity, Wingate dunes were probably 30 to 45 m high, and they migrated towards the south-southeast. Smaller dune complexes, wet sand flats signifying high water tables, and interdune areas were most prevalent during more humid climatic conditions. The largest dune deposits are found in the upper half of the Wingate. An analog for the Wingate dune complex can be found in the modern-day Sahara Desert of North Africa.

Good road-cut exposures of the Wingate Sandstone can be reached from the West Entrance of the Monument between the Chinle Formation (Tc) and the tunnels.

The Wingate consists of about 95% sandstone and about 5% mudstone; the unit is well defined by Peterson (1994). Sandstone is typically orange pink to reddish orange, very fine to fine grained, moderately to well sorted, calcareous, well stratified, and partly mottled and *bioturbated* by roots and burrows. The map unit is thinly to very thickly bedded and has slabby to blocky weathering. Stratification, when present, consists of small- to very large scale sets of *even-parallel horizontal lamination*, discontinuous *even-parallel lamination*, *tabular-tangential cross-stratification*, *tabular-planar cross-stratification*, *wedge-planar cross-stratification*, and *trough cross-stratification*. *Wind-ripple lamination* dominates the horizontal stratification sets, whereas *wind-ripple lamination* and *grain-flow lamination* characterize most large-scale sets of *cross-stratification*.

Mudstone intervals are dominated by siltstone and sandy siltstone, which are typically

light brown to light reddish brown and reddish brown, thickly to thinly laminated, flaggy to fissile weathering, and generally mottled and *bioturbated* by roots(?). Stratification in mudstone is sparse, usually consisting of discontinuous *horizontal lamination*, *wispy lamination*, and rare *current-ripple lamination*.

In the map area, at least nine first-order *bounding surfaces* with associated mudstone interdune deposits are found in the Wingate, suggesting that it was deposited by a series of dune complexes, or draas, that fluctuated in size and shape in accordance with climatic variations. The thickness of the map unit is 100 m along Upper Monument Canyon Trail (Cole and others, 1999).

Rc

**Chinle Formation (Upper Triassic; Norian and Carnian)**—The Chinle Formation forms distinctive red slopes below the towering cliffs of Wingate Sandstone (Jwg) and above the great angular unconformity on dark Proterozoic basement rocks. Excellent exposures of the Chinle can be seen in the road cut in Fruita Canyon.

Sedimentologic characteristics of the Chinle suggest deposition in a densely vegetated flood plain or mud flat, containing localized shallow ponds and small, shallow, sinuous streams. Water-table fluctuations were common during deposition. Similar environments exist today in subtropical to tropical areas of South America and Africa.

The Chinle consists of interbedded 80 to 90% mudstone, 0 to 10% sandstone, 0 to 5% sandy conglomerate, and 0 to 5% limestone; the unit is well defined by Dubiel (1994). Mudstone consists of reddish-brown to reddish-orange and grayish-purple, thickly to thinly laminated, flaggy to fissile and nodular-weathering, calcareous to very calcareous, mottled, *bioturbated*, silty claystone, clayey siltstone, and sandy siltstone. Carbonate nodules (*rhizocreations*?), root traces, and burrows (crayfish?) are common.

Sandstone occurs as small, channel-form bodies that are reddish orange to grayish red-purple, thin to medium bedded, slabby weathering, fine to very coarse grained, and very poorly sorted. Sandstone commonly contains conglomeratic mud-chips. Sedimentary structures are poorly developed and consist of *cross-stratification*, *ripple-stratification*, and *horizontal lamination*.

Conglomerate also forms channel-shaped bodies that are reddish orange to grayish red-purple, medium to thick bedded, slabby to blocky weathering, calcareous, very poorly sorted, and sandy to silty. *Clasts* are *normally graded*, consisting of pebble- to cobble-size mudstone and reworked carbonate nodules.

YI

Limestone is reddish orange, very thin to medium bedded, slabby weathering, sandy to silty, and typically mottled and *bioturbated*. Some limestone beds have 1- to 5-cm-thick stromatolitic (algal?) structures.

The map unit is about 27 m thick along Upper Monument Canyon Trail (Cole and others, 1999).

**Lamprophyre dikes (Middle Proterozoic)**—*Lamprophyre* dikes are slightly altered, thin, dark-greenish-gray to greenish-black dikes.

One of these dikes can be visited by following No Thoroughfare Canyon trail upstream from Devils Kitchen about 500 m to a major drainage junction. Follow the left drainage about 250 m to the locality where the dark dike crosses the drainage.

The rock contains phenocrysts of biotite, hornblende, and pyroxene in a fine-grained *matrix*. Dikes are 2 to 3 m thick and are present in the northeastern part of No Thoroughfare Canyon and at the junction of Red and Columbus Canyons. The dikes are subparallel and *dip* to the southeast at 50 to 73°. The *lamprophyre* dike in No Thoroughfare Canyon was dated at about 1,400 Ma by the  $^{40}\text{Ar}/^{39}\text{Ar}$  method (M.J. Kunk, written commun., U.S. Geological Survey, 2000).

Xi

**Meta-igneous gneiss (Early Proterozoic)**—Meta-igneous gneiss is metamorphosed granite that contains minor xenoliths of host rock and is exposed chiefly in the eastern part of Ute Canyon. Meta-igneous bodies in and near Ute, Red, Columbus, and Gold Star Canyons are probably part of a single pluton, here called the Ute Canyon *stock*.

The best access to the meta-igneous gneiss is found by following the lower trail head of Liberty Cap trail to the junction with Ute Canyon trail (not shown on map) below Liberty Cap. From there, non-weathered exposures can be found by following Ute Canyon trail about 400 m upstream to stream crossings on the gneiss.

The meta-igneous gneiss is pinkish gray to medium gray, coarse grained, contains very coarse grained relict igneous phenocrysts of *subhedral* to *euhedral* alkali feldspar, and has a penetrative, but weakly to moderately developed, *schistosity* that is defined by aligned biotite. The xenoliths, which locally form 5 to 10% of the rock, consist of the dark-colored part of the *migmatitic* meta-sedimentary host rock and range from 0.1 to 3 m wide. The meta-igneous gneiss contains 20 to 40% *anhedral* quartz, 20 to 40% *subhedral* biotite, 10 to 30% *euhedral*, twinned, relict phenocrysts of alkali feldspar 1 to 4 cm long, and 10 to 20% *subhedral* plagioclase. During alteration and weathering, quartz grains were coated by a red hematitic stain and some of the biotite was altered to chlorite.

The age of emplacement of the igneous body is estimated to be  $1,721 \pm 14$  Ma based on the preliminary *discordant U/Pb* zircon date (sample Ute 1, D.M. Unruh, unpub. written commun., U.S. Geological Survey, 1999) of the meta-igneous gneiss collected from the pluton in Ute Canyon. Nearly vertical contacts with the surrounding *migmatitic* meta-sedimentary gneiss (Xm) country rock are poorly exposed but appear to be *discordant* with structures in that country rock. The lower contact of the meta-igneous gneiss is not exposed. The upper part of the meta-igneous body has been removed by erosion and is overlain by the Chinle Formation (Fc).

**Xm** *Migmatitic* meta-sedimentary rocks (Early Proterozoic)—The *migmatitic* meta-sedimentary rocks consist of a complexly folded mixture of dark schist and light migmatitic pegmatite found in the bottoms of most of the canyons at the Monument.

Good exposures of the migmatitic meta-sedimentary rocks can be reached by trails (not

shown on map) into either the North Entrance or the East Entrance to Monument Canyon. The freshest exposures are in the deepest drainages off the trails.

The sedimentary rock *protolith* probably included graywacke, arkose, *lithic arkose*, *subarkose*, and some shale. Meta-sedimentary rocks include 65% schist, 35% *migmatitic* pegmatite, and sparse *boudins* of *calc-silicate* rock. The map unit also includes a minor amount of post-metamorphic, tourmaline-bearing, pegmatite dikes.

Medium- to high-grade amphibolite metamorphism partially melted the original graywacke to arkosic sedimentary rocks, producing (1) unmelted masses of higher-melting-temperature ferromagnesian minerals (melanosome) that formed the schist and (2) a melt that crystallized to form the lower-temperature-melting quartz- and feldspar-bearing pegmatite (leucosome).

The schist is a mixture of streaky light-gray to dark-gray and pinkish-gray micaceous rock that



Good exposures of the *migmatitic* meta-sedimentary rocks are seen at the base of the Chinle-Wingate cliffs. View to the northwest at the right-angle bend in Ute Canyon. *Photograph by R.B. Scott, 1998.*

## Selected Stratigraphic Topics

contains 10 to 100% biotite, 0 to 85% quartz, 0 to 40% plagioclase, 0 to 25% alkali feldspar, 0 to 10% muscovite, 0 to 10% muscovite pseudomorphs after sillimanite, and 0 to 10% garnet. The schist has been deformed during metamorphism to create tabular, discontinuous zones of dark, well-foliated, fine- to medium-grained rock that typically has pod-shaped masses and tight elliptical to isoclinal folds. Some of the schist contains *porphyroblasts* of muscovite, garnet, and (or) muscovite pseudomorphs after sillimanite(?), which may contain traces of sillimanite.

The *calc-silicate* rock is greenish white to greenish brown and fine grained. It consists of pods, or *boudins*, that contain 40 to 70% epidote, 20 to 50% quartz, and 1 to 10% garnet.

*Migmatitic* pegmatites are pinkish gray to pinkish white, are coarse grained (1-3 cm), and contain 20 to 80% alkali feldspar, 15 to 80% quartz, 0 to 10% biotite, 0 to 2% garnet, and 0 to 3% muscovite. Deformation during metamorphism has created pinch-and-swell, *ptygmatic*, commonly symmetrical, elliptical, and tight to isoclinal folds in the pegmatitic layers that are commonly a few millimeters to 10 cm wide; however, some sheet-like dikes are as much as 3 m wide.

The post-metamorphic pegmatite dikes are distinctly different from *migmatitic* pegmatites in that the post-metamorphic pegmatites intrude all the metamorphic rock types described above and are less deformed than the host rock. Post-metamorphic pegmatites form only 2- to 3-m-wide dikes and contain coarse- to very coarse grained minerals that consist of 35 to 85% alkali feldspar, 10 to 20% quartz, 0 to 10% plagioclase, 0 to 10% biotite, 0 to 5% muscovite, and 0 to 5% tourmaline. These dikes probably are *comagmatic* with the Vernal Mesa Quartz Monzonite.

The preliminary *discordant* U/Pb zircon date (obtained from sample NT11C, D.M. Unruh, unpub. written commun., U.S. Geological Survey, 1999) of the schistose part of the meta-sedimentary rocks is  $1,741 \pm 11$  Ma; it is not clear whether the date represents the age of old rocks that were eroded to produce the sediments or the age of metamorphism. However, the short 20-m.y. interval between the dates for the intrusive meta-igneous gneiss (Xi) and the meta-sedimentary country rocks suggests that the 1,741-Ma date is the age of metamorphism.

**Alluvial fans.** In semiarid environments like that of the map area, ephemeral streams and *debris flows* commonly deposit gravelly sediment in alluvial fans along steep mountain and plateau fronts. Alluvial fans are present in two depositional settings in the map area: (1) A few alluvial fans presumably formed where steep-gradient, ephemeral streams deposited gravelly sediment along the northeast front of the Uncompahgre Plateau. However, these presumed fans were so modified by overlying eolian sand and *sheetwash deposits* (Qse) that fan-shaped landforms are no longer recognizable. Therefore, these presumed fans are called younger alluvial-slope deposits (Qasy) and older alluvial-slope deposits (Qaso). (2) A few small Holocene young *fan-alluvium* and *debris-flow deposits* (Qfy) formed on the flood plain of the Colorado River. Young *fan-alluvium* and *debris-flow deposits* are not common in the map area because some of those deposited on the flood plain of the Colorado River have been removed by the river.

**Bedrock contacts.** In the process of mapping the bedrock geology of Colorado National Monument and surrounding areas, stratigraphic horizons were selected that ensured that unit boundaries were readily mappable. Therefore, mappable stratigraphic horizons do not necessarily follow stratigraphic breaks defined by microfossil evidence or by detailed stratigraphic information such as *paleosols* that are only locally present because mapping by such features would be impractical.

The base of the Mancos Shale (Km) was mapped at the base of the nearly continuous dark fissile shale above the uppermost prominent set of thin sandstone beds and carbonaceous interbeds of the Dakota Formation (Kd). Only the lowest 20 m of the Mancos Shale are exposed in the map area. These strata are equivalent to the Tununk Member of the Mancos Shale recognized in Utah (Fouch and others, 1983; Cole, 1987). Although the age of the Mancos Shale extends from Campanian to Cenomanian Ages (Young, 1959) in the Grand Valley area, only the lowermost Mancos is exposed in the map area and the age of these strata probably represents parts of Turonian and Cenomanian Ages (Fouch, 1983).

The contact between the Dakota Formation (Kd) and the underlying Burro Canyon Formation was defined arbitrarily as the base of the lowest carbonaceous mudstone above the Burro Canyon Formation (Kb). According to William A. Cobban (U.S. Geological Survey, oral commun., 1999), the upper part of the Dakota contains Cenomanian fauna near Delta, Colo., 60 km to the southeast of the map area, and the lower Dakota is probably Albian near the map area (Table 3).

The base of the Burro Canyon Formation rests on the K-1 (basal Cretaceous) unconformity (Peterson, 1994; Peterson and Turner, 1998) above the Brushy Basin Member of the Morrison Formation (Jmb), but that unconformity was impractical to map because it has been defined by microfossils and a poorly exposed *paleosol*. Therefore, the base of the Burro Canyon was arbitrarily defined as the lowest thick sandstone or conglomerate bed above the mudstone of the Brushy Basin Member (Jmb). As a result, an undetermined interval of lowermost Burro

Canyon mudstone beds above the unconformity may have been included in the Brushy Basin (Aubrey, 1998). Because of the discontinuous and lenticular character of the sandstone and conglomerate beds in the Burro Canyon, the basal contact and the thickness of the rock unit are somewhat irregular. The Burro Canyon Formation is Albian and Aptian Age according to *palynological* evidence (Craig, 1981).

Contacts between the Morrison Formation members were located at horizons that could be followed readily on aerial photographs and easily located in the field. The Brushy Basin Member of the Morrison Formation (Jmb) rests *disconformably* above the Salt Wash Member (Jms) (unnamed unconformity; R.G. Young, oral commun., Grand Junction, Colo., 1999). Single-crystal,  $^{40}\text{Ar}/^{39}\text{Ar}$  ages of feldspars from the Brushy Basin Member indicate that this member is probably Tithonian and Kimmeridgian (Kowallis and others, 1991; Kowallis and others, 1998). The contact between the two members was defined as the top of the highest thick sandstone of the Salt Wash below the mudstone beds of the Brushy Basin. As the overlying Brushy Basin Member (Jmb) was assigned to the Tithonian and Kimmeridgian Ages (Kowallis and others, 1991; Kowallis and others, 1998) and the underlying Tidwell Member (Jmt) was assigned to Kimmeridgian and latest Oxfordian Ages (Kowallis and others, 1998), the Salt Wash is restricted to the Kimmeridgian. For mapping purposes, the upper contact of the Tidwell Member (Jmt) was placed at the top of the uppermost major limestone bed of the Tidwell below the thick sandstone intervals of the Salt Wash Member. These limestone and sandstone intervals are discontinuous and lenticular, and therefore this contact and thicknesses of adjacent units are irregular. Anderson and Lucas (1998) consider the strata below the Salt Wash Member southwest of the map area to be the Summerville Formation based on thin parallel-bedded *gypsiferous* strata typical of the Summerville Formation. The absence of this distinctive rock type in the map unit indicates that the term "Tidwell Member" of the Morrison Formation should be retained in the map area. The lowermost sandstone package that defines the base of the Tidwell is informally called "A" bed and rests on the J-5 unconformity (Pipiringos and O'Sullivan, 1978) above the distinctive green-over-red mudstone of the Wanakah Formation. O'Sullivan (1992) indicated that the age of the Tidwell is Kimmeridgian, but subsequent  $^{40}\text{Ar}/^{39}\text{Ar}$  sanidine dating suggests that the Tidwell is Kimmeridgian to latest Oxfordian (Kowallis and others, 1998).

The Wanakah Formation (Jw) was previously called the Summerville Formation in Colorado National Monument (Lohman, 1963, 1981). Although stratigraphic correlations by O'Sullivan (1980, 1992) suggest that the Summerville does not exist in western Colorado, more recent work of Anderson and Lucas (1998) south and west of the map area proposed that the name Summerville Formation is appropriate for strata below the Salt Wash Member. It is unclear whether the Summerville Formation as defined by Anderson and Lucas includes the Wanakah, and here the Wanakah nomenclature is retained. The base of the Wanakah Formation is readily recognized in the field or

on aerial photographs as the base of the distinctive red lower part of the map unit. The Wanakah is assigned to the Callovian Age (O'Sullivan, 1992; Peterson, 1994).

The prominent white cap of the Entrada Sandstone above the Slick Rock Member (Jes) differs significantly from the Moab Member of the Entrada Sandstone present southwest of the map area. The Moab Member does not contain thin to thick, light-colored beds of sandstone that only rarely display small-scale wind ripple structures and does not commonly include interbeds of reddish-brown to grayish-red mudstone, both characteristic of the white cap in the map area. Therefore, the stratigraphic nomenclature of Lohman (1963, 1981) for this unit is not retained in this report, and an informally named "board bed" unit (Jeb) is accepted here following O'Sullivan and Pipiringos (1983) until further stratigraphic studies are performed. The Slick Rock Member of the Entrada Sandstone rests on the J-2 unconformity (Pipiringos and O'Sullivan, 1978); erosional relief on the J-2 unconformity is as much as 3 m. The Slick Rock Member is Callovian Age (Peterson, 1998a).

The Kayenta was tentatively assigned to Pliensbachian and Sinemurian Ages by Peterson and Pipiringos (1979), then restricted by Peterson (1988b) to Pliensbachian and Sinemurian Ages, and most recently further restricted by Peterson (1994) to Pliensbachian.

The Wingate has been assigned to the Hettangian Age based on dinosaur fossils (Padian, 1989), but more recently it was expanded to Pliensbachian to Hettangian Ages by Peterson (1994).

The age of the Chinle Formation is Late Triassic (Norian and Carnian); its sedimentology and depositional history in northwestern Colorado is summarized by Dubiel (1992).

The basal contact of the Chinle Formation on Proterozoic rocks is an angular unconformity that represents a break in the rock record between about 1,400 and 230 million years ago, or about 1,170 million years.

## Geochronology

In conjunction with mapping the Colorado National Monument area, several rock units have been dated by radiometric methods. A detailed explanation of the geologic setting of the dated samples, the methods used, and interpretations of the results follows. Some results are preliminary because further research is required to define which of several possible geologic events has been dated. The time of formation of crystalline rocks of the Proterozoic basement can be dated, but with difficulty, mostly because the radiometric "clock" of zircon is not necessarily reset by the degree of metamorphism of the rocks in the map area. The time of deposition of overlying Mesozoic sedimentary strata cannot be dated using radiometric techniques, and the age of many of the sandstone units cannot be determined because they are relatively nonfossiliferous. In contrast, the charcoal in Holocene valley-fill deposits is easily dated by  $^{14}\text{C}$  methods. The geochronological results are discussed below.



Dissected Holocene and latest Pleistocene sandy valley-fill deposits in the upper part of No Thoroughfare Canyon. View to the northeast. *Photograph by W.C. Hood, 1998.*

Evidence indicates that the Proterozoic rocks of Colorado National Monument either were metamorphosed from sediments derived from rocks that were formed about 1,740 Ma or were metamorphosed about 1,740 Ma. This event was quickly followed by intrusion of a *stock* about 1,720 Ma. Parts of the Uncompahgre Plateau and the Black Canyon of the Gunnison were then intruded by large *batholith*- and *stock*-size bodies of quartz monzonite about 1,430 Ma, although direct evidence of this intrusion was not recognized within the map area.

The preliminary *discordant U/Pb* zircon date (obtained from sample NT11C, D.M. Unruh, unpub. data, U.S. Geological Survey, 1999) of the schistose part of the *migmatized* meta-sedimentary rocks (Xm) southwest of Devils Kitchen is  $1,741 \pm 11$  Ma. The *discordant* nature of the date is considered to be related to regional reheating and loss of Pb caused by emplacement of the 1,400-Ma Vernal Mesa Quartz Monzonite. Although the quartz monzonite is not exposed in the map area, it may be present at depth. It is unclear from either geochronological data or ambiguous petrographic evidence derived from the shapes of zircon grains whether this date represents the age of the *protolith* or the age of *migmatization* of the meta-sediments. This date appears to be older than the *Rb/Sr isochron age* of 1,630 Ma for the feldspathic gneiss dated by Hedge and others (1968) south of the map area on the Uncompahgre Plateau,

but the large uncertainty ( $\pm 130$  Ma) related to the low Rb/Sr ratio of the feldspathic gneiss allows the two dates to be compatible. The post-metamorphic pegmatitic dikes that cut the 1,700-Ma *migmatitic* rocks of the Monument area are considered to be *comagmatic* with the Vernal Mesa Quartz Monzonite.

In the Monument area, the age of emplacement of the Early Proterozoic meta-igneous gneiss (Xi) of the Ute Canyon *stock* (west of the mouth of Ute Canyon) has been estimated to be  $1,721 \pm 14$  Ma based on the preliminary *discordant U/Pb* date (sample Ute 1, D.M. Unruh, unpub. data, U.S. Geological Survey, 1999). The *discordant* nature of this date may also be related to Pb loss caused by regional heating following intrusion of the Vernal Mesa Quartz Monzonite. This date may be slightly older than the *Rb/Sr isochron age* of  $1,670 \pm 40$  Ma determined for emplacement of a gneissic granodiorite collected about 40 km west of the map area on the Uncompahgre Plateau (Hedge and others, 1968). However, if the uncertainty is taken into account, there is a 3-m.y. overlap in their ages.

At least two quartz monzonite *batholith*-size bodies intruded the region in and near the Uncompahgre Plateau more than 1,400 Ma. The Vernal Mesa Quartz Monzonite in Unaweep Canyon about 30 km southwest of the map area was dated at  $1,480 \pm 40$  Ma by the *Rb-Sr isochron* method by Hedge and others (1968). A petrographically similar plutonic body in the Black Canyon of the

Gunnison River about 80 km to the southeast of the map area has a similar age using the same dating method (Hansen and Peterman, 1968). The age of intrusion of the Vernal Mesa Quartz Monzonite in Unaweep Canyon has been confirmed by the *concordant date* of  $1,433 \pm 2$  Ma using the U/Pb method for zircon from sample UN2 (D.M. Unruh, unpub. data, U.S. Geological Survey, 1999). In the canyons just west of the map area, there is another intrusion. This *stock* contains large potassium feldspar phenocrysts aligned at *attitudes* inconsistent with the *attitudes* of the *schistosity* of the older *migmatized* meta-sedimentary gneiss and does not display a through-going *schistosity*. These relations are similar to those of the Vernal Mesa and Black Canyon intrusions and suggest that the stock may have a younger intrusive age, similar to the 1,400-Ma age of the Vernal Mesa intrusion. The undeformed pegmatite dikes in the map area may be *comagmatic* with this body.

Two *lamprophyre* dikes (Y1) cut the Proterozoic rocks, one in the northeastern part of No Thoroughfare Canyon and one in the northeastern part of Columbus Canyon. The biotite in the *lamprophyre* dike in No Thoroughfare Canyon (sample K98.8.10F) provided a preliminary  $^{40}\text{Ar}/^{39}\text{Ar}$ -method date of slightly less than about 1,400 Ma (M.J. Kunk, U.S. Geological Survey, unpub. data, 2000). Unrelated diabase dikes in similar Proterozoic rocks of the Black Canyon of the Gunnison about 90 km to the southeast of the map area were dated by the *Rb/Sr isochron* method at  $510 \pm 60$  Ma (Hansen and Peterman, 1968) and are much younger than the *lamprophyres* in Colorado National Monument.

Sandy valley-fill deposits (Qvf) that locally cover canyon floors on the Uncompahgre Plateau commonly contain significant amounts of charcoal fragments (Scott and others, 1999). Thirteen charcoal samples have been dated using  $^{14}\text{C}$  dating

**Table 4.**  $^{14}\text{C}$ laboratory values and calibrated ages for valley-fill deposits in and near the map area.

Sample	Depth (m)	$^{14}\text{C}$ lab value (years BP)	Calibrated age (years BP)	Lab number	Latitude	Longitude
Uppermost part of No Thoroughfare Canyon						
C2	2.2	$1,970 \pm 50$	1,900 1,910 1,920	W1734	$38^\circ 59.209'$	$108^\circ 41.714'$
C3	6	$4,870 \pm 50$	5,600	W1735	$38^\circ 59.218'$	$108^\circ 41.722'$
C4	9	$9,190 \pm 50$	10,250 10,300 10,320 10,350 10,360	W1736	$38^\circ 59.213'$	$108^\circ 41.754'$
Farther downstream in No Thoroughfare Canyon						
C5	6	$4,210 \pm 40$	4,830	W2072	$38^\circ 59.890'$	$108^\circ 41.100'$
C6	9	$4,470 \pm 50$	5,050 5,190 5,200	W2071	$38^\circ 59.890'$	$108^\circ 41.100'$
C7	19	$5,380 \pm 50$	6,200	W2442	$38^\circ 59.890'$	$108^\circ 41.100'$
C8	19.5	$4,900 \pm 50$	5,610	W2443	$38^\circ 59.890'$	$108^\circ 41.100'$
C9	19.8	$5,060 \pm 60$	5,760 5,830 5,860 5,880	W2444	$38^\circ 59.890'$	$108^\circ 41.100'$
C10	~19	$4,540 \pm 50$	5,290	W2445	$38^\circ 59.908'$	$108^\circ 41.070'$
Below the exit of No Thoroughfare Canyon from Colorado National Monument						
C1	~1.6	$1,280 \pm 50$	1,180 1,200 1,230 1,250	W1734	$39^\circ 1.853'$	$108^\circ 37.520'$
Upper part of Red Canyon						
C11	1.5	$2,370 \pm 40$	2,350	W2073	$39^\circ 1.955'$	$108^\circ 40.638'$
Cactus Park, 20 km southeast of the map area						
C12	~2	$8,600 \pm 50$	9,550	W2169	$38^\circ 52.08'$	$108^\circ 29.55'$
Alcove above samples C2 to C4 on western canyon wall						
C13	0.3	$4,410 \pm 40$	4,980 5,030	W2074	$38^\circ 58.710'$	$108^\circ 40.887'$



View to the southwest from the upper part of No Thoroughfare Canyon showing an alcove in the cliff of Wingate Sandstone. *Photograph by R.B. Scott, 1998.*

techniques at the University of California, Berkeley, Accelerator Mass Spectrometer (analyses by J.P. McGeehin, unpub. data, U.S. Geological Survey, 1998 and 1999). These laboratory measurements (Table 4) are given in years before present (years BP), referenced to the year 1954. Because there have been fluctuations in the abundance of  $^{14}\text{C}$  in the atmosphere in the past (related to cosmic radiation variations), each laboratory measurement can be translated into multiple calibrated ages (Stuiver and others, 1998) (Table 4). These calibrated ages still have a relatively narrow range of values and can provide approximate ages of the charcoal. Because the trees from which the charcoal came may have been piñon or juniper that had lived for several hundred years, the calibrated ages may be older by several hundred years than the time of the wildfire that produced the charcoal.

Three charcoal samples from a deep stream cut in the uppermost part of No Thoroughfare Canyon were dated. The lab value of the youngest sample (C2), collected 2.2 m below the top of unit Qvf, is  $1,970 \pm 50$  years BP; the lab value of the next older sample (C3), collected 6 m below the top of the unit, is  $4,870 \pm 50$  years BP; the lab value of the oldest sample (C4), collected 9 m below the top of the unit, is  $9,190 \pm 50$  years BP. A few centimeters below sample C3, an artifact (stone scraper)

was found, suggesting that the canyon was inhabited by ancestors of Native Americans more than about 5,600 years BP based on the calibrated age of the charcoal.

Another five samples collected about 2 km farther downstream in No Thoroughfare Canyon were dated. The lab value of the youngest sample (C5), collected 6 m below the surface, is  $4,210 \pm 50$  years BP. The lab value of the next older sample (C6), collected 9 m below the surface, is  $4,470 \pm 50$  years BP. The third sample (C7) was collected about 19 m below the surface and 1.2 m above the base of the sediments of unit Qvf, and has a lab value of  $5,380 \pm 50$  years BP. The lab value of the fourth sample (C8) collected at 0.7 m above the base of the sediments was measured at  $4,900 \pm 50$  years BP. The lab value of the lowest sample (C9), collected 0.4 m above the base, was measured at  $5,060 \pm 60$  years BP. For reasons that are unclear, the ages of the lowest two samples are not consistent with the stratigraphic sequence, even when taking into account the analytical uncertainties of the dating method. Possibly, older sediments were undercut by erosion and replaced by younger sediments about 300 and 500 years later, but it is more likely that different ages of trees are involved or large variations in transport time affected the sequence.

Sample C10 collected 60 m further downstream, at a depth of about 19 m and 1 m above the bedrock, has a lab value of  $4,540 \pm 50$  years BP. Sample C1 collected from the lower part of No Thoroughfare Canyon at a depth of about 1.6 m, just within the southeastern boundary of Colorado National Monument, has a lab value of  $1,280 \pm 50$  years BP. Although this sample was collected from valley-fill deposits (Qvf), the exposure in a cut-bank, which is overlain by eolian sand and *sheetwash deposits* (Qse), is too narrow to be shown on the map. Another sample (C11) collected from the upper part of Red Canyon, 1.5 m below the surface of a 3-m-high terrace adjacent to the drainage, has a lab value of  $2,370 \pm 40$  years BP.

Sample C12, collected from similar sediments at a depth of about 2 m in Cactus Park, 20 km southeast of the map area, provided a lab value of  $8,600 \pm 50$  years BP (and a calibrated age of about 9,550 years BP). It indicates that sediments equivalent to the valley-fill deposits were probably deposited elsewhere on the Uncompahgre Plateau also during the Holocene and latest Pleistocene.

Jack Roadifer (emeritus faculty member at Mesa State College) found a mastodon tooth in the streambed of No Thoroughfare Canyon. It is assumed that the tooth was eroded from the lower part of the valley-fill deposits. The oldest calibrated ages from sample C4 that range from 10,250 to 10,360 years BP and the presence of the tooth confirm that the oldest part of the valley-fill deposits is older than 10,000 years BP, and therefore, is late Pleistocene. The ages of the valley-fill sediments are progressively younger downstream in No Thoroughfare Canyon. This relation can be explained by a *downlap depositional sequence*, and it is also likely that there are numerous unconformities in this sedimentary sequence (Scott, Hood, and others, 1999).

Charcoal sample C13 was collected from the west wall of the upper part of No Thoroughfare Canyon from distinctly different sediments in an alcove protected from erosion. This alcove is about 45 m above the floor of the canyon. Careful inspection of the cliff above the alcove suggests that a large slide block of the Wingate Sandstone (Jwg) dammed the entrance of the alcove, allowing charcoal-bearing sediments to accumulate in the alcove behind the dam. Only remnants of the slide block still exist. The  $^{14}\text{C}$  lab value of  $4,410 \pm 40$  years BP provides minimum calibrated ages of 4,980 or 5,030 years BP for the disintegration of the sandstone block.

## Geologic Formation of Colorado National Monument

Over a period of about 1.7 billion years, a little longer than a third of the Earth's history, geologic processes have created the features at Colorado National Monument. These processes include volcanism in island arcs along the growing ancestral North American continental margin, high-grade metamorphism, several periods of mountain building, several periods of deep erosion, deposition of marine and non-marine sediments, more uplift, and, finally, erosion that carved the modern landforms. In the Geologic History section, we will describe the geologic processes that operated during the formation of the Monument. In the Structural and Tectonic Issues section, we will present a more detailed interpretation of the structures and tectonism that are responsible for much of the character of the Monument.

## Geologic History

For well over a century, many geologists have studied the geologic history of the area around Colorado National Monument. Our study of the Monument area adds to this geologic knowledge. In the following pages we will first describe the general setting of the Monument region, then address the history of the Monument area and relate that history to features on the map of the Monument.

Colorado National Monument and adjacent areas of this map are within the Colorado Plateau, about 110 km west of the northeastern border of the Plateau where the Colorado River cuts through the steeply *dipping* strata of the Grand Hogback (Figure 1). The Colorado Plateau is an elevated, mildly folded and faulted physiographic province generally underlain by nearly flat-lying sedimentary rocks. The Colorado National Monument map area overlaps the northeastern margin of the Uncompahgre uplift, which is expressed topographically by the Uncompahgre Plateau. It forms a northwest-trending, elongate uplift on the Colorado Plateau that measures 150 km by 45 km. In the northeastern part of the map area, the Uncompahgre Plateau abruptly ends with an 800 m drop in elevation to the level of the Redlands area, the Colorado River, and Grand Valley. This elevation change coincides with changes from nearly horizontal strata on the Uncompahgre Plateau to steeply *dipping* and faulted strata in a narrow zone in which strata drop nearly 600 m. The S-shaped fold that accompanies this steeply *dipping* zone is called a *monocline*. Under the Redlands area, the northeast *dip* of strata decreases to  $5^\circ$  (see sections A-A' and B-B'). The *dip* of strata decreases eastward under Grand Valley to  $2^\circ$ , but then increases again to about  $5^\circ$  in the Book Cliffs *monocline* under the Book Cliffs (Figure 2), based on *structure contours* drawn on the top of the Dakota Formation on a regional map compiled by Cashion (1973).

During the Early Proterozoic, south of the edge of the Archean North American craton in Wyoming, island arc volcanic rocks and related sediments accumulated along a convergent *plate margin*. Evidence of these *calc-alkalic* volcanic rocks and sedimentary rocks is widespread in a 500-km-wide belt of Early Proterozoic rocks in Colorado (Reed and others, 1987), including Colorado National Monument. About 1.74 billion years ago, during a period of compressive mountain building along that new continental margin, isoclinal folding, high-grade metamorphism, and partial melting converted these rocks into the *migmatitic* metasedimentary rocks (Xm) now so well exposed in the canyon bottoms of the Monument. Only 20 million years later (1.72 billion years ago), a granitic body (metigneous gneiss, Xi) intruded the area of No Thoroughfare and Ute Canyons. The granitic rock was only weakly affected by the waning phase of metamorphism and compression. About 1.4 billion years ago, two narrow, northeast-trending *lamprophyre* dikes (YI) intruded the area, probably after the end of this first period of compressional mountain building.

No record of geologic events during the next 1,170 million years exists in the Monument area; this enormous break in the rock record is known as the Great Unconformity. Throughout Colorado, deep erosion of Early Proterozoic rocks removed kilometers of the overlying, less metamorphosed rocks and



View to the east across the North Entrance of Monument Canyon. Note the *hinge line* between the shallow dip on the highlands on the right and steeper dips on the left. The Wingate Sandstone becomes significantly thinner on the left as it enters the *monoclinal fold*. *Photograph by R.B. Scott, 1998.*

exposed the highly metamorphosed cores of ancient mountains. During Cambrian through Mississippian time (570-320 Ma), relatively thin marine sandstone, limestone, dolomite, and shale were deposited, covering much of the North American craton.


During Pennsylvanian and Permian time (320-245 Ma), Colorado was subject to a second period of compression and uplift, which formed the Ancestral Rocky Mountain Front Range uplift and the Ancestral Uncompahgre uplift by crustal shortening on *high-angle reverse* and thrust faults (Ye and others, 1996). Lower Paleozoic marine rocks were eroded from the Monument area and were transported several tens of kilometers southwestward to be deposited in great thicknesses in the Paradox Basin (Figure 2). Eventually, Early Proterozoic metamorphic rocks again lay exposed in the Monument area.

Then, deposition began again. Triassic through Cretaceous sediments were deposited over Colorado, this time under largely non-marine conditions until the Late Cretaceous seas covered the area. During the Mesozoic, non-marine sandstone and shale were deposited on the Great Unconformity above the Early Proterozoic metamorphic rocks. Most of the cross-bedded sandstone was deposited in desert conditions similar to those in the modern Sahara, and shale commonly was deposited in shallow non-marine

lakes. These strata were then covered by the thick marine Mancos Shale and younger non-marine sandstone and shale.

For a third time mountain building affected Colorado. The Laramide orogeny began during the Late Cretaceous (about 70 Ma) and continued into middle Eocene (about 50 Ma). Although the Rocky Mountains experienced significant compression and uplift, farther west the Colorado Plateau experienced more subtle uplifts that caused the sedimentary strata to become folded above deep-seated, *high-angle reverse faults* to form *monoclinal folds* (Hunt, 1956a; Lohman, 1965; Stone, 1977; Miller and others, 1992; Davis, 1999). It is this style of folding and faulting that created most of the structural framework of the northeastern and southwestern margins of the Uncompahgre Plateau and Colorado National Monument.

After the Laramide, during a significant part of the Cenozoic Era, great volumes of sedimentary rocks, particularly the soft, easily eroded shales, were slowly removed from the Colorado Plateau. During periods of relative tectonic quiescence, rivers in the area tended to meander and began to carve broad valleys into areas underlain by Mancos Shale, such as Grand Valley. Regional uplift(s) in the Late Cenozoic caused the rivers to entrench their meanders into the more resistant rocks beneath the Mancos, forming the Grand Canyon, the Goosenecks of the San Juan



**Figure 1.** Regional geographic features in western Colorado and eastern Utah.

River, and Ruby and Horse Thief Canyons at the northwestern end of the Uncompahgre uplift. This process of exhumation as a result of regional uplift is continuing today, and erosion of the canyons on the northeastern edge of the Uncompahgre Plateau at Colorado National Monument is beginning to strip older, more resistant Mesozoic rocks from the Plateau. And for a fourth time, Early Proterozoic rocks are being exposed. It is this canyon-cutting process that today is actively creating the magnificent scenery at Colorado National Monument.

### Structural and Tectonic Issues

In this section, we address more detailed scientific issues. Because evidence of the character and timing of uplift of the Uncompahgre Plateau is subtle, many puzzles and controversies remain unresolved. Therefore, this section is not an attempt to resolve issues, but rather to highlight them. Although the text is more technical than the preceding discussion of the geologic history, the Glossary should make it possible for non-geologists to follow issues.

### Interpretation of Structures At Colorado National Monument

First we address the nature of faulting associated with Laramide uplift. As stated above, *monoclinal* folds in the Mesozoic sedimentary rocks above *high-angle reverse faults* in basement rocks are considered to be characteristic of Laramide

deformation (Hunt, 1956a; Lohman, 1965; Stone, 1977; Miller and others, 1992; Davis, 1999). In contrast, normal faults are commonly associated with post-Laramide extension. Some areas on the Uncompahgre Plateau margins display only high-angle reverse faults, other areas display both reverse and normal faults, and one area displays only normal faults. The question arises, does the presence of normal faults suggest that some of the uplift or deformation of the Uncompahgre is post-Laramide?

All major faults on the northeastern margin of the Uncompahgre Plateau in the map area are clearly *high-angle reverse faults*, and therefore, they are consistent with compressional features associated with the Laramide. However, elsewhere on the northeast margin, both *normal* and *reverse faults* are generally present (Heyman, 1983; Heyman and others, 1986). The geometric relations between these reverse and normal faults suggests that the normal faults are secondary and *antithetic* to major reverse faults, and therefore, both types of faults were probably formed together during the Laramide.

On most of the southwest margin of the Plateau, only *high-angle reverse faults* of Laramide age deformed Mesozoic strata (White and Jacobson, 1983; Heyman and others, 1986). However, on the northwest part of the southwest margin of the Plateau, major faults that affected Mesozoic strata are all *normal faults* (Williams, 1964; Case, 1966). No major *high-angle reverse fault* is recognized in the subsurface (White and Jacobson, 1983; Heyman and others, 1986). At this locality, Williams (1964) uses structure contours drawn on the base of the Dakota Formation to demonstrate as much as 685 m of *structural relief* between the Paradox basin and the Uncompahgre Plateau on *normal faults* and *monoclinal* folds. The possibility that these





Figure 2. Geographic features near the map area.

large structures are related to post-Laramide extension rather than to Laramide compression is rejected because the elevations of stratigraphic horizons on the Uncompahgre Plateau uniformly increase from northwest to southeast across this area. If a significant amount of extensional post-Laramide uplift were superimposed on Laramide uplift in this specific area, departures from Williams' uniformly spaced structure contours would

be noticeable. Probably these normal faults are not post-Laramide, and a major *high-angle reverse fault* does underlie these structures, but has not been recognized in the subsurface.

A second issue is whether the attitudes of foliation in the Proterozoic basement rocks influenced the attitudes of the *high-angle reverse faults* along the northeastern margin of the Plateau in the map area. In the map area, the *high-angle reverse*

*High-angle reverse fault* in the first canyon northwest of the Serpents Trail parking lot. View to the southeast shows an abrupt end of light-colored beds of the lower part of the Wingate Sandstone against the Chinle Formation at the fault. The fault dips steeply to the southwest (right). *Photograph by W.C. Hood, 1998.*



Redlands fault *dips* southwest to south between  $62^\circ$  and  $83^\circ$ , averaging  $72^\circ$ . Based on numerous foliation attitudes of Proterozoic rocks, the foliation in both the meta-sedimentary rocks and the meta-igneous body is sub-parallel to the northwest-trending mountain front between No Throughfare and Ute Canyons, but the foliation in meta-sedimentary rocks is nearly perpendicular to the mountain front in the more northerly canyons. Therefore, there may be some pre-existing structural control for the southern part of the Redlands fault. In contrast, between Gold Star and Kodels Canyons where the fault progressively changes from a northwestern trend to a western trend, there is no apparent control from the metamorphic foliation attitudes.

Another subject of intense study has been the geometry of monoclines associated with the margins of the Plateau. Local areas of these folds have been the subject of numerous studies (for example, Stone, 1977; Stearns and Jamison, 1977; Jamison, 1979; Jamison and Stearns, 1982; Heyman and others, 1986; Land, 1993). In general, strata deformed over the main *high-angle reverse* Redlands fault form an S-shaped fold. In greater detail, the nearly flat-lying strata on the uplifted Uncompahgre Plateau make a sharp bend or *hinge line* where the *dip* of strata and the dip of the surface of the Proterozoic rocks increase toward the northeast (sections A-A' and B-B'). In some cases, a small-offset, down-toward-the-mountain-front,

*antithetic normal fault* underlies this *hinge line*, at least in the northwestern part of the map area (section A-A'). Commonly, the *dip* of strata in the panel of rock between the *hinge line* and the main *high-angle reverse* Redlands fault increases significantly closer to the fault. Immediately above the Redlands fault, folded strata reach the *inflection point* in the S-shaped fold (called an *inflection hinge* on section A-A'). Locally, *dips* at the *inflection hinge* approach vertical and are locally overturned. Farther down the structure toward the northeast, the *dips* in the strata decrease toward the final hinge of the S-shaped fold. Northeast of that hinge, *dips* are nearly constant. Commonly, the Wingate Sandstone (Jwg) shows evidence of significant *attenuation* within the S-shaped fold where the unit thins by microfaults or shear (Jamison, 1979; Jamison and Stearns, 1982; Heyman, and others 1986; Davis, 1999). The Wingate also absorbs the fault so that the upper Wingate is only folded. As shown in section A-A', this pattern of change in *attitudes* of the Mesozoic strata is repeated between the main front of the Plateau and the Colorado River, suggesting that another *high-angle reverse fault* is buried at depth. These changes in *dip* are also shown by traces of *hinge lines* on the map.

The term “draped” has been used in the past to describe the monoclinal fold above these faults. However, Erslev (1991) and Erslev and Rogers (1993) interpret similar structures elsewhere as *fault propagation folds*. In the *hanging-wall* block above the Redlands fault, microfaults have steep *dips* that may have resulted from anticlinal stretching or layer-parallel extension; on the footwall block, microfaults have *attitudes* subparallel to bedding, which may have resulted from synclinal crowding or back thrusting on bedding (Erslev, 1991).

Regardless of the shape drawn for the high-angle reverse faults at depth, problems arise when movement on faults is geometrically restored, assuming rigid-block rotation on the faults to reconstruct a pre-faulting geometry. Attempts to create *balanced sections* fail because the basement-Mesozoic rock contact dips steeply to the northeast (section A-A'). The problem becomes more severe if a listric-shaped fault is assumed (Kellogg and others, 1995; Erslev and others, 1999). Kellogg and others (1995), faced with a similar problem elsewhere, provided a complex deformation mechanism that geometrically solves this problem by having shear between thrust pairs rotate the block between the thrusts to the observed *dip* of the contact of the basement with sedimentary rocks. No evidence for such deformation exists in the map area. A simpler model may involve multiple micro-faults that formed a triangular zone that spread from the main thrust, creating a fan-like shape similar to the triangular zones of deformation described by Erslev and Selvig (1997). This model allows internal deformation of the triangular-shaped block of basement rock to change the attitude of the basement-Mesozoic contact.

## Late Cenozoic Regional Uplift

As discussed in the Geologic History section above, after Laramide uplift and deformation, the entire Colorado Plateau probably endured a long period of relative quiescence in the Tertiary, during which headward erosion by low-gradient rivers

progressively cut back through soft overlying strata. The Mancos Shale, in particular, was susceptible to erosion. Removal of the thick Mancos Shale from parts of the Colorado Plateau was still underway about 3.5 Ma in middle Pliocene, as proposed by Fleming (1994), based on Pliocene deposits in southern California that contain reworked Cretaceous pollen derived from the Mancos Shale. As low-gradient precursors of the Colorado, San Juan, Green, and Dolores Rivers were eroding, they formed meanders in the soft strata. Eventually, these rivers began to entrench their meanders into the harder Mesozoic strata beneath the Mancos.

The period of regional canyon cutting probably began with late Cenozoic regional uplift across the Colorado Plateau, deeply entrenching the meanders (T.A. Steven, emeritus USGS, written commun., 2000; Steven and others, 1995; Steven and others, 1997). On the Uncompahgre Plateau, Unaweep Canyon displays evidence of the history of uplift in that region. Unaweep Canyon is an abandoned *antecedent river* (Figure 2) that probably was entrenched during this regional uplift. For some time the *antecedent* river's ability to erode kept pace with the rate of uplift.

## Pliocene Arching at Unaweep Canyon

At present, two small *underfit* streams, East and West Creeks, drain the broad, 700-m-deep Unaweep Canyon. The meandering abandoned river course includes only part of the canyon; the river course extends 16 km southwest gently up gradient from Cactus Park to a drainage divide and then gently down gradient for about 35 km (Figure 2). From this point, roughly coincident with the Plateau's structural axis, erosion of the canyon by the youthful West Creek sharply increased the stream gradient for 18 km to the Dolores River at Gateway. Northeast of Cactus Park, the youthful East Creek has cut a narrow steep stream course to the Gunnison River at Whitewater. The conclusion that Unaweep Canyon was formed by a relatively large *antecedent river* was reached over a century ago by Peale (1877) and Gannett (1882). This concept by early geologists was followed by similar proposals by Hunt (1956b), Lohman (1961, 1965), and Cater (1966), but they disagreed on when the canyon was cut, how the canyon was cut, and whether the Colorado River or the Gunnison River cut the canyon.

Mapping in the adjacent Grand Junction quadrangle sheds light on which river may have cut Unaweep Canyon (Scott and others, in press). A string of Colorado River gravels at an elevation of about 170 m above the south side of the Gunnison River were found within 12 km of Cactus Park. Below these elevations only Gunnison River gravels were found. This indicates that the Colorado River may have originally flowed close to Unaweep Canyon and further suggests the possibility that the Colorado River may have originally flowed through Unaweep Canyon. If so, the river probably was diverted to its modern course by processes of complex stream captures by tributaries in Grand Valley. Although Gannet (1882) and Lohman (1961, 1965) came to the same conclusion for different reasons, many others (among them, Peale, 1877; Hunt, 1956; Cater, 1966) disagreed. Clearly, further detailed research is needed.

We use the topography of modern drainage in Unaweep Canyon as evidence to propose local late Cenozoic uplift on the Uncompahgre Plateau. At Cactus Park, remnants of Gunnison River gravels rest on bedrock at an elevation of about 1,885 m, indicating that at one time the Gunnison River flowed from Cactus Park into Unaweep Canyon. This river course can be followed to the southwest from the 1,885 m elevation along 4 km of exposures of bedrock in Unaweep Canyon; however, to do so, requires climbing 55 m to an elevation of 1,940 m. Because the antecedent river flowed from northeast to southwest, this 55 m elevation gain can only be explained by arching that occurred after the river course had been established.

Oesleby (1983) estimated from seismic refraction and vertical electric sounding data that the river course southwest of this locality had been filled with as much as 335 m of surficial material, and the thicknesses determined by his surveys suggested that the valleys were originally V-shaped. About 8 km uphill from the junction of Cactus Park with Unaweep Canyon at a site where canyon walls are close to the valley center, the elevation of basement rock under valley fill is calculated to be at least 1,965 m, assuming the V-shape of the canyon below valley fill. Because Cactus Park gravels rest on bedrock at 1,885 m, then at least 80 m of arching must have occurred between the two points to raise the

elevation of the streambed in Unaweep Canyon. This arching must have been rapid enough to defeat the river's rate of downcutting and to dam the river as indicated by remnants of lakebeds above river gravels in Cactus Park. Assuming a rate of downcutting of about 0.15 m/ky, the arch may have formed about 2.8 Ma (late Pliocene) because Cactus Park is about 425 m above the present Gunnison River at Whitewater.

It has been suggested that late Pleistocene glaciation (Cole and Young, 1983) may have affected the canyon by carving triangular facets at the ends of ridges to form its U-shaped valley. However, the highest elevations on the top of the Plateau barely exceed 2,750 m, far lower than most Colorado Rocky Mountain cirques, which form at elevations greater than 3,350 m. No obvious cirques were observed on the walls of the canyon. The U-shaped valley floor is attributed to valley fill as determined by Oesleby (1983). Because glaciers deposit debris below levels of snow accumulation, but erode only above levels of snow accumulation, it is doubtful that glaciers carved the faceted ridges at elevations below 2,135 m. Continued meandering of the river in the valley could have faceted the ridges that display conspicuous vertical joints in the readily-weathered, coarse-grained Vernal Mesa Quartz Monzonite. In any case, possible glaciation does not bear on uplift and arching of the Plateau.



View to the southwest in the upper part of Lizard Canyon. The dark Proterozoic rocks in the left foreground abut the Chinle Formation on the right (partly covered by rock-fall deposits) where there are two *normal* faults. The offsets on the faults become absorbed in the two swarms of vertical fractures in the overlying Wingate Sandstone. *Photograph by R.B Scott, 1998.*

Much of this proposed geomorphologic and tectonic history of Unaweep Canyon was developed during regional reconnaissance geomorphologic studies by T.A. Steven (unpublished written commun., 1999 and 2000) in conjunction with the authors of this publication. A field trip to Unaweep Canyon with T.A. Steven (emeritus, USGS) and Charles Betton (retired geologist, Grand Junction, Colo.) provided additional critical evidence.

In summary, although Pliocene(?) regional uplift and then later Pliocene local arching clearly affected the Unaweep Canyon part of the Uncompahgre Plateau, evidence of post-Laramide uplift has not been recognized in the Colorado National Monument map area. But the absence of evidence does not exclude the possibility of minor, local, post-Laramide uplift in the map area. This conclusion for Colorado National Monument and the surrounding Uncompahgre Plateau is consistent with evidence of differential amounts of local Late Cenozoic uplift superimposed on a background of general regional uplift found elsewhere in the Rocky Mountains of Colorado (Steven and others, 1997; Erslev and others, 1999; Scott, Lidke, and others, 1999).

## Geologic Hazards

The Brushy Basin Member of the Morrison Formation contains abundant, *expansive smectitic clays*. When wet, these *expansive clays* reduce the shear strength of the Brushy Basin Member (Jmb) so that landslides commonly displace the Brushy Basin Member and the overlying Burro Canyon (Kb) and Dakota (Kd) Formations. Some of these landslides probably formed under conditions wetter than those of the present.

Old landslide deposits (Qls) partly veneer all sides of Black Ridge and have flowed across lower stratigraphic units onto the floor of Monument Canyon. They also locally cover the *dipslope* of the Morrison-Burro Canyon-Dakota Formations about 1 to 1.5 km south of the northern border and 4 to 5 km east of the west border of the map area. Although many or most of these landslides probably were generated during previous wetter climatic episodes and seem relatively stable now, bulges in roadcuts along Rim Rock Drive in the Monument suggest that these slides may have been reactivated after road construction. Excavations, excessive irrigation, and other disturbances related to home construction or excessive lawn watering on either old landslides or on gentle *dipslopes* underlain by this sequence of strata may cause either renewed or new sliding in the Redlands area.

Small, young landslide deposits (Qlsy) form along the south bank of the Colorado River. Roads and structures are subject to landslide hazards, especially those that are close to river bluffs where excess irrigation or lawn water has been applied. The most recent landslide began during the winter of 2000 and is still active during writing; the landslide has destroyed a house above the south bank of the Colorado River 0.2 km west of the east border of the map area. In the adjacent Grand Junction 7.5-minute

quadrangle, young landslides have damaged a sewage treatment plant and an irrigation pump station.

Watering of lawns in the Redlands area has been sufficient to locally activate movement of *expansive soils and clays* on and in the Brushy Basin Member of the Morrison (Jmb) as well as in some of the overlying map units. Damage to homes and roads is evident, particularly in the adjacent Grand Junction 7.5-minute quadrangle. *Smectitic clays* are alteration products of volcanic ash; therefore, these clays retain the higher radioactivity of the volcanic ash. Cole and others (1999) used a portable gamma-ray spectrometer to detect higher concentrations of gamma-ray producing radioactive elements in those parts of the strata that have the highest concentrations of *expansive clays* and, therefore, are those most prone to landsliding.

Surficial deposits that contain debris from the Brushy Basin Member are particularly susceptible to shrinking, swelling, and *hydrocompaction*; all of these deposits make an unstable base for roads or foundations of buildings. Eolian sand (Qe) is probably susceptible to *hydrocompaction* and possibly to *piping*. *Cienaga deposits* (Qcg) are poorly suited for supporting roads and structures or for the efficient operation of septic systems. Hazards commonly associated with these deposits include seasonal high water tables, low *bearing capacity*, and the presence of sulfate minerals, which deteriorate untreated concrete and steel. The Brushy Basin Member of the Morrison (Jmb), which underlies *Cienaga deposits*, is relatively impermeable and contains abundant *expansive clay*.

Intense summer thunderstorms are common on the Uncompahgre Plateau in the map area and supply large volumes of water in a short time to the canyons of Colorado National Monument, where constrictions in the canyons increase both the rate of flow and the flood heights. The resulting flash floods present a serious geologic hazard not only to visitors on foot in narrow canyons, but also to houses and roads that are close to flood-prone intermittent streams where these streams exit through narrow canyons onto the Redlands area. Boulders more than 2 m in diameter have been moved during historic and prehistoric flash floods. Alluvium (Qal) and flood-plain and stream-channel deposits (Qfp) are subject to periodic flooding. The Colorado River floods each spring following the period of maximum melting of thick snow packs in mountainous upstream areas.

Unstable cliffs formed by the Wingate Sandstone (Jwg), the Kayenta Formation (Jk), and the Salt Wash Member of the Morrison (Jms) produce rockfalls that pose a local geologic hazard. Where road construction has destabilized the rock, large rockfalls have occurred, damaging Rim Rock Drive in the Monument. Such a rockfall occurred in January 2000 when automobile-size blocks of sandstone from the Salt Wash Member of the Morrison Formation (Jms) slid on thin clay layers and toppled onto Rim Rock Drive, blocking traffic for at least a month.

## Geologic Resources

The most important geologic resource in the map area is the beauty of the erosional features and rocks exposed in the margin of the Uncompahgre Plateau. Many visitors to Colorado National Monument and the surrounding U.S. Bureau of Land Management lands support the tourist industry of Grand Junction and Grand Valley.

The map area contains abundant sand and gravel resources. Gravel pits are shown on the map by dotted boundaries in map unit Qfp. Most of these deposits contain rounded to well-rounded and well-sorted pebble-cobble gravel. The clasts consist largely of basaltic rocks, quartzite, micaceous red sandstone, gray fine- to medium-grained granitic rocks, "oil shale" of the Green River Formation, and intermediate volcanic rocks. The matrix of the gravel generally consists of silty sand and sand. The gravels are commonly overlain by 1 to 2 m of overbank and possibly eolian materials containing silty fine sand and fine sand. The gravels also contain about 5 to 15 percent "oil shale" clasts, derived from the Green River Formation. The "oil shale" has a low *bearing capacity*. Although, these gravels may be suitable for road base, they may not be suitable as an aggregate for concrete and asphalt. Drill-hole data for the area north of the Colorado River indicate that 3 to 15 m of *sheetwash deposits* (Qsw) overlie 3 to 7 m of Colorado River gravel in unit Qfp (Ken Weston; U.S. Bureau of Reclamation, written commun., 1999; Phillips, 1986). These data, however, may not represent the entire thickness of unit Qfp, because it is difficult to distinguish in drilling records between *sheetwash deposits* (Qsw) and lenses of sandy silt in the upper part of unit Qfp. The thickness of unit Qfp locally may exceed 7 m.

## Acknowledgments

The hospitality and cooperation of the staff of Colorado National Monument added significantly to the pleasure of mapping the Monument and surrounding area, especially by providing housing with showers, kitchen, and a terrific view. In particular, the friendly support of the previous Superintendent, Steve Hickman, and his staff of park rangers made normally difficult tasks much easier. Pat Perrotti, previous Resource Manager for the Monument, went out of his way to fill us in on current geologic events at the Monument. Bill Rodgers, Protection Ranger, spent a day in the field with us to locate critical boundaries in the new southern addition to the Monument. Judi Lofland, Museum Technician at the Monument, provided old photographs of the area and helped us with important historical details. Both Superintendent Palma Wilson and Dave Price, Resource Manager for the Monument, contributed editorial details. Bruce Heise of the National Park Service Geologic Resources Division and liaison to the USGS helped make the map a high-priority product. Joe Gregson, also with the Geologic Resources Division, obtained and transferred digital line graph (DLG) data critical for a legible topographic base for the map. The partnership with both the

Colorado National Monument Association and the National Park Service has been instrumental in the creation of this product for the public. In the USGS, Paco Van Sistine of the Earth Surface Processes Team provided prompt and critical GIS help, as did Nancy Shock and Alex Donatich of the Central Publication Group. The constructive reviews by Bruce Bryant and Jim Yount of the USGS significantly improved the quality of the map and text. Discussions with Robert Young of Grand Junction were valuable and invigorating. The radiometric dating by Mick Kunk and Dan Unruh of the USGS provided critical constraints on the ages of Proterozoic events. The  $^{14}\text{C}$  dates supplied by Jack McGeehin of the USGS not only gave us the timing for geologic events during the late Quaternary, but also allowed us to date the minimum period of Native American habitation in the canyons of Colorado National Monument. Working with Tom Steven on the geomorphologic implications of Unaweep Canyon has been both a most enlightening and invigorating experience. Finally, the impressive digital creative art of Carol Quesenberry and the immensely thorough editorial guidance of Craig Brunstein spurred us on to the finish. It certainly takes teamwork to make a map.

## References Cited

- Allen, J.R.L., 1970, Physical processes of sedimentation: London, George Allen and Unwin, 248 p.
- American Geological Institute, 1982, Grain-size scales used by American geologists, modified Wentworth scale, *in* Data Sheets (2nd ed.): Falls Church, Va., American Geological Institute, Sheet 17.1.
- Anderson, O.J., and Lucas, S.G., 1998, Redefinition of Morrison Formation (Upper Jurassic) and related San Rafael Group strata, southwestern U.S.: *Modern Geology*, v. 22, p. 39–69.
- Aubrey, W.M., 1998, A newly discovered, widespread fluvial facies and unconformity marking the upper Jurassic/Lower Cretaceous boundary, Colorado Plateau: *Modern Geology*, v. 22, p. 209–233.
- Birkeland, P.W., 1999, Soils and Geomorphology: New York, Oxford University Press, 430 p.
- Boggs, S., Jr., 1995, Principles of sedimentology and stratigraphy: Englewood Cliffs, Prentice Hall, edition 2, 774 p.
- Campbell, C.V., 1967, Lamina, laminaset, bed and bedset: *Sedimentology*, v. 8, p. 7–26.
- Cashion, W.B., 1973, Geologic and structure map of the Grand Junction quadrangle, Colorado and Utah: U.S. Geological Survey Miscellaneous Investigations Series Map I-736, scale 1:250,000.
- Case, J.E., 1966, Geophysical anomalies over Precambrian rocks, northwestern Uncompahgre Plateau, Utah and Colorado: *American Association of Petroleum Geologists Bulletin*, v. 50, p. 1423–1443.
- Cater, F.W., 1966, Age of the Uncompahgre uplift and Unaweep Canyon, west-central Colorado: *U.S. Geological Survey Professional Paper* 550-C, p. C86–C92.
- Cobban, W.A., Merewether, E.A., Fouch, T.D., and Obradovich, J.D., 1994, Some Cretaceous shorelines in the western interior of the United States, *in* Caputo, M.V., Peterson, J.A., and Franczyk, K.J., eds., Mesozoic Systems of the Rocky Mountain Region, USA: Rocky Mountain Section of the Society of Economic Paleontologists and Mineralogists (Society for Sedimentary Geology), p. 393–414.

- Cole, R.D., 1987, Cretaceous rocks of the Dinosaur Triangle, in Averett, W.R., ed., Paleontology and Geology of the Dinosaur Triangle: Grand Junction Geological Society 1987 Guidebook, p. 21–35.
- Cole, R.D., Hood, W.C., and Scott, R.B., 1999, Sedimentological reevaluation, high-resolution gamma-ray log, and landslide hazards of the stratigraphic section at Colorado National Monument, Western Colorado: Geological Society of America Abstracts with Programs, v. 31, no. 7, p. A–283.
- Cole, R.D., and Moore, G.E., 1994, Sequence stratigraphy of Cedar Mountain-Dakota interval, western and southern Piceance Creek basin, Colorado: American Association of Petroleum Geologists Annual Convention Program, v. 3, p. 124.
- Cole, R.D., and Young, R.G., 1983, Evidence for glaciation in Unaweep Canyon, Mesa County, Colorado: Grand Junction Geological Society, 1983 Field Trip, p. 73–80.
- Craig, L.C., 1981, Lower Cretaceous rocks southwestern Colorado and southeastern Utah, in Geology of the Paradox Basin: Rocky Mountain Association of Geologists, p. 195–200.
- Davis, G.H., 1999, Structural geology of the Colorado Plateau region of southern Utah, with special emphasis on deformation bands: Geological Society of America Special Paper 342, 157 p.
- Dubiel, R.S., 1992, Sedimentology and depositional history of the Upper Triassic Chinle Formation in the Uinta, Piceance, and Eagle basins, northwestern Colorado and Northeastern Utah, in Evolution of sedimentary basins—Uinta and Piceance basins: U.S. Geological Survey Bulletin 1787–W, p. W1–W25.
- Dubiel, R.S., 1994, Triassic deposystems, paleogeography, and paleoclimate of the western interior, in Caputo, M.V., Peterson, J.A., and Franczyk, K.J., eds., Mesozoic Systems of the Rocky Mountain Region, USA: Rocky Mountain Section of Society of Economic Paleontologists and Mineralogists (Society for Sedimentary Geology), p. 133–168.
- Dunham, R.J., 1962, Classification of carbonate rocks according to depositional textures, in Ham, W.E., ed., Classification of Carbonate Rocks: American Association of Petroleum Geologists Memoir 1, p. 108–121.
- Ekdale, A.A., Bromley, R.G., and Pemberton, S.G., eds., 1984, Ichnology: the use of trace fossils in sedimentology and stratigraphy: Society of Economic Paleontologists and Mineralogists, Short Course Notes 15, 317 p.
- Erslev, E.A., 1991, Trishear fault-propagation folding: Geology, v. 19, p. 617–620.
- , 1993, Thrusts, backthrusts, and detachment of Rocky Mountain foreland arches, in Schmidt, C.J., Chase, R.B., and Erslev, D.A., eds., Laramide Basement Deformation in the Rocky Mountain Foreland of the Western United States: Boulder, Colorado, Geological Society of America Special Paper 280, p. 339–358.
- Erslev, E.A., Kellogg, K.S., Bryant, B., Ehrlich, T.K., Holdaway, S.M., and Naeser, C.W., 1999, Laramide to Holocene structural developments of the northern Colorado Front Range, in Lageson, D.R., Lester, A.P., and Trudgill, B.D., eds., Colorado and Adjacent Areas: Boulder, Colo., Geological Society of America Field Guide 1, p. 21–40.
- Erslev, E.A., and Rogers, J.L., 1993, Basement-cover geometry of Laramide fault-propagation folds, in Schmidt, C.J., Chase, R.B., and Erslev, D.A., eds., Laramide Basement Deformation in the Rocky Mountain Foreland of the Western United States: Boulder, Colorado, Geological Society of America Special Paper 280, p. 125–146.
- Erslev, E.A., and Selvig, Bjorn, 1997, Thrusts, backthrusts and triangular zones: Laramide deformation in the northeastern margin of the Colorado Front Range, in Bolyard, D.W., and Sonnenberg, S.A., eds., Geologic History of the Colorado Front Range: Denver, Colorado, Rocky Mountain Association of Geologists, p. 65–76.
- Fleming, R.F., 1994, Cretaceous pollen in Pliocene rocks: Implications for Pliocene climate in the southwestern United States: Geology, v. 22, p. 787–790.
- Folk, R.L., 1974, Petrology of sedimentary rocks: Austin, Texas, Hemphill Publishing Co., 182 p.
- Fryberger, S.G., Krystnik, L.F., and Schenk, C.J., 1990, Tidally flooded back-barrier dunefield, Guerrero Negro area, Baja California, Mexico: Sedimentology, v. 37, p. 23–44.
- Fouch, T.D., Lawton, T.F., Nichols, D.J., Cashion, W.B., and Cobban, W.A., 1983, Patterns and timing of synorogenic sedimentation in Upper Cretaceous rocks of central and northeast Utah, in Reynolds, M.W., and Dolly, E.D., eds., Mesozoic Paleogeography of the West-Central United States: Denver, Rocky Mountain Section of the Society of Economic Paleontologists and Mineralogists Rocky Mountain Paleogeography Symposium 2, p. 305–336.
- Gannett, Henry, 1882, The Unaweep Canyon [Colorado]: Popular Scientific Monthly, v. 20, 781–786.
- Geological Society of America, 1999, Geological time scale: Boulder, Geological Society of America.
- Gile, L.H., Peterson, F.F., and Grossman, R.B., 1966, Morphological and genetic sequences of carbonate accumulation in desert soils: Soil Science, v. 101, p. 347–360.
- Guthrie, R.L., and Witty, J.E., 1982, New designations for soil horizons and layers and the new Soil Survey Manual: Soil Science Society of America Journal, v. 46, p. 443–444.
- Hansen, W.R., ed., 1991, Suggestions to Authors of the Reports of the United States Geological Survey, Seventh Edition: Washington, D.C., U.S. Government Printing Office, 289 p.
- Hansen, W.R., and Peterman, Z.E., 1968, Basement-rock geochronology of the Black Canyon of the Gunnison, Colorado: U.S. Geological Survey Professional Paper 600–C, p. C80–C90.
- Hedge, C.E., Peterman, Z.E., Case, J.E., and Obradovich, J.D., 1968, Precambrian geochronology of the northwestern Uncompahgre Plateau, Utah and Colorado: U.S. Geological Survey Professional Paper 600–C, p. C91–C96.
- Heyman, O.G., 1983, Distribution and structural geometry of faults and folds along the northwestern Uncompahgre uplift, western Colorado and eastern Utah: Grand Junction, Colorado, Grand Junction Geological Society 1983 field trip, p. 45–57.
- Heyman, O.G., Hunto, P., and White-Heyman, M., 1986, Laramide deformation of the Uncompahgre Plateau—Geometry and Mechanisms, in Stone, D.S., ed., New Interpretations of Northwest Colorado Geology: Rocky Mountain Association of Geologists Guidebook, p. 65–76.
- Hunt, C.B., 1956a, Cenozoic Geology of the Colorado Plateau: U.S. Geological Survey Professional Paper 279, 99 p.
- , 1956b, Geology of the Taylor site, Unaweep Canyon, Colorado, in Archeological investigations on the Uncompahgre Plateau in west central Colorado: Denver Museum of Natural History Proceedings, no. 2, p. 64–69.
- Ingram, R.L., 1954, Terminology for the thickness of stratification and parting units in sedimentary rocks: Geological Society of America Bulletin, v. 65, p. 937–938.

- Izett, G.A., and Wilcox, R.E., 1982, Map showing localities and inferred distributions of the Huckleberry Ridge, Mesa Falls, and Lava Creek ash beds (Pearlette family ash beds) of Pliocene and Pleistocene age in the Western United States and Southern Canada: U.S. Geological Survey Miscellaneous Investigations Series Map I-1325, scale 1:4,000,000.
- Jamison, W.R., 1979, Laramide deformation of the Wingate Sandstone, Colorado National Monument: A study of cataclastic flow: College Station, Texas, unpublished dissertation, Texas A&M University, 170 p.
- Jamison, W.R., and Stearns, 1982, Tectonic deformation of Wingate Sandstone, Colorado National Monument: American Association of Petroleum Geologists Bulletin, v. 66, p. 2584–2608.
- Kellogg, K.S., Schmidt, C.J., and Young, S.W., 1995, Basement and cover-rock deformation during Laramide contraction in the northern Madison Range (Montana) and its influence on Cenozoic Basin Formation: American Association of Petroleum Geologists Bulletin, v. 79, no. 8, p. 1117–1137.
- Kocurek, Gary, and Dott, R.H., Jr. 1983, Jurassic paleogeography and paleoclimate of the central and southern Rocky Mountains region, in Reynolds, M.W., and Dolly, E.D., eds., Mesozoic Paleogeography of the West-Central United States, Rocky Mountain Paleogeography, Symposium 2: Denver, Colo., Rocky Mountain Section, Society of Economic Paleontologists and Mineralogists, 101–116.
- Kowallis, B.J., Christiansen, E.H., and Deino, A.L., 1991, Age of the Brushy Basin Member of the Morrison Formation, Colorado Plateau, western USA: Cretaceous Research, v. 12, p. 483–493.
- Kowallis, B.J., Christiansen, E.H., and Deino, A.L., Peterson, Fred, Turner, C.E., Kunk, M.J., and Obradovich, J.D., 1998, The age of the Morrison Formation: Modern Geology, v. 22, p. 235–260.
- Land, Lewis, 1993, Three-dimensional characterization of basement faults and forced folds in clastic rocks along the northeastern edge of the Uncompahgre Plateau, western Colorado: Norman, Oklahoma, unpublished thesis, University of Oklahoma, 129 p.
- Lohman, S.W., 1961, Abandonment of Unaweep Canyon, Mesa County, Colorado, by capture of the Colorado and Gunnison Rivers: Article 60 in U.S. Geological Survey Professional Paper 424-B, p. B144–B146.
- 1963, Geologic map of the Grand Junction area, Colorado: U.S. Geological Survey Miscellaneous Investigations Series Map I-404, scale 1:31,680.
- 1965, Geology and Artesian Water Supply, Grand Junction Area, Colorado: U.S. Geological Survey Professional Paper 451, 149 p.
- 1981, The geologic story of Colorado National Monument: U.S. Geological Survey Bulletin 1508, 142 p.
- Marvin, R.F., Mehnert, H.H., and Montjoy, W.M., 1966, Age of the basalt cap on Grand Mesa, in Geological Survey Research 1966: U.S. Geological Survey Professional Paper 550-A, p. A81.
- McKee, E.D., and Weir, G.W., 1953, Terminology for stratification and cross-stratification in sedimentary rocks: Geological Society of America Bulletin, v. 64, p. 381–390.
- Miller, D.M., Nilsen, T.H., and Bilodeau, W.L., 1992, Late Cretaceous to early Eocene geologic evolution of the U.S. Cordillera, in Burchfiel, B.C., Lipman, P.W., and Zoback, M.L., eds., The Cordilleran Orogen: Cotermittent U.S.: Boulder, Colorado, Geological Society of America, The Geology of North America, v. G-3, p 205–260.
- Munsell Color, 1973, Munsell soil color charts: Baltimore, Md., Kollmorgen Corp., Macbeth Division.
- Oesleby, T.W., 1983, Geophysical measurement of valley fill thickness, Unaweep Canyon, West Central Colorado: Grand Junction Geological Society, 1983 Field Trip, p. 71–72.
- O'Sullivan, R.B., 1980, Stratigraphic sections of Middle Jurassic San Rafael Group and related rocks from the Green River to the Moab area in east-central Utah: U.S. Geological Survey Miscellaneous Field Studies Map MF-1247.
- O'Sullivan, R.B., 1992, The Jurassic Wanakah and Morrison Formations in the Telluride-Ouray-Western Black Canyon Area of southern Colorado: U.S. Geological Survey Bulletin 1927, 24 p.
- O'Sullivan, R.B., and Pipiringos, G.N., 1983, Stratigraphic sections of Middle Triassic Entrada Sandstone and related rocks from Dewey Bridge, Utah, to Bridgeport, Colorado: U.S. Geological Survey Oil and Gas Investigations Chart OC-122.
- Padian, K., 1989, Presence of dinosaur Scelidosaurus indicates Jurassic age for the Kayenta Formation (Glen Canyon Group, northern Arizona): Geology, v. 17, p. 438–441.
- Peale, A.C., 1877, Report on the Grand River district, Colorado: U.S. Geological and Geographical Survey of the Territories, 9<sup>th</sup> Annual Report, p. 31–101.
- Pemberton, S.G., MacEachern, J.A., and Frey, R.W., 1992, Trace fossil facies models: environmental and allostratigraphic significance, in Walker, R.G., and James, N.P., eds., Facies Models, Response to Sea Level Change: Geological Association of Canada, p. 47–72.
- Peterson, Fred, 1994, Sand dunes, sabkhas, streams, and shallow seas: Jurassic paleogeography in the southern part of the Western Interior, basin, in Caputo, M.V., Peterson, J.A., and Franczyk, K.J., eds., Mesozoic Systems of the Rocky Mountain Region, USA: Rocky Mountain Section of Society of Economic Paleontologists and Mineralogists (Society for Sedimentary Geology), p. 233–272.
- Peterson, Fred, 1988a, Stratigraphy and nomenclature of Middle and Upper Jurassic rocks, western Colorado Plateau, Utah and Arizona, in Revisions to stratigraphic nomenclature of Jurassic and Cretaceous rocks of the Colorado Plateau: U.S. Geological Survey Bulletin 1633-B, p. 17–56.
- Peterson, Fred, 1988b, Pennsylvanian to Jurassic eolian transport systems in the western United States: Sedimentary Geology, v. 56, p. 207–260.
- Peterson, Fred, and Pipiringos, G.N., 1979, Stratigraphic relationships of the Navajo Sandstone to Middle Jurassic formations in parts of southern Utah and northern Arizona: U.S. Geological Survey Professional Paper 1035-B, p. B1–B43.
- Peterson, Fred, and Turner, C.E., 1998, Stratigraphy of the Ralston Creek and Morrison Formations (Upper Jurassic) near Denver, Colorado: Modern Geology, v. 22, p. 3–38.
- Pettijohn, F.J., Potter, P.E., and Siever, R., 1973, Sand and Sandstone: New York, Springer-Verlag, 553 p.
- Phillips, W.A., 1986, Cobble aquifer investigation: Colorado River Basin Salinity Control Project: Grand Junction, Colorado, Grand Junction Office, U.S. Bureau of Reclamation, 20 p.
- Picard, M.D., 1971, Classification of fine-grained sedimentary rocks: Journal of Sedimentary Petrology, v. 41, p. 179–195.
- Piety, L.A., 1981, Relative dating of terrace deposits and tills in the Roaring Fork Valley, Colorado: Boulder, University of Colorado, M.S. thesis, 209 p.
- Pipiringos, G.N., and O'Sullivan, R.B., 1978, Principal unconformities in Triassic and Jurassic rocks, Western Interior United States—A preliminary survey: U.S. Geological Survey Professional Paper 1035-A, 29 p.

- Potter, P.E., Maynard, J.B., and Pryor, W.A., 1980, Sedimentology of shale: New York, New York Springer-Verlag, 306 p.
- Powers, M.C., 1953, A new roundness scale for sedimentary particles: *Journal of Sedimentary Petrology*, v. 23, p. 117–119.
- Reed, J.C., Jr., Bickford, M.E., Premo, W.R., Aleinikoff, J.N., and Pallister, J.S., 1987, Evolution of the Early Proterozoic Colorado province: Constraints from U-Pb geochronology: *Geology*, v. 15, p. 861–865.
- Richmond, G.M., and Fullerton, D.S., 1986, Introduction to Quaternary glaciations in the United States of America, in Sibrava, V., Bowen, D.O., and Richmond, G.M., eds., *Quaternary Glaciations in the Northern Hemisphere: Quaternary Science Reviews*, v. 5, p. 3–10.
- Rock-Color Chart Committee, 1951, Rock-Color Chart: Boulder, Colo., Geological Society of America.
- Scott, R. B., Carrara, P.E., Hood, W.C., and Murray, K.E., [in press], Geologic Map of the Grand Junction quadrangle, Mesa County, Colorado: U.S. Geological Survey Miscellaneous Field Studies Map, scale 1:24,000.
- Scott, R.B., Hood, W.C., Johnson, James, Tausch, Robin, Sexton, T.O., Perrotti, Patrick, 1999, Charcoal record in sediments and fire ecology history of piñon-juniper uplands of the Uncompahgre uplift, western Colorado: *Geological Society of America Abstracts with Programs*, v. 31, no. 7, p. A-482–483.
- Scott, R.B., Lidke, D.J., Hudson, M.R., Perry, W.J., Jr., Bryant, Bruce, Kunk, M.J., Budahn, J.R., and Byers, F.M., Jr., 1999, Active evaporite tectonics in the Eagle River valley and the southwestern flank of the White River uplift, Colorado, in Lageson, D.R., Lester, A.P., and Trudgill, B.D., eds., *Colorado and Adjacent Areas*: Boulder, Colorado, Geological Society of America Field Guide 1, p. 97–114.
- Scott, R.B., and Shroba, R.R., 1997, Revised preliminary geologic map of the New Castle quadrangle, Garfield County, Colorado: U.S. Geological Survey Open-File Report 97-737, scale 1:24,000.
- Shroba, R.R., 1994, Quaternary loess stratigraphy along the Colorado River between Glenwood Springs and Rifle, Colorado—Preliminary findings: American Quaternary Association, 13<sup>th</sup> Biennial Meeting, Minneapolis, Minn., Abstracts, p. 24.
- Shroba, R.R., and Scott, R.B., 1997, Revised preliminary geologic map of the Rifle quadrangle, Garfield County, Colorado: U.S. Geological Survey Open-File Report 97-852, scale 1:24,000.
- Soil Survey Staff, 1975, Soil taxonomy: U.S. Department of Agriculture Handbook 436, 754 p.
- Stearns, D.W., and Jamison, W.R., 1977, Deformation of sandstones over basement uplifts, Colorado National Monument, in Veal, H.D., ed., *Exploration Frontiers of the Central and Southern Rockies*: Denver, Colorado, Rocky Mountain Association of Geologists, 1977 Symposium, p. 31–39.
- Steven, T.A., Hon, K., and Lanphere, M.A., 1995, Neogene geomorphic evolution of the central San Juan Mountains near Creede, Colorado: U.S. Geological Survey Miscellaneous Investigations Series Map I-2504.
- Steven, T.A., Evanoff, Emmett, and Yuhas, R.H., 1997, Middle and late Cenozoic tectonic and geomorphic development of the Front Range of Colorado, in Bolyard, D.W., and Sonnenberg, S.A., eds., *Geologic History of the Colorado Front Range*: Denver, Colo., Rocky Mountain Association of Geologists, 1997 RMS—AAPG Field Trip #7, p. 115–124.
- Streckeisen, A.L., 1973, Plutonic rocks, classification and nomenclature recommended by the IUGS subcommittee on the systematics of igneous rocks: *Geotimes*, v. 18, no. 10, p. 25–29.
- Stone, D.S., 1977, Tectonic history of the Uncompahgre uplift, in *Exploration Frontiers of the Central and Southern Rockies—1977 Symposium: Rocky Mountain Association of Geologists*, p. 23–30.
- Stuiver, Minze, Reimer, P.J., Bard, Edouard, Beck, J.W., Burr, G.S., Hughen, K.A., Kromer, Bernd, McCormac, Gerry, van der Plicht, Johannes, and Spurk, Marco, 1998, Intcal98 radiocarbon age calibration, 24,000–0 cal BP: *Radiocarbon*, v. 40, no. 3, p. 1041–1083.
- Turner, C.E., and Fishman, N.S., 1991, Jurassic Lake T'oo'dichi'. A large alkaline, saline lake, Morrison Formation, eastern Colorado Plateau: *Geological Society of America Bulletin*, v. 103, p. 538–558.
- Varnes, D.J., 1978, Slope movement types and process, in Schuster, R.L., and Krizek, R.J., eds., *Landslides, analysis, and control*: National Academy of Sciences, Transportation Research Board Special Report 176, p. 11–33.
- Wentworth, C.K., 1922, A scale of grade and class terms for clastic sediments: *Journal of Geology*, v. 30, p. 377–392.
- White, M.A., and Jacobson, M.I., 1983, Structures associated with the southwest margin of the Ancestral Uncompahgre uplift: Grand Junction, Colo., Grand Junction Geological Society 1983 field trip, p. 33–39.
- Whitney, J.W., Piety, L.A., and Cressman, S.L., 1983, Alluvial history in the White River basin, northwest Colorado: *Geological Society of America Abstracts with Programs*, v. 15, no. 5, p. 328.
- Williams, P.L., 1964, Geology, structure, and uranium deposits of the Moab quadrangle, Colorado and Utah: U.S. Geological Survey Miscellaneous Investigations Series Map I-360, scale 1:100,000.
- Willis, G.C., 1994, Geologic map of the Harley dome quadrangle, Grand County, Utah: Utah Geological Survey Map M-157, scale 1:24,000.
- Ye, Hongzhan, Royden, Leigh, Burchfiel, Clark, and Schuepbach, Martin, 1996, Late Paleozoic deformation of interior North America: The greater ancestral Rocky Mountains: *American Association of Petroleum Geologists Bulletin*, v. 80, p. 1397–1432.
- Young, R.G., 1959, Cretaceous deposits of the Grand Junction area, Garfield, Mesa, and Delta Counties, Colorado: *Rocky Mountain Association of Geologists*, 11<sup>th</sup> field conference, p. 17–25.

## Glossary

This glossary contains geological words and combinations of words not found in common dictionaries, for example, Webster's New World Dictionary, Third College Edition, 1988, Simon & Schuster, Inc. Words that are italicized in the text are included in this glossary. Most of the definitions were simplified and modified from the *Glossary of Geology*, Fourth Edition, published by the American Geological Institute, 1997; used with their permission.

*anhedral* Form of a crystal that does not display its crystal faces.

*antecedent river* A river that maintains its course as the underlying rocks are deformed; in this case, cutting a canyon as the Uncompahgre Plateau is uplifted and arched.

*antithetic fault* A fault that is secondary to a major fault, formed at the same time as the major fault, but is oriented at a high angle to the major fault, and has a sense of offset opposite that of the major fault.

*<sup>40</sup>Ar/<sup>39</sup>Ar method* A radiometric dating technique based on the rate of decay of radioactive isotopes of potassium and argon daughter products.

- Archean** The oldest Eon recorded in rocks on Earth, between 2,500 and 3,800(?) Ma.
- asymmetric ripple lamination, ripple stratification, or ripple marks** *Ripple lamination, ripple stratification, or ripple marks* that are not symmetrical; implies current transport.
- attenuation** A process of thinning; in this case, thinning of strata caused by folding.
- attitude** The structural position of rock layers or structures in space; determined by measurement of *strike* and *dip* of planar features such as bedding or faults.
- balanced cross sections** Cross sections that restore strata to their original geometry after offsets on faults and folds are removed.
- batholith** An igneous intrusion displaying greater than 100 km<sup>2</sup> of exposure. (See *stock* for contrast).
- bearing capacity** The maximum weight that ground can support without failing by shear.
- bioturbated** Description of bedding that has been disturbed by biological activity such as burrowing.
- boudin** A sausage-shaped pod of metamorphic rock encased in surrounding metamorphic rock *matrix*.
- bounding surface** An erosional surface that truncates and separates groups of *cross-beds*.
- braided streams or braided-river systems** Streams or rivers with anastomosing, or *braided*, patterns of water courses.
- <sup>14</sup>C dating** A radiometric dating technique based on the rate of radioactive decay of <sup>14</sup>C, an isotope of carbon.
- calc-alkalic** A chemical group of igneous rocks in which the SiO<sub>2</sub> weight percent is between 56 and 61 and the CaO and Na<sub>2</sub>O + K<sub>2</sub>O weight percents are equal to each other. Commonly rocks of this chemistry are indicative of continental margin magmatism.
- calc-silicate** A metamorphic rock that contains Ca-rich silicate minerals, such as epidote, diopside, tremolite, actinolite, and grossularite (Ca garnet), and that was probably originally Ca-rich sediments.
- cataclastic flow** Deformation of rock caused by intergranular movement of particles relative to one another.
- charophyte** A fresh-water green algae.
- cienaga-type deposits** Deposits formed in marshy areas in arid climates.
- clast** Rock fragment greater than 2 mm in diameter.
- clast supported** A sediment or soil in which there are sufficient *clasts* so that *clasts* rest on one another and therefore support the weight of overlying material.
- climbing dunes** Dunes banked against the windward side of a topographic rise.
- colluvial deposits** Any deposits consisting of loose, heterogeneous, and incoherent masses of rock fragments and (or) finer sediment that were emplaced by *mass wasting* at or near the base of slopes.
- comagmatic** Igneous rocks that were derived from a common parent magma.
- combined flow ripple marks, combined ripple marks, or cross-ripple marks** Combination of current and wave action; for example, longshore drift. These conditions produce a complex pattern of ripple marks.
- concordant date** Radiometric dates for minerals by two or more methods that are in agreement; for example, indistinguishable dates based on different U and Pb isotopes.
- cross-beds, cross-bedded, cross-bedding** Beds inclined at an angle relative to the main bedding planes.
- cross-lamination or cross-stratification** Laminations (less than 1 cm thick) or stratification (no thickness restriction) in sandstone or siltstone that have *cross-beds*.
- current-ripple lamination** Laminations (less than 1 cm thick) that display asymmetric ripple marks.
- debris-flow deposits** Deposits emplaced as a flowing mass, consisting of rock fragments and finer sediment, of which more than half the particles are coarser than sand.
- desert varnish** A coating of iron and other oxides found on rock fragments after prolonged exposure in deserts.
- diagenetic alteration** Any physical, chemical, or biological changes in sediment after deposition.
- dip** Inclination of beds or faults measured from horizontal; perpendicular to *strike*.
- dipslope** A slope that is underlain by strata that *dip* in the same general direction and amount as the slope.
- disconformably; disconformity** Pertaining to a *disconformity*, an unconformity or break in deposition between parallel strata.
- discordant** A contact between an igneous intrusion and country rock that is not parallel to the foliation or bedding of the country rock.
- discordant U/Pb date** Radiometric dates for a mineral by two or more methods that result in different dates for each method; for example, different dates for different U and Pb isotopes.
- downlap depositional sequence** A depositional sequence where each succeeding younger layer terminates against the base of the sequence, where progressively younger layers are found farther down the depositional gradient.
- drape fold** A fold that appears to have been draped over a fault in underlying rocks; such folds are more correctly called *fault propagation folds*.
- euhedral** Form of a crystal that has all its crystal faces.
- even-parallel lamination** Laminae that are nearly the same thickness and parallel in strata that contain sedimentary structures indicative of deposition by flowing wind or water.
- expansive clay, soils, surficial deposits, or bedrock** Clay, soil, surficial deposits, or bedrock units that contain *smectitic clay* that expands when wet and shrinks when dry.
- fan-alluvium** Alluvial deposits that form a fan-like shape.
- fault propagation fold** A fold that formed above the end of a fault.
- flaggy** Having the character of splitting into layers about 1 to 5 cm thick; similar to flagstone.

- grain-flow lamination* Lamination inclined at the angle of repose on the leeward side of a dune and formed by sand avalanches.
- gypsiferous* Containing the mineral gypsum.
- hanging wall* The block of rock above a fault.
- heterolithic* Consisting of several rock types.
- high-angle reverse fault* A fault that dips more than 45° and places older rocks above younger rocks.
- hinge line* Trace of the line that marks distinct changes in dip of strata.
- horizontal lamination:* Lamination that was deposited parallel to the earth's surface.
- hornfels* A fine-grained rock metamorphosed by heat from an igneous body.
- hydrocompaction* Any water-induced decrease in volume, causing subsidence of the ground surface. *Hydrocompaction* is produced by compaction of particles and (or) the dissolution and collapse of rock fragments or *matrix* material. This compaction results in surface or near-surface collapse.
- inflection hinge line* Trace of the line that marks the change from a concave-shaped fold to a convex-shaped fold.
- intergranular flow* Deformation of a rock caused by the flow of grains relative to one another.
- kinematics* In geology, the study of the direction that rock moves during faulting or folding.
- lag gravel* A coarse gravelly deposit left after wind or water removed finer sediments.
- lamination, lamellae* Layers of rock that are less than 1 cm thick.
- lamprophyre* A dark-colored intrusive rock that generally forms a dike and commonly contains phenocrysts of biotite, hornblende, and pyroxene in a fine-grained *matrix*.
- laterally and vertically amalgamated scour surfaces* Large-scale (few to tens of meters) scour surfaces that truncate each other in both horizontal and vertical directions. Commonly formed by *braided* and meandering rivers and migrating dunes.
- lithic arkose* An arkose that contains abundant rock fragments.
- mass wasting* Transport of soil or rock downslope by the force of gravity.
- matrix* The fine-grained material between coarser-grained *clasts* in a sediment or soil or between coarse crystals in an igneous or metamorphic rock.
- matrix supported* A sediment or soil in which there is sufficient *matrix* so that *clasts* within the *matrix* do not rest on one another and therefore the *matrix* supports the weight of overlying material.
- migmatitic, migmatite, migmatization* Having the character of a *migmatite*; a metamorphic rock that has been partially melted to form a feldspar- and quartz-rich granitic part and an unmelted residue rich in dark minerals such as biotite and hornblende; the process of forming a *migmatite*.
- monoclinal fold, monocline* A fold that forms an inclined plane of strata between areas of nearly horizontal strata.
- normal fault* A fault that generally dips 45° to 90° and places younger rocks over older rocks.
- normally graded* Deposits that display *clasts* that gradually decrease in size upwards.
- oscillation-flow ripple marks* or *oscillation ripple marks* Symmetrical ripple marks caused by waves that washed grains back and forth.
- packstone* A sedimentary carbonate rock that has its grains arranged in a grain-supported framework.
- paleosols* Ancient buried soils or soil horizons.
- palynological* Pertaining to the science of the study of pollen, in this case fossil pollen.
- parting lineations* Lineations consisting of ridges or grooves formed parallel to current direction.
- Pennsylvanian* A period in the Paleozoic Era between 290 and 330(?) Ma.
- Permian* A period in the Paleozoic Era between about 240 and 290 Ma.
- piping* Subsurface erosion of sand and finer material by percolating water, resulting in the formation of voids and conduits about a few centimeters to a few to several meters wide. These cavities can result in surface collapse.
- plate margin* Edge of relatively rigid slabs of the earth's lithosphere called plates.
- porphyroblasts* Coarse crystals in a fine-grained metamorphic rock *matrix*.
- Precambrian* The part of geologic time before the Paleozoic Era (greater than about 570 million years ago).
- protolith* The parent rock prior to that rock becoming metamorphosed.
- ptygmatic fold* Folds of granitic material in a metamorphic rock. *Ptygmatic folds* have shapes that are dissimilar to other structures in the rock.
- Rb/Sr isochron age* The age of a geological event measured by the rubidium-strontium radiometric dating method.
- rhizocretions* Fossil roots.
- ripple lamination, current-ripple lamination, wind-ripple lamination* A sedimentary structure found in sand or silt that consists of ripple mark layers less than 1 cm thick.
- ripple stratification* A sedimentary feature in sand or silt that consists of layers of ripple marks.
- schistosity* Foliation in schist or other crystalline rock formed by the parallel alignment of platy minerals.
- scour-and-fill structures and scour surfaces:* Wavy bedding surfaces formed by erosion by water or wind.
- sheetwash deposits* Material transported and deposited on low-gradient slopes by water that is not confined to channels; considered to be a *colluvial deposit* in this report.
- sigmoidal cross-bedding* Cross-beds with S-shaped beds.
- slickenlines* Grooves and ridges formed as rock on one side of a fault grinds against rock on the other side.
- smectite, smectitic clay* A clay mineral that swells when wet and shrinks when dry; an *expansive clay*.
- stock* An igneous intrusion less than 100 km<sup>2</sup> in area.

<i>strain</i>	The change in shape of rock during deformation caused by stress applied to the rock.	<i>tabular-planar cross-stratification</i>	A set of planar <i>cross-beds</i> or laminae that are truncated on top and bottom by parallel surfaces.
<i>streaming lineations</i>	Faint streaks or lines on bedding surfaces produced by oriented elongate sand grains.	<i>tabular-tangential cross-stratification</i>	A set of curved <i>cross-beds</i> or laminae that are truncated by parallel surfaces.
<i>strike</i>	The compass direction of the horizontal trace of a planar feature such as bedding or a fault.	<i>trough cross-stratification</i>	A set of curved <i>cross-beds</i> or laminae that are truncated on top and bottom by curved surfaces.
<i>structural relief</i>	The amount of vertical offset on a stratigraphic horizon created by a folding or a faulting process.	<i>underfit streams</i>	Streams that appear too be to small to have eroded the valley in which they flow.
<i>structure contours</i>	Contours drawn on a specific stratigraphic horizon that show the shapes of structures.	<i>wackestone</i>	A mud-supported carbonate sedimentary rock containing more than 10% grains.
<i>subarkose</i>	A quartz-rich sedimentary rock that has < 25% feldspar, whereas an arkose has > 25% feldspar.	<i>wedge-planar cross-stratification</i>	A set of planar <i>cross-beds</i> or laminae that are truncated on top and bottom by surfaces that are not parallel to one another.
<i>subhedral</i>	Form of a crystal that has only some of its crystal faces.	<i>wind-ripple lamination</i>	Layering in eolian sandstone that resembles “pinstripes” caused by migration of wind ripples across an interdune surface.
<i>symmetric ripple lamination</i> or <i>ripple stratification</i>	<i>Ripple lamination</i> or <i>ripple stratification</i> that has a symmetric shape; implies wave action.		

