

UNITED STATES DEPARTMENT OF THE INTERIOR
U.S. GEOLOGICAL SURVEY

Operations Plan for the Southern California Integrated GPS Network,
Fiscal Year 1996

By

SCIGN Coordinating Board¹

Open-File Report 96-283

¹William Prescott (USGS), Yehuda Bock (UCSD), Ken Hudnut (USGS), Mike Watkins (JPL), Duncan Agnew (University of California, San Diego), Andrea Donnellan (JPL), Larry Fenske (CalTrans), Brad Hager (Massachusetts Institute of Technology), David Jackson (University of California, Los Angeles), Jim Mori (USGS), Don D'Onofrio (NOAA/National Geodetic Survey), Bill Young (Riverside County, California), Frank Webb (JPL), and Frank Wyatt (UCSD)

This report is preliminary and has not been reviewed for conformity with U.S. Geological Survey editorial standards or with the North American Stratigraphic Code. Any use of trade, firm, or product names is for descriptive purposes only and does not imply endorsement by the U.S. Government.

FY96 SCIGN Operations Plan

2 May 1996

13 June 1996—Appendices B-1, B-2 updated
5 July 1996—Receiver contingency excised

Southern California Integrated GPS Network

William Prescott Chairman (USGS)

Executive Committee

Yehuda Bock (UCSD)

Ken Hudnut (USGS)

Mike Watkins (JPL, California Institute of Technology)

plus Chairman

Coordinating Board

Duncan Agnew (UCSD)

Andrea Donnellan (JPL, California Institute of Technology)

Larry Fenske (CalTrans)

Brad Hager (Massachusetts Institute of Technology)

David Jackson (University of California, Los Angeles)

Jim Mori (USGS)

Don D'Onofrio (NOAA/National Geodetic Survey)

Bill Young (Riverside County, California)

Frank Webb (JPL, California Institute of Technology)





plus Executive Committee

Other Contributors

Frank Wyatt (UCSD)

Approvals

The following agency/institution representatives have read this operating plan and agree in principle with the outlined plan. Signatures on this page do not commit any of the agencies/institutions to the detailed budgets included in the plan.

| | | |
|------------------------------|---|------------------------------|
| SCEC Science Director |  David D. Jackson | <u>4/26/96</u> Date |
| SCEC Center Director |  Thomas L. Henyey | <u>4/26/96</u> Date |
| JPL Program Manager |  Charles Elachi | <u>4-26-96</u> Date |
| USGS Regional Coordinator |  James J. Mori | <u>4/25/96</u> Date |
| SIO Director |  Edward A. Frieman | <u>4/29/96</u> Date |
| SCIGN Chair |  William H. Prescott | <u>25 April 1996</u> Date |

| | |
|---|-----------|
| SOUTHERN CALIFORNIA INTEGRATED GPS NETWORK..... | 2 |
| Executive Committee..... | 2 |
| Coordinating Board..... | 2 |
| Other Contributors..... | 2 |
| APPROVALS..... | 3 |
| EXECUTIVE SUMMARY..... | 7 |
| <i>Background</i> | 7 |
| <i>Timetable for SCIGN Expansion</i> | 8 |
| BUDGET | 9 |
| COST-SHARING | 11 |
| OUTYEAR PLANS..... | 13 |
| IMPLEMENTATION..... | 13 |
| <i>Introduction</i> | 13 |
| <i>Receiver purchase</i> | 14 |
| Preferred Receiver Purchase Plan..... | 14 |
| <i>Site selection and permitting</i> | 14 |
| <i>Site construction</i> | 16 |
| <i>Receiver maintenance</i> | 17 |
| <i>Network coordinator</i> | 17 |
| GLOSSARY | 17 |
| APPENDICES..... | 18 |
| <i>Introduction to Appendices A, B and C</i> | 18 |
| APPENDIX A — SITE SELECTION AND PERMITTING SPECIFICATIONS..... | 18 |
| <i>Introduction</i> | 18 |
| <i>Definitions</i> | 19 |
| <i>Interface with SCIGN committee</i> | 19 |
| <i>Contract requirements</i> | 19 |
| Site Selection..... | 19 |
| Sky view and multipath..... | 19 |
| Permanence..... | 20 |
| Security & Safety..... | 20 |
| Site geology..... | 20 |
| Access..... | 21 |
| Power..... | 21 |
| Communications..... | 21 |
| Permission..... | 21 |
| Landuse fees..... | 22 |
| Receiver occupation test..... | 22 |
| DigAlert..... | 22 |
| Site description..... | 22 |
| Contractor qualifications..... | 22 |
| Supervision..... | 23 |
| APPENDIX B — SITE CONSTRUCTION SPECIFICATIONS..... | 23 |

| | |
|---|-----------|
| <i>Introduction</i> | 23 |
| <i>Contract requirements</i> | 23 |
| APPENDIX B-1 — DEEPLY ANCHORED MONUMENTS - CONSTRUCTION PROCEDURES | 24 |
| <i>Preparation of casing: (2.06)</i> | 24 |
| <i>Geology/Hydraulic Crawlers: (2.01)</i> | 24 |
| <i>Layout/Alignment of drill rig: (5.03)</i> | 25 |
| <i>Casing Setting: (5.05)</i> | 26 |
| <i>Testing the Holes: (5.06)</i> | 26 |
| <i>Centralizers: (5.07)</i> | 28 |
| <i>Assy. of Pipe: (5.08)</i> | 28 |
| <i>Aligning the Pipes: (5.09)</i> | 29 |
| <i>Grouting: (5.10)</i> | 29 |
| <i>Welding: (5.11)</i> | 31 |
| <i>Pipe Finishing - Painting: (5.12)</i> | 31 |
| <i>Adaptor and Reference Height: (5.13/5.14)</i> | 31 |
| <i>Enclosure (7.02)</i> | 33 |
| APPENDIX B-2—SPECIFICATIONS FOR A DEEPLY ANCHORED AND BRACED GEODETIC MONUMENT (DRILLED AND GROUTED) | 33 |
| <i>1. Introduction</i> | 33 |
| <i>2. Drilling</i> | 34 |
| <i>3. Casing</i> | 34 |
| <i>4. Pipe</i> | 35 |
| <i>5. Pipe Insertion and Alignment</i> | 35 |
| <i>6. Grout and Grouting</i> | 35 |
| <i>7. Welding</i> | 36 |
| <i>8. Finishing</i> | 36 |
| <i>9. Adaptor</i> | 37 |
| <i>10. Inspection and Compliance</i> | 37 |
| APPENDIX B-3 — DRAWING INDEX -- GPS MONUMENTS | 37 |
| APPENDIX B-4 — ROCK MARK SPECIFICATIONS | 38 |
| APPENDIX B-5 — RECEIVER BOX | 38 |
| APPENDIX C — RECEIVER PLACEMENT AND MAINTENANCE | 38 |
| <i>Introduction</i> | 38 |
| <i>Contract requirements</i> | 38 |
| APPENDIX D — NETWORK COORDINATOR | 39 |
| <i>Introduction</i> | 39 |
| <i>Job announcement</i> | 39 |
| <i>Introduction</i> | 39 |
| <i>Location:</i> | 39 |
| <i>Position description</i> | 39 |
| <i>Qualifications</i> | 40 |
| <i>To apply</i> | 40 |
| APPENDIX E — FORMS | 41 |
| <i>Site evaluation</i> | 41 |
| <i>Location rejection</i> | 41 |

JPL Permission form..... 41
Station Horizon mask..... 41
APPENDIX F — NEW SITE LOCATION MAPS.....**45**

Executive Summary

We plan to expand the Southern California Integrated GPS Network (SCIGN) by the addition of about 30 new sites. This will take the network from its current size of 38 operating sites to 68 operating sites. The bulk of the funds for the current expansion will come from NASA (about \$1.4M). In addition the USGS is providing funding for operation and maintenance (about \$250K). New receivers will be purchased through the Southern California Earthquake Center (SCEC) from the Academic Research Infrastructure (ARI) price list. Permitting and construction of the new sites will be done under JPL administered contracts.

At the same time, some sites will be added to the network using receivers purchased by University investigators under the ARI procurement. We expect to have three UCSB receivers and seven UCSD receivers from this source. In addition, there are three JPL sites at varying stages in the installation process. Collectively, the 30 sites added with NASA funding plus these already-purchased-but-not-yet-installed receivers will bring the network total to 81 (=38+30+3+7+3). Farther in the future, funding for an additional 45 sites has also been requested from NSF.

SCIGN intends to operate all existing and currently funded stations for a total of five years. At the end of five years, the network will be re-evaluated and decisions about its future will be made in light of the contributions made by the network and the funding situation at that time.

To assist in melding these sites into an integrated network, SCIGN is creating the position of Network Coordinator. This position will be located at SCEC in Pasadena and will be responsible for monitoring and maintaining the entire collection of stations.

Background

In Southern California, a group of scientists from several institutions is pursuing a new approach to studying earthquake hazards. The goal of the project is to complement ongoing earthquake hazard investigations in a high-risk metropolitan area with precise deformation measurements from an array of densely spaced continuous GPS sites. To achieve high precision, the sites are being carefully monumented and all the GPS receivers will operate continuously. At present SCIGN includes 38 stations installed and operated by University of California, San Diego (UCSD), NASA's Jet Propulsion Laboratory (JPL), and the U.S. Geological Survey (USGS) (Figure 1). Funding from NASA is available to install another 30 sites and additional funding is being sought from other sources. New stations will be installed both regionally (~30 km spacing) and along three densely (spacing 1 to 3 km) instrumented profiles (A-A', B-B', and C-C' in Figure 1). All data are processed at UCSD and JPL. Discussions of the advantages of including two processing centers have been spelled out in various funding proposals. Briefly, the processing centers use different and independent processing software. The comparison and contrast in the results from the two centers will be essential in interpreting time series obtained from the network. The necessity for two processing centers will be included in the general evaluation at the end of the initial five year experiment. All data from stations in the array are available on the internet (<http://scec.gps.caltech.edu/scign.html>).

The SCIGN coordinating board includes: Will Prescott (USGS), Chairman, Duncan Agnew and Yehuda Bock (UCSD), Andrea Donnellan, Mike Watkins, and Frank Webb (JPL, California Institute of Technology), Larry Fenske (CalTrans), Brad Hager

(Massachusetts Institute of Technology), Ken Hudnut and Jim Mori (USGS), David Jackson (University of California, Los Angeles), Don D'Onofrio (National Atmospheric and Oceanic Administration/National Geodetic Survey), and Bill Young (Riverside County, California). SCIGN is organized under the auspices of the Southern California Earthquake Center (SCEC) with funding from NASA, the USGS National Earthquake Hazards Reduction Program and the National Science Foundation. The SCIGN Executive Committee consisting of Prescott, Bock, Hudnut, and Watkins makes day to day decisions regarding SCIGN. The body of this document was prepared by this committee. A site-construction subcommittee consisting of Frank Webb, Frank Wyatt, and Will Prescott prepared the some of the appendices. A subcommittee consisting of Ken Hudnut, Duncan Agnew and Andrea Donnellan prepared the maps indicating the locations of the next expansion sites.

Timetable for SCIGN Expansion

Below is a chart indicating the time schedule for the expansion. A few target dates are key:

- 1996 March 8 Draft operating plan complete and submitted to SCIGN and SCEC
- 1996 April 1..... SCEC and SCIGN approve operating plan
- 1996 May 1 JPL purchasing departments completes request for bids
- 1996 May 1 Request for bids are advertised
- 1996 June 1 Bidding closes
- 1996 June 15..... Bidder selected, contract awarded
- 1996 June 15..... Hire network coordinator
- 1996 July 1..... Site selection and installation begins
- 1996 August 8~... Ground breaking/ribbon cutting/press conference
- 1996 October 1 ... First receiver installed
- 1997 January 1 ... All sites built and all receivers operational

| Activity | 1996 Mar | Apr | May | Jun | Jul | Aug | Sep | Oct | Nov | Dec | 1997 Jan |
|-------------------------------------|-------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-------------|
| Develop operating plan | <--> | | | | | | | | | | |
| Develop contract specifications | <--> | | | | | | | | | | |
| SCEC/SCIGN approval of op plan | <--> | | | | | | | | | | |
| Develop request for bids | <--> | | | | | | | | | | |
| Hire coordinator | <-----> | | | | | | | | | | |
| Accept bids | <--> | | | | | | | | | | |
| Evaluate bids | \ <--> | | | | | | | | | | |
| Select winning bids, award contract | <-> | | | | | | | | | | |
| Ground breaking/ribbon cutting | <-> | | | | | | | | | | |
| Select sites, permit and install | <-----> | | | | | | | | | | |
| Sites operational | <-----> | | | | | | | | | | |

Budget

The budgets included below reflect the projected expenditure of the recent (FY95) NASA GPS Array augmentation funds, approximately \$1.4 M as of 1 March 1996 and FY96 USGS SCIGN operation funds, approximately \$235K. The funds supplied by NASA, NSF, and the USGS for analysis, archiving, interpretation, and maintenance are not included here, but are discussed in the matching funds section. The \$1.4M will provide for the procurement of 30 receivers, and the installation of 36 sites. This funding will also provide some enhancements at the processing centers (JPL and SOPAC). Both processing centers are responsible for archiving RINEX data from the array. Raw data from SCIGN sites is archived at the downloading center. Both processing centers have been and will continue to maintain on-line access to the RINEX data and plots of resulting positions or position differences. Funding is allocated to the processing centers to enable this effort to continue for all sites in the expanded array. The funding will also be used to install several receivers provided at no cost to the SCIGN array, and to complete three sites for which receivers are already purchased. We also include a 10% reserve to allow for unforeseen costs or overruns.

Table 1. Budget for NASA funds

| FY96 Budget | Overhead | No. | Unit | Total |
|---|-----------------|--------------|-------------------|--------------|
| | rate (%) | units | cost (\$K) | (\$K) |
| Field site costs | | | | |
| Equipment | | | | |
| Receivers and antennas | 1.0 | 30.0 | 14.0 | 424 |
| Ancillary site equipment | 1.0 | 36.0 | 0.5 | 18 |
| Monumentation hardware | 6.1 | 36.0 | 3.5 | 134 |
| Equipment subtotal | | | | 576 |
| Personnel | | | | |
| Reconnaissance | 6.1 | 36.0 | 2.0 | 76 |
| Field engineering | 6.1 | 36.0 | 1.0 | 38 |
| Site permitting | 6.1 | 36.0 | 1.5 | 57 |
| Site construction | 6.1 | 36.0 | 5.0 | 191 |
| Personnel subtotal | | | | 362 |
| Analysis center costs | | | | |
| Equipment | | | | |
| JPL computer hardware | 0.0 | 1.1 | 100.0 | 110 |
| SOPAC computer hardware | 0.0 | 1.1 | 75.0 | 83 |
| Equipment subtotal | | | | 193 |
| Personnel | | | | |
| JPL management | 0.0 | 0.22 | 160.0 | 35 |
| JPL scientist | 0.0 | 0.22 | 160.0 | 35 |
| JPL engineer | 0.0 | 0.25 | 120.0 | 30 |
| <i>JPL Personnel subtotal</i> | | <i>0.69</i> | | <i>100</i> |
| SOPAC management | 0.0 | 0.10 | 100.0 | 10 |
| SOPAC administration | 0.0 | 0.10 | 50.0 | 5 |
| SOPAC scientist | 0.0 | 0.25 | 75.0 | 19 |
| SOPAC programmer | 0.0 | 0.25 | 60.0 | 15 |
| <i>SOPAC Personnel subtotal</i> | | <i>0.70</i> | | <i>49</i> |
| Analysis Centers Personnel subtotal | | 1.39 | | 149 |
| Expected costs (Field equip.&pers.' + Center equip.&pers.) | | | | 1280 |
| Reserve | | | | 128 |
| Total (Costs + Reserve) | | | | 1408 |

Table 2. Budget for USGS funds

| FY96 Budget | Overhead | No. | Unit | Total |
|---|-----------------|--------------|-------------------|--------------|
| | rate (%) | units | cost (\$K) | (\$K) |
| Field site costs | | | | |
| Personnel | | | | |
| Receiver installation | 0.0 | 36.0 | 0.5 | 18 |
| Site Maintenance (6 visits/yr/site) | 0.0 | 76.0 | 1.5 | 114 |
| Personnel subtotal | | | | 132 |
| Coordinator costs | | | | |
| Personnel | | | | |
| Network coordinator | 100.0 | 1.0 | 40.0 | 80 |
| Coordinator Personnel subtotal | | 1.0 | | 80 |
| Expected costs (Field + Coordinator) | | | | 212 |
| Reserve | | | | 21 |
| Total (Costs + Reserve) | | | | 233 |

Cost-Sharing

The total cost of the additional stations in the SCIGN network proposed herein and in the NSF proposal will be \$4.35M over the next 5 years. At the same time, the groups involved will continue to operate and maintain stations already existing in the SCIGN.

This plan for the NASA funds that have been allocated will provide an additional 30 stations to the network. The NSF proposal included with the appendices to this plan request from the NSF \$2M over 5 years to purchase, install, and maintain 45 permanent GPS stations in southern California, and to process and archive all of the data over the 5 year period.

Hence this plan for spending the NASA funds, in combination with proposed support from NSF, will facilitate adding a total of 75 new stations.

The Southern California Earthquake Center (funded through NSF/USGS/FEMA/Caltrans and with cost sharing from its principal institutions) will provide an in-kind match of ~\$1.0M in support for analysis of the data from these instruments over the next 5 years to the Scripps Orbit and Permanent Array Center. The United States Geological Survey (USGS) will support maintenance of existing stations in the SCIGN during this 5 year time interval as well. The Riverside County Flood Control and Water Conservation District is funding installation of three UCSD-SIO ARI receivers.

| AGENCY | Support |
|-----------------|------------------|
| FEDERAL | |
| Air Force | 91,000 |
| NASA | 3,795,000 |
| NSF | 395,116 |
| USGS | 802,798 |
| STATE | |
| Caltrans | 12,500 |
| LOCAL | |
| Orange Co. | 51,116 |
| Riverside Co. | 187,850 |
| San Diego Co. | 5,000 |
| Los Angeles Co. | 60,000 |
| OTHER | |
| SCEC | 707,675 |
| Ashtech | 50,000 |
| Caltech | 30,000 |
| Green Found. | 21,000 |
| Mobil | 20,000 |
| UCSB | 4,000 |
| UCSD | 264,000 |
| TOTAL | 6,497,055 |

Table 3: Support of continuous GPS from various sources for the time period 1991-1995.

Expenditures through 1995 on continuous GPS in southern California show that there have been considerable contributions of both programmatic and discretionary funding from a variety of other Federal, State, and Local government agencies, as well as from private sources in the past. We expect this trend to continue and potentially increase during the 5 years covered by the NSF proposal, and discussed within this plan.

Table 4. Support for the installation and operation of the SCIGN. *FY'96 Support* column is for funds that have been either allocated or approved through panel review at this time. *FY97-FY02 Proposed or Requested* column is for funds that have been either formally requested through panel review or discussed with program managers.

| Agency | FY96 Support | FY97-FY02 Proposed or Requested |
|---------------|---------------------|--|
| NASA | \$1,359K | \$5,000K |
| NSF | | 2,000K |
| USGS | 257K | 1,250K |
| SCEC | 200K | 1,000K |

Other relevant developments include the pending proposal to FEMA for improving the digital seismic network, which would provide some of the SCIGN stations with digital real-time telemetry. Also, the County agencies have already been helping SCIGN to identify potential sites where they own land (maintenance yards, etc.) and could greatly facilitate our site selection and permitting. Agencies responsible for public safety of engineered structures have been interested in the SCIGN developments of new methods to monitor engineered structures as a result of our pilot study with Los Angeles County at Pacoima Dam.

The new results of SCIGN have been presented to Program Directors in all participating agencies, as well as members of the United States Congress, the Director of the State Office of Emergency Services, and many others. SCIGN developments will also be presented at the Caltech/USGS Broadcast of Earthquakes (CUBE) Users' Feedback Meeting in late March. The CUBE users include most of the large corporations in public utilities and transportation in Southern California, and provide funding to Caltech for joint projects such as SCIGN through the Earthquake Research Affiliates (ERA) program at Caltech. This is a potentially large source of private funding that is just now being developed. In addition, SCEC has proactively sought funding from the Insurance Industry through a series of meetings with Insurers, including the major one held at USC in November 1995. The scientists involved in SCIGN, along with our partners in the funding quest, have been very actively seeking other sources of funding through a variety of channels, and they will continue to inform people of the capabilities and potential of this new technology.

Outyear plans

SCIGN intends to operate all existing and currently funded stations for a total of 5 years. At the end of 5 years, the network will be re-evaluated and decisions about its future will be made in light of the contributions made by the network and the funding situation at that time. Expansion of the network by the addition of new stations will proceed as funds become available. In light of the uncertainty of the source and amount of new funding we have not made detailed plans for future expansion. We anticipate that such future expansion will be handled in a manner similar to that outlined here for the current expansion. In particular, future expansion plans will probably partition the resources between new receivers, installation costs and enhancement of processing center capability in a manner similar to that proscribed here.

Implementation

Introduction

In order to implement the SCIGN array, we have to purchase the receivers, select appropriate sites, install the receivers, and assure their continued operation. Most of these activities will be carried out under contract. Neither the SCIGN board nor SCEC have the necessary staff for these activities. Nor can an expansion of this magnitude be carried out by the existing staff of the cooperating agencies and institutions.

Several actions will be required:

| | | | Funding Source | Contracting agent |
|----------------------------------|----------------------------|-----------|----------------|-------------------|
| 1) Receiver purchase | (30 @ \$14.5K/ea) .. | \$435K .. | NASA..... | USC |
| 2) Site selection and permitting | . (30 @ \$4.5K/ea).... | \$135K .. | NASA..... | JPL |
| 3) Site construction | (36 @ \$8.5K/ea) ... | \$306K .. | NASA..... | JPL |
| 4a) Receiver placement | (36 @ \$0.5K/ea).... | \$18K .. | USGS..... | USGS |
| 4b) Receiver maintenance | (76 @ \$1.5K/ea).... | \$114K .. | USGS..... | USGS |
| 5) Network coordinator | (1 @ \$60K/yr) | \$60K .. | USGS..... | USC |

The biggest challenge will be to identify geologically and geophysically suitable sites, to obtain permission from the owners for these sites, and to construct the monuments at these sites. We have decided to break the network construction into three parts. The skills required for the three parts differ and it is likely that different companies will be required

for each. We anticipate that one company will carry out the site reconnaissance, evaluation, selection and permitting. A second company will carry out the actual construction work, putting concrete and steel in the ground, and installing power and communication service. Because these two activities will have to be tightly coupled, we anticipate that there will be a contractor-subcontractor relationship between the contractors. Finally, placement of the receivers at the prepared sites will be done by the network coordinator with assistance from a maintenance contractor.

We have explored various options for all of these contracts. The options that have been discussed included contracting through JPL, through the USGS, through USC, and through UCSD; sole source purchasing, purchasing through the ARI process, and others. After giving consideration to factors such as respective overhead rates and institutional preferences for implementing various parts of the project, we have decided to proceed as outlined below. We will continue to examine the options for each step and expect to revise the plan as necessary to accommodate changing circumstances.

Receiver purchase

GPS receivers will be purchased through the SCEC/University of Southern California. The purchase contract will guarantee the vendor that we will purchase at least 20 receivers and will contain options to purchase up to an additional 20 receivers. The actual number purchased will be adjusted after final bids for all aspects of the work have been received and may be adjusted after some of the sites have been permitted and installed. We expect the procurement to occur in two stages: an initial procurement of 20 receivers and a secondary procurement of additional receivers after the installation is under way and installation costs have been re-estimated. The receivers will meet the University Navstar Consortium Academic Research Infrastructure (UNAVCO-ARI) Continuous Geodetic Reference Station (CGRS) specifications. All receivers purchased will include a Dorne-Margolin antenna with choke ring.


Preferred Receiver Purchase Plan

In order to move the funds for this purchase from NASA to SCEC, USC will submit a proposal to NASA for unrestricted funds in the amount of \$435K to be used for the SCIGN network. These funds will come from the \$1.4M earmarked by NASA for SCIGN. USC will ask all the ARI participant vendors to submit a "best and final" offer for CGRS receivers. The best and final offers will be evaluated by a USC technical evaluation committee chaired by John McRaney and including the SCIGN Chairman, Will Prescott. The evaluation criteria will include the ability to meet the CGRS specifications (40%), compatibility with existing receivers in the network (40%), and price (20%).

Site selection and permitting

Selection of the approximate locations of the sites to be added to the net at this time will be made by a Site Selection Subcommittee (the "Dots" committee, including Agnew, Donnellan, and Hudnut). In the selection process, consideration will be given to insuring that the sites address important scientific objectives now, as well as providing a rational base for future expansion. The selection process will be driven by the priorities established at the SCEC workshop "Geological and Design Issues of Continuous GPS Networks" held at JPL on 30-31 March 1995 (Figure 1). Our goal is to add 15 new sites to the A-A' profile and 15 new regional sites. Appendix E contains a map indicating the current choices for new stations.

Selection of the specific sites will be carried out under a contract. Recommendations of the Site Selection Subcommittee will be approved by the SCIGN governing board and a set of maps reflecting those choices will be included with the Request for Bids. The SCIGN Board has developed a set of specifications for this process (Appendix A). The contract for site selection will be executed through JPL. JPL's procurement department will turn the specifications into a request for bids. The request for bids will be reviewed by the SCIGN executive committee prior to its advertisement. Bids will be evaluated by a technical evaluation committee that includes the SCIGN Chairman as a voting member.



Site construction

Site construction will be carried out under a contract. Site construction will include building an antenna monument, installing a receiver box, and bringing in power and communications. The SCIGN board has developed a set of specifications for this process (Appendix B). The

contract for site construction will be executed through JPL. JPL's procurement department will turn the specifications into a request for bids. The request for bids will be reviewed by the SCIGN executive committee prior to its advertisement. Bids will be evaluated by a technical evaluation committee that includes the SCIGN Chairman as a voting member.

Receiver maintenance

Maintenance of the receivers will be carried out under contract. One of the first tasks under the maintenance contract will be to place new receivers and antennas at the already-constructed sites. The SCIGN board has developed a set of specifications for this process. The complete specifications are attached (Appendix C). The contract for receiver placement and maintenance will be executed through the USGS. We anticipate that this will be done through an add-on to existing seismic station maintenance contracts. The SCIGN chair person will participate in negotiating the add-on and the SCIGN board will review the language. If the contract is implemented by competitive bid, USGS's procurement department will turn the specifications into a request for bids. The request for bids will be reviewed by the SCIGN executive committee prior to its advertisement. Bids will be evaluated by a technical evaluation committee that includes the SCIGN Chairman as a voting member. Receiver placement and maintenance are separated into separate contracts because the number of sites will be different for the two contracts, and the time period of performance will be different. However, we anticipate that both activities will be carried out by the same vendor.

In addition there will be other, smaller, procurements; principally for computer hardware for JPL and Scripps. These procurements will be handled entirely by the end user institution. NASA/JPL should transfer the appropriate amount (see Budget section) to the appropriate institution. Upon completing the procurements, but not later than one year after receiving the funds, the receiving institution will provide the SCIGN board with a summary of the expenditures.

Network coordinator

Operation of the SCIGN network will be overseen by a Network Coordinator. The Network Coordinator will be hired by SCEC with funds provided by the USGS. The position will be located at the USGS/SCEC center at 535 Wilson Street, Pasadena, California. The duties of the network coordinator will be to insure that the entire network is maintained in an operational state at all times. A detailed position description is attached (Appendix D).

Glossary

- ARIAcademic Research Infrastructure
- Caltech.....California Institute of Technology
- CaltransCalifornia Department of Transportation
- CGRS.....Continuous Geodetic Reference Station
- CUBE.....Caltech/USGS Broadcast of Earthquakes
- ERA.....Earthquake Research Affiliates
- FEMA.....Federal Emergency Management Agency
- GPSGlobal Positioning System
- JPL.....Jet Propulsion Laboratory
- NASA.....National Aeronautics and Space Administration
- NEHRP.....National Earthquake Hazards Reduction Program
- NGSNational Geodetic Survey
- NOAANational Atmospheric and Oceanic Administration

NSF.....National Science Foundation
 RINEXReceiver Independent Exchange format
 SCECSouthern California Earthquake Center
 SCIGNSouthern California Integrated GPS Network
 SIOScripps Institute of Oceanography
 SOPACScripps Orbit and Permanent Array Center
 UCSB.....University of California, Santa Barbara
 UCSD.....University of California, San Diego
 UNAVCOUniversity Navstar Consortium
 USCUniversity of Southern California
 USGS.....U.S. Geological Survey
 WWWWorld Wide Web

Appendices

Introduction to Appendices A, B and C

The skills and equipment required for selecting and permitting sites differ greatly from the skills and equipment required for excavating, drilling, building the monuments, and installing communication and power. For this reason we have separated the specifications into two pieces: Appendix A covering site selection and permitting, and Appendix B covering site construction. However, these two activities must be closely coordinated. The construction contractor cannot proceed until the selection contractor has located and permitted the site. And the selection contractor must thoroughly understand the requirements of construction in order to find suitable sites and in order to explain the installation to landowners prior to obtaining permission. Consequently, we expect these two parts to both be awarded to a single contractor who will likely subcontract for one or more of the subparts. This single contractor could be a geologic consulting firm that subcontracts with a construction firm for the actual construction, or a construction firm that subcontracts with a geologic consultant for the site selection. Other scenarios are possible. The prime contractor and all subcontractors must be indicated in bids and must demonstrate that they can meet the requirements of the request for bids.

Placement of the receivers and antennas in the newly prepared sites might logically be done by the site construction contractor. However, once emplaced the receivers will be maintained by a separate maintenance contractor. In order to streamline the handover of new sites to the maintenance contractor, we decided it made more sense to have the maintenance contractor place the receivers in the already prepared sites. Our objective is to reduce the possibility of disputes about responsibility in the event of startup problems.

Appendix A — Site selection and permitting specifications

Introduction

The SCIGN management requires selection, permitting and documentation of approximately 30 new Global Positioning System (GPS) sites in the Los Angeles metropolitan area. We anticipate that this part of the implementation will be done by a geologic consulting firm or by a company with similar suitable expertise. The site construction subcontract must meet the specifications given in Appendix B. The total number of sites needed may be adjusted during the course of the contract, however, the number will be at least 20 and not more than 40.

Definitions

Location will be used to refer to one of the dot locations on the maps provided with the request for bids. *Site* or *candidate site* will be used to refer to a specific place that has been accepted or is being considered for monumenting.

Interface with SCIGN committee

The executive committee will provide the contractor with a set of 1:100,000 scale maps indicating the desired locations of the stations. These maps will indicate approximately 50 target locations. The map will indicate the priority order of the locations. It is anticipated that it will be difficult, impossible or too costly to find sites corresponding to some of the targeted locations (hence 50 locations for an eventual 30 sites; all of the extra sites will be located in the metropolitan area where most problems are anticipated; no extra sites will be indicated in less populated areas). The contractor may skip impossible locations and proceed with next priority ordered location, but, for each skipped location, the contractor should provide contracting officials and SCIGN with documentation indicating the effort expended to find a site near the location and the reason for rejecting the candidate location. Once all the required sites have been found, no documentation is required for any unused locations.

Because the location of the sites is a crucial to the success or failure of the SCIGN project, the contracting officials in consultation with the SCIGN Board will review candidate sites before final selection. Once a viable site has been located, the contractor will submit a site summary (Form A), to the contracting officials and the SCIGN Executive Committee. The Board will respond within 5 working days either advising contracting officials to authorize the contractor to proceed with the site or to reject the site. Failure of the board and the contracting officials to respond within 5 working days will constitute acceptance of the site. The board expects that most candidate sites that meet the criteria spelled out below will be accepted. Once the contracting officials, in consultation with the SCIGN Board, have approved the site, the contractor should finalize permitting and then the construction contractor can proceed with site construction.

Contract requirements

Site Selection

The contractor will be responsible for finding a viable site at each indicated map location.

The contractor will be responsible for negotiating permission to use the site. The final site permission agreement will be between JPL and the landowner (see Permission below).

15 of the sites must be selected from locations along Profile A-A' (Figure 1).

15 of the sites must be located at regional locations.

All sites must be located within 3 km of the target location.

For both the profile and the regional sites, failure to find a suitable site corresponding to a particular target location is acceptable but must be documented on the appropriate form (see Forms).

Note: The SCIGN Board recognizes that finding suitable sites in an urban area like Los Angeles is a difficult task. The following guidelines are designed to indicate in detail the characteristics that are required. We recognize that some compromises will have to be made.

Sky view and multipath

A candidate site must have an *adequate* view of the sky. Adequate is defined by the following specifications.

Preferably the site should have no obstructions of the sky above 15° elevation.
The contractor will make a horizon mask diagram for the candidate site (see Forms).
There must be no more than 4 objects extending above 15°.
All of the objects extending above 15° must obscure no more than 30-5°x5° blocks (count the squares above the 15° line in the horizon mask).
There can be no obstructions above 45°.
There can be nothing above the expected antenna location within 3 m of the expected antenna location.
There can be no transmission power lines within 100 m of the site.
Other wires and other objects subtending less than a 1° angle as viewed from the expected antenna position are allowed.
When accounting for trees on the net mask, allow for 5 years of tree growth. That is the mask should indicate as obscured, any areas that may be obscured by tree growth during the next 5 years (make a reasonable guess—no professional tree evaluation is required).
Preferably the site should be located far from any flat reflective surfaces (such as buildings, chain link fences, etc) that could serve as a source of multipath.

Permanence

The contractor must ascertain that the site will continue to be available for the expected 5 to 7 year duration of this project. Ideally, the site will allow a permanent monument. Geodetic marks have value for long periods of time (decades to centuries).
The contractor will investigate the surrounding area for the presence of signs such as “Future home of_____”.
The contractor will also ask the landowner or permittee whether there are any known plans for development or changes that would affect the usefulness of the site for GPS observations.
This investigation should include consideration of adjacent areas where modification might block the sky view at the site.

Security & Safety

Sites where public access is restricted or where the equipment is otherwise secure from theft or vandalism are preferred.
Safety of personnel visiting the site should also be considered.
However, monument construction is designed to allow installation of sites that are completely accessible to the public. Consequently, we do not expect any site to be ruled out on the basis of a lack of security.

Site geology

Sites on natural ground are preferred. Any man-made ground or fill present, must be less than 3 m thick.
No sites may be located on landslides.
The local ground slope must be less than 3% within a 20 m radius of the antenna location.
There must be no active oil pumps within 2 km of the site.
There must be no active water pumping out of or into the ground within 2 km of the site.
No sites can be located in areas indicated on precultural maps as intermittent or permanent lakes or ponds.
No sites can be located in areas indicated on precultural maps as drainage channels.
Local drainage should take runoff away from the antenna location, not toward it.

Access

The site must be accessible to the drill rigs, concrete trucks and other equipment required to construct the monument. Heavy equipment access is only needed until monument construction is complete.

Accessibility for construction should consider the following issues:

Gates/fences

Time periods when the site is not available

Time periods when there are noise restrictions

Maximum load that can be driven in without damaging property

Maximum width that can be driven in without damaging property

Maximum clearance around proposed mark

Will anything be damaged during mark construction (lawns)

Availability of power and water for construction

The site must also be accessible to visits by maintenance personnel on an occasional, but continuing basis.

Power

110 volt power must be available within a reasonable distance.

Power needs are fairly modest, approximately 15 watts.

Preferably power will be obtained by a drop from an existing power pole to a local box.

If necessary, power can be obtained from greater distances (with trench laid conduit, or overhead lines).

In order to limit costs of providing power while providing flexibility to the contractor, the total distance of all trenching or above ground power runs is limited to 1500 m for all 30 sites (an average of 50 m/site). We anticipate longer than 50 m runs at difficult sites and shorter runs at easier sites.

Often power can be obtained free from the owner.

Alternatively, we can arrange to reimburse the owner for power usage.

At some sites solar power may be a desirable option.

At all sites, space for backup batteries should be provided.

Communications

A telephone-like connection must be available within a reasonable distance.

Preferably telephone will be obtained by a drop from an existing phone line to a local box.

If necessary, phone can be obtained from greater distances (with trench-laid conduit, or overhead lines).

In order to limit costs of providing phone while providing flexibility to the contractor, the total distance of all trenching or above ground power runs is limited to 1500 m for all 30 sites (an average of 50 m/site). We anticipate longer than 50 m runs at difficult sites and shorter runs at easier sites.

Alternatively, communication can be provided by radio modem. The contractor is responsible for designing a communication plan that provides dial-up like access to each site.

Permission

Contractor is responsible for obtaining informal permission to investigate each location.

Contractor is responsible for obtaining formal permission to use each site selected.

This permission should be obtained on a standard JPL form (see Forms).

Permission has to be obtained within a time period that allows completion of construction at all sites by 1 January 1997. (i.e. some can be done early and some late, but they can't all be built last).

Permit has to allow access to: build site, to install receiver and associated hardware, and to maintain receiver and associated hardware.

Preferably the permit should extend for 7 years to 1 January 2004.
If necessary an annual permit with annual renewals is acceptable. Preferably renewal should be automatic.

Landuse fees

Sites with no landuse fees are required with few exceptions.
Exceptions will have to be considered on a case-by-case basis.
The contractor can negotiate proposed landuse agreements on JPL's behalf. Final agreements will be approved and signed by JPL.

Receiver occupation test

Sites with little or no radio frequency interference (RFI) are preferred.
The contractor will occupy each candidate site with a GPS receiver provided by SCIGN and submit the results of the occupation as part of the site evaluation.
Four receiver tests will be conducted. Each test will last 2 hours. Tests will be conducted on a weekday (Monday through Friday) and must cover the four time periods: 2–4am, 6–8am, 2–4pm, 6–8pm.
The data from the test will be analyzed with a quality control program (provided) and will have to meet specifications to be provided

DigAlert

The contractor will call DigAlert for each candidate site.
Candidate sites will be selected so as not to interfere with existing underground utilities.
The contractor will include a summary of underground utilities within a 10 m radius of the candidate antenna location in the station evaluation.

Site description

Upon completion of the site, the contractor will provide a site description that includes: adequate text and graphic information to enable finding the site; description of the geologic environment; name, address and phone number of the owner; name, address and phone number of the contact person; and, an enumeration of any special conditions regarding the site (preferred access times or routes, etc).
The entire description except for graphical information will be in digital format compatible with typical web browsers (Mosaic, Netscape).
SCIGN will provide a template for text data and will convert graphical data to a web compatible format.

Contractor qualifications

Bidders must have demonstrated training and experience in evaluation of surficial geologic conditions.
The Bidders must demonstrate knowledge and experience in identifying landslides, ground type, and modification history of the ground.
Demonstrated prior experience with GPS is preferred.
Demonstrated experience working with construction and drilling contractors is required.
Demonstrated experience working with electrical and communication contractors is required.
References to previous jobs of similar scope and content are requested.
All of the people that will be working on the project should be identified by name.
Qualifications of all of the people that will be working on the project, including subcontractors, should be included.

Supervision

The contractor may be supervised by a representative of the SCIGN board as necessary to resolve problems and to ensure contract compliance.

Appendix B — Site construction specifications

Introduction

The SCIGN management requires construction of approximately 30 new Global Positioning System (GPS) sites in the Los Angeles metropolitan area. We anticipate that this part of the implementation will be done by a company with general light construction experience involving drilling, welding, concrete, electrical and phone. We expect to have a SCIGN representative present for the actual construction. This will be particularly useful for the initial sites.

Contract requirements

The specifications include performance bonuses and penalties.

The contractor is responsible for all labor, material and supplies necessary to the installation.

This contractor will not be responsible for providing or installing the receiver and related hardware.

The contractor will build a site in accordance with these specifications.

At each selected site (see Appendix A) the contractor will build one of two mark types:

A "drilled mark" or a "rock mark".

If the site has an outcrop of unfractured, crystalline bedrock that is not deeply weathered, the contractor will have the option of installing a rock mark (see Appendix B-4).

At all other sites, the contractor will install a drilled mark (see Appendix B-1, B-2, B-3).

Contractor will install a metal box (see Appendix B-5) for the receiver and modem.

Preferably this box will be located inside a building. If necessary it can be outdoors. In either case the box should be rigidly attached to a wall or post. The box should contain 2-110 V AC outlets and either an RJ-11 phone plug or an RS-232 plug hooked to a suitable radio link.

Power and phone connections should be run through buried metal conduit meeting local code requirements.

Contractor will also install buried metal conduit connecting the box to the antenna location for the receiver-antenna cable.

The contractor will return the vicinity of the site to its original condition, if required by the landowner.

Upon completion of the site construction, the contractor will provide site plans that include a description of the as-built site construction details, and in particular indicate any deviation from the construction plans.

We also require detailed reports on the drilling and grouting operations, including drill logs that summarize as a function of depth: the materials encountered, the problems encountered and the solutions devised.

The contractor may be supervised by a representative of the SCIGN board as necessary to resolve problems and to ensure contract compliance.

Appendix B-1 — Deeply Anchored Monuments - Construction Procedures

NOTE: This document, as of 3/15/96, was written assuming an "intersection" height of 62 inches, 1.57 m. This target height may be changed (or, say, the angle of the boreholes may be changed), which will then require making changes throughout.

Preparation of casing: (2.06)

The casings consist of a 16'-long sections of 2 1/2" belled-end Sch. 40 PVC irrigation pipe, with 2 x 6' lengths and 1 2 1/2' length of 2 5/8" ID (for 14 1/2') of *Armstrong* insulation foam on it. The foam is slid down the non-belled end of the PVC pipe (if the PVC is very dirty, it's worth cleaning it off so the foam slides easier), and initially secured to the pipe with PVC cement at the top and bottom of each length of foam. Leave approximately 9" of casing unjacketed at both ends. At the top we want to do this so the casing sticking out of the ground will be "clean" (no tape or insulation) when the job is done. The foam is then secured with 1/2" filament tape running down the length of the pipe, one or two runs down at 90 degrees to one another axially down the pipe, securing the ends of the filament tape at the top and bottom of the pipe by wrapping the ends radially a few times. The foam is then wrapped radially in a slanting direction, barbershop pole style (overlapping spiral) starting at the top, with duct tape to make the package smooth. It's important not to compress the foam too much, as this makes the foam less resilient, and may cause the casing to slip too easily into the hole. Finally, at about 1-1 1/2' from the top of the casing (the belled end), the wrapping should be widened so that the casing cannot fall into the hole if the hole is too large. This can be done with some rags symmetrically wrapped around the pipe with layers of duct tape to secure them. Remember, the casing has to support the entire weight of the anchoring pipe until the grout has set, so it's important to see to it that it's firmly wedged into place. Ideally, this wedging material (bundle of rags and tape) should be removed when the grout has hardened, to relieve the rigid coupling of the casing near the surface. In the long run it is expected the rags (and, indeed the compliant foam) will rot away and so relieve themselves.

Geology/Hydraulic Crawlers: (2.01)

This section is written assuming the use of a Hydraulic-Crawler drill rig, which is clearly not the ideal in all cases. Its one great advantage is its ease of alignment. It is the drilling equipment of choice in rock, and has proven itself a viable choice in most other types of material. One strong recommendation, when doing a large number of holes would be to carry out a trial drilling exercise at each site, prior to full-blown drilling efforts.

When drilling in clay-rich material, you probably want to use the minimum amount of water, otherwise the sidewalls swell and you'll have great trouble at every stage when it comes to pulling back (up) on the bit. The material behind the bit will cause the drill string to become wedged. In rocky soil, or decomposing rock (as at Table Mountain for example) lots of water makes the job possible, helping to seal the porous material so air (and spoils) flows up the hole and not out into the formation. It's hard to know which route is proper - lots of water or trying to drill dry - without experience at the site. In either case using water right at the ground surface, to limit caving there, is a good initial move.

The hydraulic crawlers can drill fast (say, 12feet in 1 minute) in anything, but can then have a terrible time pulling backonce spoils get behind the bit that aren't being lifted to the surface. Veryimportant: *make sure the drill rig can supply air in high volume*; some rigs seem tohave deficient air-delivery systems.

Layout/Alignment of drill rig: (5.03)

This is best done with two or three people. The vertical hole is to be drilled first, then the angled holes. The alignment stakes should be laid outbefore the drill rig arrives. It's not very productive to mark the exactentry point of the angles holes until it's time to do them, as the drill rig is likely to tear them up, and wewant them to be aligned, ultimately, with the center hole as-drilled, not as it was staked. When the central hole placement and the angled-holeorientations are decided upon, the alignment stakes (sprayed fluorescentorange) should be placed about 50'-100' away from the center hole, in thedirection we want to drill. We have used a carpenter's square as a sight, to ensure that the holes are laid out at90° spacing, but an AutoLevel (or transit) with Tripod and surveying Rod allowsyou to set a much better set of marks; the Autolevel has nice azimuth markerson it. When it comes time to actually mark where you want the bit to enter the ground for the angledholes (during the drilling operation) it's useful having a short section ofpipe to hold over the vertical hole as this makes its position easier to seefor the person at a distance.

After drilling the center hole measure out 43 1/2" horizontally from thecenter of the center hole and put a very small stake there-say 2-4" long(popsicle stick?), and marked with orange spray paint-whose lateral positionneeds to be established by someone standing over an alignment stake and looking toward the center hole.You may also need a short piece of pipe, positioned briefly over the stick inthe ground, so the person at azimuth mark can "see" where the short stickis. Remember, when measuring out from the center hole, to compensate for any ground slope: if theground slopes down the stake will have to be located farther out, if itslopes up, closer in. We want the angled pipe to pass through 43 1/2"-out ata elevation equal to that at the ground around the center casing. Sometimes a small section of pipe or wood isuseful to help give a sense of level between the two places.

The hydraulic crawler rigs have a foot on the tower which bears weight whiledrilling, a lot of weight. The foot, and hence the bit position will tend tomove (skid or sink) as pressure is applied, making it harder to get the drillrod aligned as desired. A solution to this is to do some shovel work in advance; this really helps.Starting at the desired drilling point, 43 1/2" out and no farther, create a small sloped cut, sloping at 35° from horizontal, back toward the center hole. This should be about 2' wide(in the direction of the foot) and about 1' deep, being deepest back towardthe center hole. This gives the drilling foot a place to land that's perpendicular to the hole we want to drill.(On some rigs the tower foot is under the drill rod as opposed to being offto the side; in that case the slanted hole will have to be cut down deepertoward the center hole. You get the idea.) You can now use the entry point and alignment stakes tosight-in the drill rig. Have one person at the rig, giving instructions tothe driller on (1) the position of where we want the bit entering the groundand (2) keeping close track on the angle of the drill-rod/tower (35° from vertical, *not* horizontal), and (3) checking that the drill rod appears to be exquisitelycrossing over the center of the center hole (actually do this last, after thestep which follows). Have the second person sighting from the appropriate azimuth stake making sure the rig tower looksvertical and that it's not canted over to one side, from their perspective atthe azimuth point. It's easy to get fooled by optical illusions here. (If youset up, say, the Autolevel you could really do this well, using its crosshairs.) Finally, both playersshould check that that the drill rods seems to be headed directly over thevertical hole. Recheck the angle of the drill rod.

It may be necessary to make some adjustment, some allowance on the subsequent holes, during drilling of the other angled holes together everything to meet in one place. The primary aim here is to do things consistently, even if this sometimes means following a poor result from the first effort. One important thing to keep in mind is that the drill bit tends to 'skid' outward as it begins its boring, making the final pipe intersection point (where the pipes will meet in the air) higher than planned. An allowance of 1"-2" for this is the most that should be acceptable. In fact, you may want to start the first hole at (say) 42 1/2" from the center hole (an inch closer), to allow for the anticipated slippage, and then follow whatever result you get for the other holes, including this same assumed-slippage distance, if that's what it takes.

Before you begin this alignment procedure, warn the driller that he will be requested to iterate (try, try, again) when it comes time to aligning the rig. It's always proven to be worth it. It turns out that the iterative efforts, while annoying, seldom take more than a few minutes, once you're close, and dealing with poorly aligned holes can take a lot of time and lead to a much less well braced mark.

(A list of..) Some steps/issues while drilling-overview:

0. Prepare alignment markers; prepare tamping/blowout tube.
1. Align the rig, and keep *detailed* notes of soils/issues while drilling.
It's hard to know when trouble will develop, then you'll want facts.
2. While drilling, fully prepare anchoring pipes with clamps and couplings.
3. After drilling each hole "prove" it (blowout tube with max possible diameter);
re-bore (or decide to blow out later) if necessary.
4. Get drill rig's help to set casings, pushing them in. (Want them level, about 6" above the surface.)
5. When done drilling, have them blow out each hole using their air blow-out tube (if necessary).
If really troubled, install anchor pipes and apply air to them (keeps the rig around longer).

Casing Setting: (5.05)

In clayey soils, or with a drill bit of only 4 1/2" diameter we have had to use the drill rig to set the foam-padded casings. First they've pushed with some portion of the tower and then, when the drill stem could be aligned, pushed with the bit. We want the casings (all five) to end up with their midlines at 6" about the ground, level with the center casing (even if the ground is sloping). Also the casings should be snug at the surface so they won't slip during grouting. Important.

As each casing is set, we need to jam some rags around it, below the surface, to seal off any loose material. Then throw fill around the casing to make the ground level again (this assumes there will be some caving during drilling). Also we want to tape the top of the casing with duct tape, again to preserve the borehole.

Testing the Holes: (5.06)

Keep good notes throughout drilling and pipesetting on the hole depths. Remember to write down what the driller says is the total depth (T.D.), as this number make never show up again. As soon as the drill rod clears the hole the driller will usually sound the holes with a tape measure. Record this. This value will generally be "short" because of loose spoils. You should then use a fiber-glass-taped (for insurance against breakage) PVC sounding/blow-out tube to see what depth it gives. (Having someone restrain the end of this, providing resistance to it such that the pipe bends into the air, helps to get this flexible tube in and out. Think of someone pole vaulting.) With the end of this tube open, there's a good chance (especially if water has been used in the hole) that you can actually extract material while making this measurement. This is a very good idea if you should want the hole deepened, though it cores a narrow hole. Remember this later.

| | | Depths - YOURSITE | | | | |
|----|------|-------------------|------|---------|---------|------|
| | | TD | Tape | Tamped | Shimmed | Pipe |
| #1 | Vert | 38' | 32 | 35 1/2' | 34' | 32' |
| #2 | | | | | | |
| #3 | | | | | | |
| #4 | | | | | | |
| #5 | | | | | | |

All depths here are given from the ground surface. Recall the target hole depth at most sites is 35' (shimmed if necessary). This depth leaves 3' of clearance for any spoils that might fall in during anchoring pipe installation and thus should provide for more worry-free grout filling of the holes.

There's a real urge to start tamping at this point to establish the depth of the hole attainable with compacted spoils. Don't do this *unless* you're very likely to achieve the compaction you want, the final depth you want. Note that spoils tend to become jammed only a few feet ahead of the compaction tool, so it's usually hard to get more than say 4-8' of compaction, even with 20' of loose material. (This column of material can become much more compacted when the pressure-head of wet grout is introduced, though we can't assume that will happen.) In any event it's probably best to "sound" at this point with open-tube sounding tube (don't have it sealed at this stage). Record numbers.

Before the casing is set, the driller can be asked to reopen the hole.

After setting casing you may want to sound again. You certainly will want to sound the holes when they are all done and just *before* the drill rig is released. We have tried to have the right fittings and hoses to be able to connect the drill-rig's air to our sounding/blow-out tube. Blow out the holes as needed. (Except, their air supply, in many cases, can be so feeble as to be useless-at which point a real compressor is needed.) Tamping can also be used to deepen holes, if there are lots of spoils. Starting out with a small-diameter tamper (i.e., rebar, though this is a bit dangerous) will achieve the best tamping depth. You can and should eventually tamp with the sounding tube, sealed with an end cap and otherwise broadened (duct tape?) as much as you dare, to make sure the bottom reaches of the hole are as wide as possible where the pipe will extend. Remember, the grout has to make it through the annulus outside the pipe and inside the hole (broadened? by the tamping); if this annulus is narrowed to only a fraction of an inch with compacted spoils, the grout may not flow. This would be real trouble.

For those hole that are found to be too deep (say, with more than 3' of clearance below the anchoring pipe's bottom-35' you can shim them with fine gravel which compacts naturally. We do this so we are less likely to run out of grout. Sound the holes as you carefully do this.

Centralizers: (5.07)

Maybe worth pursuing, maybe not. Owing to space limitation, at this time (9/95) we're leaning toward applying these only on one side of pipe and trying to keep the anchoring pipes oriented as we lower them, which is doable but potentially pointless later on if we chose to rotate one of the pipes.

Assy. of Pipe: (5.08)

There are a couple of diagrams which shows how this all goes. The 21'-long pipes should be cut to size (nominally, 32' below ground, with 79" above the ground for the angled pipes and 66" for the vertical, so cut lower sections to 17' 7" for the angled and 16' 6" for the vertical before heading out to the site (change this someday if we decide to deliberately have the couplings end up outside of the casings). The bottom length of pipe should be cut to size since we don't need threads on its bottom end. This leaves the top as a full section. This means, for the angled holes, that the coupling will be inside the casing (a good situation to avoid it getting stuck below the casing's slip), while for the vertical pipe it will be just beyond the casing which is workable because the pipe is dangling. After sounding the holes in the field, the pipe lengths should be reconsidered, possibly cutting off of some excess pipe to assure the pipe bottom will be well clear of the hole bottom: maybe only 1' necessary - if you don't fear lots of loose spoils falling when the pipe is being installed. Remember we're trying to achieve anchoring over the entire length of the exposed pipe, so giving up a little pipe length at the end means very little.

Set the U-bolt clamps-measured from their tops:

Angled: 72" Vertical: 60" Casings: 6" (above level ground)

Before installing the pipes it's best if you decide whether you want a clockwise or anti-clockwise arrangement. The results of drilling usually favor one over the other. Install the vertical pipe first. The upper piece of pipe for each hole needs to be assembled in mid air which is tricky. You'll need a tall ladder and as many people as you can gather for this, and everyone needs to know what the objectives are. Be very careful, someone could get hurt by the clamp if the pipe gets loose. Take your time. Hard hats for everyone and have a plan for fingers to get clear if needed. First, just slip the lower pipe down into the hole, making sure there's a secure coupling on top, and that someone is at the hole opening holding the "Y" choke-plate in place. With it across the hole opening the pipe can't fall down the hole. When this pipe is in and the coupling is resting on the "Y", assemble the upper piece of pipe, first by hand (to minimize risk of cross threading) and then with pipe wrenches, with a well positioned ladder held in place by someone. Positioning of the ladder and seeing that it's stable is critical before proceeding. The ladder needs to be located such that someone standing on it can support the pipe above its center, above its center of mass-that person always handling it there, or very nearly there so the pipe doesn't want to get away backward. After tightening the pipes firmly, lower the final section down the hole. Watch out for the support clamp, and have an "all clear" plan.

It's important at this point to check that the hole is still open to the bottom of the pipe (it's possible that spoils have become knocked loose or that the pipe is jammed with material from the side walls). We use a "breath test" to make sure that the pipe is clear, blowing down the pipe should yield no perceptible back pressure. If you do sense any back pressure at all it's time for some serious thought.

We don't want the upper (temporary) couplings ontoo tight as we'll want to remove them without stress during the groutingoperation.

Aligning the Pipes: (5.09)

A nice diagram exists which shows the aim. We want the pipes to make contact 3 1/2" below top of vertical pipe, with the upper edge of the angled pipes 1"down from the top at the spot where they are inline with the outer edge ofthe center pipe. You'll need to play with the clamps to get the heights to be ``just so." Putting a mark next to the clamp on any pipe that is to be raised or lowered helpsconsiderably in making subtle adjustments. Remember the casing were put in by eye and so the pipes resting on them will likely be different fromthe ideal by inches. As you are doing this you should try to move the pipeslaterally to get good contact with the center pipe (you can move the centerpipe as well). Slight lifting of the pipes helps allow the clamps to skid better across the mouths ofthe casings. It would be nice to end up with the pipes away from thesidewalls of their casings-but it's hard to think of any reason other thanaesthetics for doing this (so don't do it). The key thing in laterally aligning the pipes is to make sure thelateral resiliency of the isolation insulation is not used up, that none ofthe pipes is laterally stressed to begin with.

As a final step-not to be done unless absolutely necessary-it's possible tobend the pipes permanently to make better contact. Once bent even slightly,small rotations of the pipe will cause a big difference in how things fittogether. You can use this to your advantage. Don't do any more bending than is absolutely necessary; doingso weakens the mechanical bracing of the final mark.

Grouting: (5.10)

After assembling the appropriate materials, grouting can begin. This is messyand not the best thing for your health; dust masks are worthwhile. It's alsoimportant that preparations be made both at the mixer and the mark fordealing with grout spoils (sometimes substantial), ideally capturing the excess material and recycling it.

We'll want to keep a **good tally** of thegrout volumes at all stages: amounts sifted into preparatory trash cans, inthe mixer, lost, and-especially-in the boreholes.

| Your Site Name - DD-Mon-9X -Bags Used | | | | | |
|---------------------------------------|-------|--------|-------|--------|------|
| Time | ID | Sifted | Mixer | _Hole_ | Lost |
| X:XX | Vert. | NN | MM | | |
| X:YY | Vert. | | JJ | HH | KK |
| Y:YY | | | | | |

The most important issue being a clear record of what went into the _Hole_.

Mixing the grout is tricky, We've had muchbetter luck since we began sifting the grout in advance; the grout from thebag is sometimes not free of clumps and clumps can cause a stoppage duringpouring (a real setback for good cementing). Small amounts of water and grout (in that order at thestart-water first) should first be combined in the mixer, keeping the mix as``stiff" as possible as more grout is added, to avoid allowing the sand toprecipitate out (which can become a real problem downhole). First more grout and then more water.

We have a set of instructions from *Hub* for use with their *ChemGrout* grout pumper which suggests always adding the water first. Outside of getting started, with a small initial volume of grout in the mixer, we think this is a poor idea. (They must know something we don't.) These instructions are worth reviewing before leaving the lab; they provide lots of info on volumes.

Typically we find we need 9 50-lbs bags per hole (and this should leave you with some excess). Stack the empty bags flat to help keep count. For reference: a 50 lbs bag of expansive grout yields typically 0.43 cubic feet; we expect to need 3.6 cubic feet per hole, or 8.4 bags.

To avoid disappointment, if it seems you are going to run out of grout before completing the day's project, it's possible to make up your own grout using Portland cement, sand, bentonite, and an expansive additive. Armed, in advance, with the latter two components (they're needed in small volumes and are not expensive) a hurried trip to a hardware store to purchase the cement and mortar sand will keep you in business.

But, back to grouting. A "one sack" (9 cubic feet, but you can only fill it half full) mixer is the ideal size for filling one hole at a time. The important things are: (1) at the start, make sure the dry grout and water are mixing and not caking up on the bottom of the mixer - shake in the grout, and (2) there's not so much water in the mixer that the aggregate (sand) separates. It helps to run the mixer as fast as you can manage, as this helps mix the grout and water. It's most important not to add so much water that the grout begins to separate (with the sand at the bottom), but one wants to keep the grout very thin when it's ready for pouring. There is a critical point at which the grout has absorbed as much water as it can and any more water begins to cause separation. At this point, another pan-full of water is too much. A roughly analogous to the desired viscosity would be that of a fluidy milkshake.

When the batch of grout is ready, it can be poured into the pipe using the patented "grout funnel" (currently at the Smithsonian trailer at Pinon). Hammering on the pipe with a top maul can increase the flow rate a little (but risks causing the pipes to become misaligned - not so good a trade off), but the best idea is (1) to make sure the grout is thin, (2) that the pour is continuous. Perhaps the most difficult part here is to keep the supply of grout coming; we don't want trapped air down the hole. You'll need bulk of the crew assigned to mixer and their responsibilities well established beforehand.

If things go well the grout will come back up to the ground surface around the outside of the pipe. But if it doesn't quite make it, you should first try to measure down the annulus with a tape measure (or rebar) to establish what depth fill was achieved and then the remaining grout can be poured down the annulus to fill the gap to the surface. Again the funnel is quite useful. Do your best to keep grout off the pipes. And again, record the number of bags used, and how full the hole got before top filling. Typically if the grout has not made it back to the surface it's because the grout didn't have enough water in it to keep flowing, and became too viscous while pouring (remember the borehole will be absorbing lots of moisture). It's important that we get a good pour through the pipe at least back up to the casing (~15' down). It's a good idea to keep an eye on the grout in the pipe as it begins to harden as this usually involves some settling and the addition of grout can help achieve both a full pipe and a non-meniscus seal where the pipe and the casing meet.

Rebar: This is added to improve the odds that the monument will last a long time. Rebar inside the pipe should provide longitudinal strength for a very long period, even in the event of severe corrosion of the pipe. Basically we push this down the pipe just after adding all the grout. To do this, two 20'-long sections of rebar must be wired together to be ~38' long, using bailing wire, with the bailing-wire ends nicely folded so no one gets hurt, and so the overlapping part of the assemblage will fit into the pipe. This joint, with wire, is a tight fit in the pipe; the wire must be low profile. We want the top of the rebar to end up just below the top of the pipes (say 1-2").

Finishing off the cement work: When you're finishing up the work with the grout we want to make sure there isn't a water-entrapping area near the ground surface where the pipe comes out of the grout in its PVC casing. The grout will tend to settle during drying and we don't want a meniscus there that would tend to allow water to puddle and ultimately corrode the pipe. As the grout stiffens it should become possible to add grout to this area forming a sloping (and thus, water-shedding) surface.

Also, we want to top off the insides of the pipe to reduce the amount of water that can stand in this volume. Do this with coupling on the center pipe in place, finger tight, to assure those threads stay healthy. (Scoop out any grout much above the actual pipe top.) Don't put a wrench on the pipes or do anything else stressful while the grout is hardening, we want a good seal of grout to pipe at the casing tops.

To accomplish this finishing work it's often necessary to mix up a small patch of grout (say 1 gallon's worth) to have for buttering.

Welding: (5.11)

We expect the weld to be under a lot of stress after some period and that the weld will have to hold. Our aim is to make sure the weld is strong enough to cause whichever pipe is causing the most stress to yield to the others-to be pulled through the ground. Wow. Plans exist for welding-gussets to permit each of the angled pipes to be attached to the vertical one. Alignment of the pipes is crucial here, though all you can do is slide the contact point around, obviously it's impossible to mess with the length. We need at least 1" of clearance from the top of the vertical pipe to the upper lip of the angled ones. Using the detailed plans, align things as well as possible. Cold Galvanizing: The weld will tend to corrode fast. Wire brush it thoroughly, and spray with cold galvanizing. Then, after the cold galvanizing has hardened, spray the whole assembly with paint.

Pipe Finishing - Painting: (5.12)

We should clean, prime and **paint** the pipe, *and* the cement at the juncture of the two, to improve the resistance to corrosion. Particularly at this juncture, corrosion is a major concern.

Adaptor and Reference Height: (5.13/5.14)

This section actually covers a number of issues, usually dealt with at one time. The tools (denoted below by lines that end with open squares) are listed as well in the supplies list, so they could be ordered from here.

1. U-clamps remove/returned: most importantly because they're hazardous.
Tools: you will need some (wire brush, crescent wrench, etc.)
2. Pipe/concrete interface inspected and worked on to fix drainage (to discourage corrosion).
Perhaps fill lower half of adaptor with sealant, to reduce water catchment.
Material: This would require grout, sealant, or paint.
3. Painting of pipes especially at pipe/concrete interface.
Tools: Some paint and brushes (or spray paint).
4. Adaptor installed, *forever*, verifying first that level range is adequate.
Components for this: lower pipe-threaded portion (4 1/2"), upper leveling portion, nut, antenna support washer, and lots of bolts.
Tools: Two largish pipe wrenches (one very large: 24") for forceful attachment; anti-seize;
lab bubble-level; Allen wrench (5/32"); crescent wrench (small); more.
- 4.5 Dome support plate and Dome added. Tools: need special screw drivers for screws.
Components: support plate, dome, and special screws and drivers.
(screws made fairly tight so can't be unscrewed easily).
5. Reference divot drilled into vertical pipe, and lots of measurements made.
Tools: Cordless drill. Small bit (~2 mm diameter). Drawing of typical mark (what we want).
Tape measure (w/ English and metric); machinist scale.
6. Stamp REF PT (for example, next to the divot).
Tools: Special letter-punches for steel. (Do in lab?)
7. Stamp the name of the monument somewhere: (say) "CSUN"
Tools: Again, special letter-punches for steel. (Do in the lab, in advance?)
8. Take Pictures: both details and setting (including collapsed parking structure). Camera.
9. Installation/leveling and documenting: of adaptor and dome.
Drawings: Take copies of what we've done before, and procedure description (below).

Adaptor leveling: [this is the source-area for the procedure]

1. Make sure alignment marks on top and bottom parts of the adaptor are aligned. (Letter-stamped: "A".
2. Leveling screws should not be extended much more than needed for level compensation.
A final minimum gap of (say) 2 mm should be adequate for any subsequent fine adjustment.
3. With the antenna in place and the *lab bubble level* on some portion of its flat surface:
4. Level with all three clamping bolts loosened, any one can bind the leveling.
5. Tighten the clamping bolts sequentially and gradually, adjusting the leveling screws as you go.
Final leveling could be done by adjusting all three leveling screws-tightening.
6. Measure the height of the various elements of the adaptor, relative to the vertical-pipe divot in as many redundant ways as seems possible:
each element of height, with overlapping intervals, at three different azimuths, metric and English.

For the reference height work it's most valuable to bring along a copy of some previous measuring work, as model.

| | Your Site Name -DD-Mon-9X | | | | | | | |
|---|---------------------------|-------|---|-------|---|-------|---|-------|
| | N | (eng) | S | (eng) | E | (eng) | W | (eng) |
| A | x.xx cm | y.yy" | | | | | | |
| B | | | | | | | | |
| C | | | | | | | | |
| D | | 1.50" | | | | | | |

E
F
G
A+B
C+D+F+1.0

A - Top of upper half to top of outer lip of lower half (~"-3/8" from top of lower half).
B - Top of outer lip of lower half to top of referencedivot.
C - Gap from bottom of lower half to top of referencedivot [on _____side].
D - Full height of lower half (from its bottom, pastouter lip, to its top).
E - From very top of lower half to top of upper halfcylinder (should be "F" and 1.00").
F - Gap between upper and lower half (i.e.,verticality adjustment wedge).
G - Overall height estimate from top of divot to topof upper-half cylinder.

Checks:

$A+B = G$ And, the table shows that it _does, or does not_.
 $C+D+E = G$

At this site:

N, is really at azimuth of ____°

Height: Thus the height for the *top* of the adaptor'supper half-cylinder is X.XXX", or X.XX cm.

Angle of vertical post as inferred from *F*: The diameter of the wedge area is 3.5". Thus a maximum gap difference of 0.0__" means the vertical post at this site must be tipped 0.____ (0.0__ radians) to the _____.

Enclosure (7.02)

This requires an adequate foundation, andconstruction study enough to discourage vandalism.

Appendix B-2—Specifications for a Deeply Anchored and Braced Geodetic Monument (Drilled and Grouted)

1. Introduction

This document, together with the attached listings and drawings provides specifications for a standard "Wyatt type" braced geodetic monument. Attachments:

| | |
|-----------------------------------|-----------------------------|
| GPS Drawing Index, | (same name) |
| Assembly drawings | GPS-LA-100 through 103, |
| Subsurface/Pipes drawings | GPS-LA-1 through 4, |
| Antenna Adaptor drawings | GPS-LA-21 through 25.5, and |
| Parts List for GPS Antenna Mount. | (same name) |

Except as otherwise stated here, the dimensions and other specifications on these drawings shall be considered to be part of the specification of what is to be built.

In this monument design the legs of the monument (which are pipes) are grouted into boreholes. The upper part of the hole is cased, and the casing is surrounded with compliant foam to provide decoupling from the ground. The lower part of the hole, being uncased, is where the legs are attached directly to the surrounding soil or rock. The grout fills the holes and casings all the way to the surface both to anchor the legs and to provide protection against corrosion.

2. Drilling

There shall be four holes for the anchoring pipes. One shall be vertical to within $\pm 2^\circ$, the other four shall be drilled at 35° from vertical, to within $\pm 2.5^\circ$. The centerlines of all holes shall intersect within 6 inches of a point (though deviations of within 2-4 inches should be routinely achieved) whose height above the ground will be specified in each case by the SCIGN Coordinator. (This is referred to hereafter as the "intersection point"). All holes shall have a minimum diameter of 4.5 inches. All holes shall be straight enough that the foam encased casing specified in Section 2 can be inserted to its full seating depth, 15.5 feet (+0 and -4 feet), and that the pipe used for the anchoring legs (1.66 inches OD) can be freely lowered-not forced-for 33 feet. If there is a likelihood of "hole wander" during drilling (borehole curvature) the diameter should be increased but it should be kept as small as possible to minimize the amount of grout needed. The holes shall have a minimum length of 35 feet, as determined by actual measurement after drilling, and achieved, if necessary, by removing any loose material from the hole (commonly, by blowing it out with compressed air delivered to the bottom). The directions of the angled holes should be at 90° from each other, $\pm 5^\circ$. Where there is no advantage to one orientation of the holes over another (e.g., to make drilling easier or to minimize the monument footprint in some direction), the holes should be aligned in the cardinal directions, North, East, South and West. As a matter of practice, the vertical hole should be drilled first.

A record of the progress (e.g., times and drilling rates) and all pertinent events (e.g., depths and observations) during the drilling operation shall be kept and this information supplied to the Network Coordinator. Especially, all evidence of rock type and changes in ground composition and any evidence of ground water shall be recorded. We do not have in mind the need of a geologist for this effort.

3. Casing

The casing shall be one 16-foot length of belled-end Schedule 40 2.5 inch PVC pipe (2.875 inches OD). This casing shall be jacketed with compliant foam 0.75 inches thick, from within 0.75 foot of its top to within 0.75 foot of its bottom, attached in such a way as not to slip during installation. A clamp or collar on the casings shall be employed to cause the top of the casings to come to rest with approximately 6 inches extending above ground (measured to the midline for the casings in the angled holes), and for them to stay that way when loaded with the weight of the galvanized pipe and any other construction activities. The casings shall be inserted prior to inserting the anchoring pipes (below), usually during drilling to ensure the holes stay open, and with the intention that the tops (midlines for angled holes) of all casings are caused to be very nearly at the same level. These casings may be forced into the ground, using moderate weighting, but not using so much as to jeopardize the intended compliance of the jacketing foam.

4. Pipe

The legs shall be constructed from 21-foot sections of threaded Schedule-80 1.25-inch galvanized pipe (1.66 inches OD) joined with 1.25-inch Schedule-80, small-diameter couplings (that is, approximately 2.07 inch OD couplings). Each hole will require two sections of pipe, with the bottom section of pipe cut off to create the desired overall length: 32 feet of pipe below the ground surface and an appropriate amount above it. The pipe for the vertical hole shall be cut so that the upper threaded end will extend between 3 and 4 inches above the intersection point; this length is to be adjusted later to 3.5 inches. During construction this threaded end, in particular, shall be protected from damage. All couplings should be tightened firmly, to at least 50 ft-lb of torque. A centralizer or pipe collar shall be used on the lower section of pipe to ensure that the pipe is not everywhere resting against the borehole sidewall; drawing GPS-LA-4 shows a possible design.

5. Pipe Insertion and Alignment

Prior to insertion of the casing and pipe, all loose material above 35' hole length shall be removed from the hole, and the remaining material shall be compacted (doing this manually seems to work well) to assure a firm hole bottom. Shim material, small gravel, may be used to raise the level of the hole bottom (providing a secure bottom should any of the pipes get loose during construction and to reduce the amount of grout needed). Adjustable clamps shall be employed to support each of the five assembled anchoring pipes on the upper lip of their casing, with the desired length of pipe extending above the ground. With the casing already in place, each pipe section shall be lowered into its hole the connections made between paired pipe sections. The pipes must end up freely hanging in the holes (possibly judged by whether a single person can manually raise and lower the pipe).

Prior to grouting of the pipes their alignment shall be verified and adjustments made to achieve the following result: the vertical pipe shall extend 3.5 inches (- 0 and + 0.5 inches) past the intersection point and the angled-hole pipes extend 2.5 inches past their side contact with the vertical pipe at the intersection height. Drawing GPS-LA-2 shows this arrangement, with the angled pipes contacting the vertical one either in a clockwise or counterclockwise pattern. Length adjustment can be easily done by adjusting the support clamps. Lateral position adjustments may require the introduction of slight, permanent bends into the pipes where they exit the ground surface. These bends must not amount to more than 5 degrees of deflection (6 inches of displacement over 6 feet of pipe), putting a high priority on careful alignment of the boreholes, as discussed earlier. The pipes shall be temporarily held together at the intersection point to assure that they are in their correct position throughout grouting.

6. Grout and Grouting

The anchoring grout shall be both pumpable and expansive, using a non-metallic expansive additive. The expansive additive shall have completed no more than 20% of its total expansion at the time the grout is emplaced. This requires that the grout be made and poured in a timely fashion.

The grout shall be emplaced by pumping or pouring it through the interior of each pipe--not down the annulus between the pipe and the casing--until it reappears at the top of the casing, having made its way from its exit at the bottom of the pipe back to the ground surface. The grout shall be emplaced in such a way that no air bubbles are introduced. Ensuring a continuous flow of grout down through the pipe and back up the borehole to the surface requires proper materials (grout type and mixture) and grout-handling equipment. (Under ideal conditions, it is possible to perform this operation simply by pouring the grout, though this approach should not be pursued initially.)

After the grout has been emplaced in each pipe, at least 35 feet of half-inch reinforcing bar (typically two 20 foot sections of rebar lashed together with some overlap) shall be inserted inside the pipe. After emplacement the grout level inside the pipe shall be made flush with the top of the pipe to inhibit corrosion due to puddled water there. This step, of topping off the holes, can be done later if welding of the pipes is to be done immediately, before the grout begins to harden. In this case the grout level inside the pipe should be kept below the level of the weld but clearly visible (not too far down) to allow for monitoring the integrity of the grout inside the pipe. The grout at the surface of the casing (the annulus around the pipe near the ground surface) shall be finished off neatly and in such a way as to avoid puddling of water around the pipes: conically for the vertical pipe, and sloping or conical surface for the angled ones.

The total amount of grout emplaced in each hole shall be accurately recorded, and this information supplied to the Network Coordinator.

As each hole is completed the alignment of the pipes at the intersection point shall be verified, and every effort made to avoid agitating the pipes during curing.

7. Welding

It is expected that in most cases the welding will not be done simultaneously with grouting. In this situation the welding shall not be done until a minimum of 36 hours have passed since grouting. The pipes should be welded together with gussets as indicated in Drawing GPS-LA-2. The weld should be done to first-class standards, with galvanizing removed from the pipe in advance of welding. It is essential that the threads on the vertical pipe be kept in good condition and that there be at least 1 inch of clearance (to use these threads) from the top of the vertical pipe to the highest point of any of the angled pipes. While the welding equipment is present, it would be prudent to tack-weld the bottom section of the antenna adaptor in place (for security, discussed below), in a manner where the weld could be cut away with a saw should we want to remove the adaptor. After welding the surfaces shall be thoroughly wire brushed to remove all weakened material and contaminated surfaces, and the surfaces sprayed with "cold galvanizing" to assure long life of the weld.

8. Finishing

A clearly distinguishable, permanent divot (drilled with a bit approximately 0.063 inches in diameter, and to a depth of about 0.1 inches) shall be placed on the vertical pipe at least 0.375 inches and no more than 0.75 inches from the lowest point of the threads on the vertical pipe. The mark shall be metal stamped (along side) with the wording REF. A description of this reference-height divot, including its position and azimuthal location, shall be recorded. The exposed portions of all pipes (except for the threaded portion of the top of

the vertical pipe) but including the grout-filled ends of all pipes shall be coated with one coat of primer and one coat of exterior paint. The vicinity of the site shall be returned to its original condition. The area within 2 feet of each of the pipes shall be regraded as necessary to avoid the collection of water around them.

9. Adaptor

(1) An adaptor, (2) a antenna dome, and (3) a dome support plate shall be prepared in accordance with Drawings GPS-LA-21 through 26. The adaptor shall be fabricated from Type 304 or 316 stainless steel. The adaptor shall be attached to the threaded end of the vertical pipe firmly, using large pipe wrenches. The aim of securing the adaptor firmly is both for good stability and for reducing the prospects of vandalism. Toward these ends, it is suggested that the adaptor's lower section be tackwelded into place after it is tightened. [The SCIGN representative, when adjusting the adaptor for level and installing the antenna, should use drawing GPS-LA-100dim as a template for height-reference measurements.]

10. Inspection and Compliance

As the below-ground work can only be evaluated during the constructing work it is the intention of the SCIGN committee to have a representative present during the drilling and grouting phases of construction with authority to examine any part of the work. A representative will also review the final drilling and grouting records and inspect the finished monument and surrounding area and will report to the SCIGN Board on the quality of work and agreement with these specifications.

Appendix B-3 — Drawing Index -- GPS Monuments

| <u>Subject and Titles</u> | <u>Drawing No.</u> |
|---------------------------|--------------------|
| <u>Assembly</u> | |
| Total Installation | GPS-LA-100 |
| Complete Assembly | GPS-LA-101 |
| Center Assembly | GPS-LA-102 |
| Dome Assembly | GPS-LA-103 |
| Assembly Drawing - Ht | GPS-LA-101dim |
| <u>Subsurface/Pipes</u> | |
| Subsurface Assy. Plan | GPS-LA-1 |
| Surface Assy Plan | GPS-LA-2 |
| Casing Prep | GPS-LA-3 |
| Pipe Centralizer Plan | GPS-LA-4 |
| <u>Adaptor</u> | |
| Washer | GPS-LA-21 |
| Tilt Block | GPS-LA-22 |
| Base | GPS-LA-23 |
| Plastic Base | GPS-LA-24 |
| Modified Dome | GPS-LA-25 |
| Plastic Dome Side View | GPS-LA-25.5 |

Parts List -----

Early - Rock and Wall Type

| | | |
|----------------------------|-------|------|
| GPS Stand for Pine Meadows | GPS 0 | [NA] |
| SIO2 Antenna Mount - Ht | GPS 1 | [NA] |
| Rocha Antenna Mount - Ht | GPS 2 | [NA] |

Parkfield-93 - Two-Color EDM

| | | |
|--|-------|------|
| Parkfield Center pipe | GPS 3 | [NA] |
| Parkfield Center Pipe fitting | GPS 4 | [NA] |
| Parkfield Subsurf. Assy. Plan | GPS 5 | [NA] |
| Parkfield Borehole/Pipe/Insulation Choices | GPS 6 | [NA] |
| Parkfield Surface Assembly Plan | GPS 7 | [NA] |
| Parkfield Reflector Fitting | GPS 8 | [NA] |

Appendix B-4 — Rock mark specifications

Appendix B-5 — Receiver box

Minimum dimensions:

Minimum gauge steel:

Built-in lock

Water tight

Box must be ventilated.

If outdoors, the box must include thermostatically controlled forced ventilation.

Appendix C — Receiver placement and maintenance

Introduction

The SCIGN management requires placement of Global Positioning System (GPS) receivers at approximately 36 newly constructed sites in the Los Angeles metropolitan area. The SCIGN management also requires maintenance of approximately 76 sites in the Los Angeles metropolitan area, 40 existing and 36 new. We expect that this will be done primarily by a Network Coordinator (Appendix D) located at the SCEC offices in Pasadena. To assist the Network Coordinator in this effort we expect to execute an add-on to an existing seismic station maintenance contract (with Allied Signal) currently in place at the USGS Pasadena.

Contract requirements

The contractor will assist network coordinator in installing a receiver at each new site.

The contractor will make one routine maintenance visit to each site in each six month period.

In addition, the contractor will respond within 48 hours, to requests from the the data processing centers about the status of particular sites.

The add-on agreement should specify that GPS station maintenance receives equal priority with seismic station maintenance, particularly during critical post-seismic time periods.

The contractor will assist the Network Coordinator in maintaining a www-accessible log file for each station in the array.

The contractor will add an entry to the appropriate log file for each visit to a station, documenting the station condition and any changes that were made.

The contractor may be supervised by a representative of the SCIGN board as necessary to resolve problems and to ensure contract compliance.

Detailed specifications for construction of the mark are included in Appendix C-1

Detailed drawings for construction of the mark are included in Appendix C-2

Appendix D — Network coordinator

Introduction

Operation of the SCIGN network will be overseen by a Network Coordinator. The network coordinator will be hired by SCEC with funds provided by the USGS. The position will be located at the SCEC center at 535 Wilson Street, Pasadena, California. The duties of the network coordinator will be to insure that the entire network is maintained in an operational state at all times. SCIGN is a distributed network. Downloading occurs at three locations; processing and data archiving are done at two different processing centers. To insure that the entire network functions smoothly, SCIGN needs someone who will take responsibility for checking on the whole network. When there are problems, the network coordinator will work with the various data centers and maintenance people to correct them. The network coordinator will also act as a single point of contact for the network.

Job announcement

The Southern California Integrated GPS Network (SCIGN) is seeking a Network Coordinator.

Note: In an attempt to circulate this widely, we are distributing it to several mailing lists. We apologize to anyone receiving more than one copy.

Introduction

SCIGN is a distributed Global Positioning System network with data downloading and archiving occurring at several locations. Currently SCIGN consists of about 40 sites; the number of sites is growing. The duties of the network coordinator will be to insure that the entire network is maintained in an operational state at all times. The network coordinator will work with the various data centers and maintenance people to insure that the network operates reliably and to maintain adequate records on the stations that compose the network.

Location:

The position will be located at the SCEC center at 535 Wilson Street, Pasadena, California adjacent to the U.S. Geological Survey Pasadena office and to the CalTech campus.

Position description

Coordinate selection of new SCIGN sites.

Coordinate construction of monuments at new SCIGN sites.

Supervise or carry out the placement of receivers at the new sites.

Check status of all network stations daily.

Insure that all stations are tracking and providing data to the appropriate data center.

Coordinate trouble shooting on any down stations to locate the source of problem.

Coordinate the required maintenance to bring down stations back on line.

Coordinate all hardware, firmware and software upgrades to the receivers.
Maintain site logs for all sites.
Maintain site change logs for all sites.
Be responsible for downloading sites that come into Pasadena office (SCIGN sites are downloaded at a number of different facilities).
Maintain communication with both processing centers (JPL, SOPAC) to insure that stations are providing needed data and information.

Qualifications

Experience with Unix, Mac and PC operating systems
Experience with GPS receiver hardware and data handling
Experience with data communications via modem, radio, and telephone links.
Ability to interact constructively with the variety of groups involved in operating SCIGN.
Ability to pay attention to details.
Ability to work independently.

To apply

Send extended resume to the chairman of the selection committee:
Ken Hudnut (hudnut@seismo.gps.caltech.edu)

Applications will be accepted until the position is filled.

Appendix E — Forms

Site evaluation

Location rejection

JPL Permission form

Station Horizon mask

Site Evaluation Form (1 of 2)

| | |
|---|------------|
| Site name, number, or description _____ | |
| Observer's name _____ | Date _____ |

Sky view and multipath _____

Permanence _____

Security & Safety _____

Site geology _____

Access _____

Power _____

Phone _____

Site Evaluation Form (2 of 2)

| | |
|---|------------|
| Site name, number, or description _____ | |
| Observer's name _____ | Date _____ |

Permission _____

Landuse fees _____

Receiver occupation test _____

DigAlert _____

Attach eight photographs of the site: looking north, south, east and west from the site; and looking north, south, east and west at the site. The proposed antenna site should be marked with a stake that appears in four of the photos.

Attach additional pages if more space is needed. It is not necessary to transcribe information onto this form. If it is more conveniently available in another format, just attach copies. Copies of other relevant information should also be attached.



Station Horizon Mask

Station Name or Number: _____ Date: _____

Location/description: _____


Total number of obscured
blocks above 15°: _____

Observer's name: _____



SCIGN 1996-03-03

Appendix F — New site location maps




Continue on Page 50

ISABELLA LAKE

D

35°30' 18" N




© Delorme

Continue on Page 53

Contour Interval 100 meters

BAKERSFIELD



Continue on Page 49

Continue on Page 64

Continue on Page 60




Continue on Page 73 inset

© DeLorme

Contour Interval 100 meters

Scale 1:150,000

Continue on Page 62




35'00"

Continue on Page 75

© DeLorme

Contour Interval 100 meters

Continue on Page 76





34°30' 118°37'30" 7C

© DeLorme
Continue on Page 80

Contour interval 100 meters
1:111 m/mphs = 328 ft/feet

Scale 1:150,000

Continue on Page 78



77

Continue on Page 91

Contour interval 100 meters (1100 meters = 3280.8 feet)

Scale 1:150 000



1 QUARTER MAP ON BACK OF ATLAS


Continues on Page 82

78

LOS ANGELES CO
VENTURA CO

Continue on Page 77

Continue on Page 80



34°30' 117°33'00"

79


Continue on Page 83

Contour interval 100 meters (1100 meters = 3280.84 feet)

Scale 1:150,000

67


Continue on Page 80



Continua on Page 82

C

D



34°30' 117°00'

Continua on Page 85


Contour interval 100 meters (100 meters = 328.08 feet)

NOT REPRODUCED

Scale 1:150,000

81

Continue on Page 82



Continue on Page 87


30 00

85

A


NEEDLES

Continue on Page 86




87

Continue in DeLorme's Arizona Atlas & Gazetteer YUCCA AZ



Continue on Page 73

Continue on Page 92



118°45'

91

© DeLorme


Contour Interval 100 meters
1:100 meters = 1:29 (66 feet)

91

14:36

Continue on Page 77


D



B SAN BERNARDINO

Continue on Page 92

Continue on Page 96



11700

Continue on Page 105

© Del Norte

Contour interval 100 meters

Page 63


04/24/96

14:43

818 393 4965

JPL

2006



Continue on Page 95

Continue on Page 105


Continue on Page 68

TWENTYNINE PALMS

D


34700
11670 20

97




Continue on Page 107

© DeLorme
Contour Interval 100 meters



Continue on Page 97

Continue on Page 106




Continue on Page 113

Contour interval 100 meters

DeLorme

105



117700 24'00"

Continue on Page 95

6

5


SAN BERNARDINO

SAN BERNARDINO

BANNING A

B

Continue on Page 106



Continue on Page 105

Continues on Page 114


04/24/96

14:59

818 393 4965

JPL


012




Continue on Page 96

Continue on Page 105

106




| | | | |
|---|--------------|-----------------------------|------------|
| University of California IGPP 0225 La Jolla, California 92093 | | | |
| GPS LA Antenna | | TITLE Total Installation | |
| DRAWN BY P Zimmer/ CBH | DATE 13Apr95 | DRAWING NUMBER | GPS-LA-100 |
| Do Not Scale This Drawing | SCALE 1"=8" | | |



Complete Assembly


| | | | |
|---|--|---------------------------|--|
| University of California IGPP 0225 La Jolla, California 92093 | | DATE 12Apr95 | |
| GPS Antenna Mounts | | SCALE 1" = 3" | |
| DRAWN BY C. B. Hollinshead | | Do Not Scale This Drawing | |
| TITLE Complete Assembly | | DRAWING NUMBER GPS-LA-101 | |



Scale: 1" = 3" when first printed; after copying check against dimensions above.


Assembly Dimensions

| | | | |
|---|-----------------|---------------------------------|------------------|
| University of California IGPP 0226 La Jolla, California 92093 | | TITLE Assembly | |
| DRAWN BY mod. Frank Wyatt Do Not Scale This Drawing | DATE 31Oct95 | DRAWING NUMBER GPS-LA-101dim | SCALE 1" = 3" |



Center Assembly


| | | | |
|---|---------------|---|------------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x .x .xx .xxx angular 1/64" .1" .01" .005" 1deg | |
| GPS Antenna Mounts | | TITLE Center Assembly | |
| DRAWN BY C. B. Hollinshead | DATE 11Apr95 | DRAWING NUMBER | GPS-LA-102 |
| Do Not Scale This Drawing | SCALE 1" = 2" | | |



Dome Assembly

| | | | |
|---|---------------|---|------------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x .x .xx .xxx angular 1/64" .1" .01" .005" 1deg | |
| GPS Antenna Mounts | | TITLE Dome Assembly | |
| DRAWN BY C. B. Hollinshead | DATE 12Apr95 | DRAWING NUMBER | GPS-LA-103 |
| Do Not Scale This Drawing | SCALE 1" = 2" | | |


1 1/4" Sch 80 Galv. Pipe filled with Hub 100 Grout and 1/2" rebar



this print is missing its overlay cuts

Note: All pipe assemblies 1 1/4" Sch 80 Pipe with standard Sch. 40 couplings
All casings 2 1/2" Sch. 40 PVC Pipe with 3/4" wall insulating foam

| | | | |
|---|--------------|---|----------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) X/4 .X .XX .XXX angular 1/64" .1" .01" .005" 1deg | |
| Piñon Flat Observatory | | TITLE Subsurface Assembly Plan | |
| DRAWN BY Paul Zimmer | DATE 1/19/95 | DRAWING NUMBER | GPS-LA-1 |
| Do Not Scale This Drawing | SCALE | | |



Gusseted with 1/4" steel triangles welded between angled anchors and vertical anchor
See Detail

Angled pipe extends 2.5" beyond intersection point

Spot Welded at intersection of angled anchors and vertical anchor

Vertical pipe extends 3.5" beyond int. point

Intersection height

Pipe clamp prevents pipe from slipping into casing before pouring grout and while grout sets

62" (1.57m)

35°
~60° to clamp

72° to clamp


76°

43.5"


Side View of Pipe clamp (angle iron and U-bolt)

| | | | |
|---|--------------|----------------|-----------------------|
| University of California IGPP 0225 La Jolla, California 92093 | | | |
| Piñon Flat Observatory | | TITLE | Surface Assembly Plan |
| DRAWN BY Paul Zinner | DATE 1/18/95 | DRAWING NUMBER | GPS-LA-2 |
| Do Not Scale This Drawing | SCALE 1"=8" | | |

12-Oct-95





1 1/4" Sch. 80 Galv.
 Pipe, 2 1/2" Sch 40 PVC
 Pipe Casing, 3/4" Wall
 Insulation Foam




 - 1 1/4" Pipe Coupling

 - Sch. 80 Galv. Pipe (1 1/4" pipe)


 - Sch. 40 PVC Pipe (2 1/2" pipe)

 - Drilled Hole (5" Nom.)

 - Non-Shrink Grout (Tremgrout 747)


 Insulation Foam - (Armstrong 2 5/8" Nom. ID, 3/4" Wall)

 - 1/2" Rebar




Armstrong 2 5/8" I.D. 3/4" Wall Insulation Foam, wrapped along length with strapping tape to secure foam, then wrapped with duct tape

| | | | |
|---|--------------|--------------------------|--|
| University of California IGPP 0735 La Jolla, California 92093 | | TITLE Casing Preparation | |
| Piñon Flat Observatory | | DRAWING NUMBER GPS-LA-3 | |
| DRAWN BY Paul Zimmer | DATE 1/18/95 | SCALE | |
| Do Not Scale This Drawing | | | |



| | | | |
|---|--------------|---|--|
| University of California IGPP 0225 La Jolla, California 92093 | | TITLE Borehole Pipe Centralizer Plan | |
| Piñon Flat Observatory | | DRAWING NUMBER GPS-LA-4 | |
| DRAWN BY Paul Zimmer | DATE 1/19/95 | | |
| Do Not Scale This Drawing | SCALE 2"=1' | | |



Washer

Mat'l: 304/316 Stainless



1 req'd per unit

| | | | |
|---|---------------|---|-----------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x .x .xx .xxx angular 1/64" .1" .01" .005" 1deg | |
| GPS Antenna Mounts | | TITLE Washer | |
| DRAWN BY C. B. Hollinshead | DATE 11Apr95 | DRAWING NUMBER | GPS-LA-21 |
| Do Not Scale This Drawing | SCALE 1" = 1" | | |

Drill & Tap
10-24 thru
3 places @ 120°
on 3.125" DBC

Drill 5/16" D thru
3 places @ 120°
on 2.25" DBC

Drill 5/8" D thru;
See GPS-LA-102
for assembly --
welded bolt



stamp letter for
orientation
1 place

Adaptor Leveling Block

Mat'l: 304/316 Stainless

1 req'd per unit


| | | | |
|---|---------------|--|-----------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x x .xx .xxx angular 1/64" .1" .01" .005" 1deg | |
| GPS Antenna Mounts | | TITLE Leveling Block | |
| DRAWN BY C. B. Hollinshead | DATE 11Apr95 | DRAWING NUMBER | GPS-LA-22 |
| Do Not Scale This Drawing | SCALE 1" = 1" | | |

1/4" x 1/8" dp.
Vee groove
3 places @ 120°


1.25" NPT thru
from bottom

Drill #7 thru
Tap 1/4"-20
x .75" dp.
3 places @ 120°
on 2.25" DBC

Drill #7 thru &
Tap 1/4"-20 X .75" dp.
6 places @ 60°
on 4.125" DBC



was
1 1/4"
at
Nothridge
Talker




stamp letter for
orientation
1 place

Adaptor Base

Mat'l: 304/316 Stainless

1 req'd per unit

| | | | |
|---|---------------|--|-----------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x x .xx .xxx angular 1/64" .1" .01" .005" 1deg | |
| GPS Antenna Mounts | | TITLE Adaptor Base | |
| DRAWN BY C. B. Hollinshead | DATE 11Apr95 | DRAWING NUMBER | GPS-LA-23 |
| Do Not Scale This Drawing | SCALE 1" = 1" | | |




Plastic Base

Mat'l: 3/8" Lexan


1 req'd per unit

| | | | |
|---|---------------|---|-----------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x .x .xx .xxx angular 1/64" .1" .01° .005" 1deg | |
| GPS Antenna Mounts | | TITLE Plastic Base | |
| DRAWN BY C. B. Hollinshead | DATE 12Apr95 | DRAWING NUMBER | GPS-LA-24 |
| Do Not Scale This Drawing | SCALE 1" = 4" | | |



Modified Plastic Dome
Mat'l: 1/4" Opaque White Acrylic
1 req'd per unit

| | | | |
|---|----------------------|---|------------------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x .x .xx .xxx angular 1/64" .1" .01" .005" 1deg | |
| GPS Antenna Mounts | | TITLE Modified Plastic Dome | |
| DRAWN BY C. B. Hollinshead | DATE 11Apr95 | DRAWING | GPS-LA-25 |
| Do Not Scale This Drawing | SCALE 1" = 4" | NUMBER | |



Note: Extrude Acrylic into approx. hemisphere to the specifications shown above, with lip as shown

Plastic Dome
Mat'l: 1/4" Opaque
White Acrylic

| | | | |
|---|-----------------|---|-------------|
| University of California IGPP 0225 La Jolla, California 92093 | | Tolerances +/- (unless specified) x/x .x .xx .xxx angular 1/64" .1" .01" .005" 1deg | |
| GPS Antenna Mounts | | TITLE Plastic Dome Side View | |
| DRAWN BY Paul Zimmer | DATE 20 Apr. 95 | DRAWING NUMBER | GPS-LA-25.5 |
| Do Not Scale This Drawing | SCALE 1" = 4" | | |

Parts List for GPS Antenna mount

| <u>Part Description</u> | <u># req'd</u> | <u>Refer to Drawing No.</u> |
|--|----------------|-----------------------------|
| Washer | 1 | GPS-LA-21 |
| Adaptor -- Upper half | 1 | GPS-LA-22 |
| Adaptor -- lower half | 1 | GPS-LA-23 |
| Plastic Base | 1 | GPS-LA-24 |
| Modified Dome | 1 | GPS-LA-25 |
| 10-24 x 0.5" SS set screw (w/ rounded ends) | 3 | GPS-LA-102 |
| 1/4"-20 x 1.75" SS soc cap | 3 | GPS-LA-102 |
| 1/4"-20 x 0.75" SS hex bolt | 6 | GPS-LA-102 |
| 1/4"- 18-8 SS Sex Bolts - 3/4" lg (McMaster Carr #90650A102, p. 2378, cat. #99) | 6 | GPS-LA-103 |
| 5/8"-11 x 2.5" SS bolt | 1 | GPS-LA-102 |
| 5/8"-11 SS nut | 1 | GPS-LA-102 |