

(200)

T67r

no. 436

OFFICIAL USE ONLY

# Uranium in the Mayoworth Area, Johnson County, Wyoming- A Preliminary Report


RESOURCE COMPILATION SECTION

By J. D. Love

~~GEOLOGICAL SURVEY  
EPCO  
RECEIVED~~

~~SEP 13 1954~~

~~Denver~~



*Trace Elements Investigations Report 436*

*GS.C. 358*

UNITED STATES DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

OFFICIAL USE ONLY

OFFICIAL USE ONLY

Geology and Mineralogy

This document consists of 25 pages.  
Series A

UNITED STATES DEPARTMENT OF THE INTERIOR  
GEOLOGICAL SURVEY

URANIUM IN THE MAYOWORTH AREA,  
JOHNSON COUNTY, WYOMING --  
A PRELIMINARY REPORT\*

By

J. D. Love

April 1954

Trace Elements Investigations Report 436  
*GS-C-358*

This preliminary report is distributed without editorial and technical review for conformity with official standards and nomenclature. It is not for public inspection or quotation.

\*This report concerns work done on behalf of the Division of Raw Materials of the U. S. Atomic Energy Commission.

When separated from Part II, handle Part I as UNCLASSIFIED.

OFFICIAL USE ONLY

GEOLOGY AND MINERALOGY

<u>Distribution (Series A)</u>	<u>No. of copies</u>
National Lead Company, Winchester . . . . .	1
Argonne National Laboratory . . . . .	1
Atomic Energy Commission, Washington . . . . .	1
Battelle Memorial Institute, Columbus . . . . .	1
Carbide and Carbon Chemicals Company, Y-12 Area . .	1
Division of Raw Materials, Albuquerque . . . . .	1
Division of Raw Materials, Butte. . . . .	1
Division of Raw Materials, Denver . . . . .	1
Division of Raw Materials, Douglas . . . . .	1
Division of Raw Materials, Hot Springs . . . . .	1
Division of Raw Materials, Ishpeming . . . . .	1
Division of Raw Materials, Phoenix . . . . .	1
Division of Raw Materials, Richfield . . . . .	1
Division of Raw Materials, Salt Lake City . . . . .	1
Division of Raw Materials, Washington . . . . .	3
Dow Chemical Company, Pittsburgh . . . . .	1
Exploration Division, Grand Junction Operations Office .	1
Grand Junction Operations Office . . . . .	1
Technical Information Service, Oak Ridge . . . . .	6
Tennessee Valley Authority, Wilson Dam . . . . .	1
U. S. Geological Survey:	
Alaskan Geology Branch, Menlo Park . . . . .	1
Fuels Branch, Washington . . . . .	3
Geochemistry and Petrology Branch, Washington . . .	1
Geophysics Branch, Washington . . . . .	1
Mineral Deposits Branch, Washington . . . . .	2
E. H. Bailey, Menlo Park . . . . .	1
K. L. Buck, Denver . . . . .	1
J. R. Cooper, Denver . . . . .	1
N. M. Denson, Denver . . . . .	2
C. E. Dutton, Madison . . . . .	1
W. L. Emerick, Plant City . . . . .	1
A. L. Brokaw, Grand Junction . . . . .	1
L. S. Gardner, Albuquerque . . . . .	1
M. R. Klepper, Washington . . . . .	1
A. H. Koschmann, Denver . . . . .	1
R. A. Laurence, Knoxville . . . . .	1
D. M. Lemmon, Washington . . . . .	1
J. D. Love, Laramie . . . . .	1
V. E. McKelvey, Menlo Park . . . . .	1
A. Q. Taylor, Salt Lake City . . . . .	1
Q. D. Singewald, Beltsville . . . . .	1
J. F. Smith, Jr., Denver . . . . .	1
A. E. Weissenborn, Spokane . . . . .	1
TEPCO, Denver . . . . .	2
TEPCO, RPS, Washington . . . . .	3
(Including master)	59

## CONTENTS

	Page
Abstract . . . . .	4
Introduction . . . . .	5
Geographic setting . . . . .	7
Geologic setting . . . . .	8
Stratigraphy . . . . .	10
Uranium occurrences . . . . .	13
Description of localities . . . . .	13
Locality 1 . . . . .	13
Locality 2 . . . . .	16
Origin of uranium in the Mayoworth area . . . . .	19
Literature cited . . . . .	23
Unpublished reports . . . . .	24

## ILLUSTRATIONS

Plate 1. Section from Bighorn Mountains through Mayoworth to North Pumpkin Butte . . . . .	9
Figure 1. Geologic map of Mayoworth area . . . . .	6
2. Stratigraphic section of rocks near Mayoworth, Wyoming . . . . .	11
3. Uranium Locality 1 in oolitic basal limestone of Sundance formation . . . . .	14
4. Photomicrograph x 40 of polished surface of oolites in basal limestone of Sundance formation replaced by metatyuyamunite at Locality 1 . . . . .	14

## TABLE

Table 1. Analyses of samples from Mayoworth area . . . . .	17
--	----



URANIUM IN THE MAYOWORTH AREA, JOHNSON COUNTY,  
WYOMING -

A PRELIMINARY REPORT

By J. D. Love

ABSTRACT

The uranium mineral, metatyuyamunite, occurs in the basal limestone of the Sundance formation of late Jurassic age along the east flank of the Bighorn Mountains, about 2 miles southwest of the abandoned Mayoworth post office. This occurrence is of particular interest because it is the first uranium mineralization reported from a marine limestone in Wyoming. The discovery uranium claims were filed in July 1953, by J. S. Masek, Dan Oglesby, and Jack Emery of Casper, Wyo. Subsequent reconnaissance investigations have been made by private individuals and geologists of the U. S. Geological Survey and Atomic Energy Commission.

The metatyuyamunite is concentrated in a hard gray oolitic limestone that forms the basal bed of the Sundance formation. A selected sample of limestone from a fresh face in the northernmost deposit known at the time of the field examination contained 0.70 percent equivalent uranium and 0.71 percent uranium. Eight samples of the limestone taken at the same place by the Atomic Energy Commission contained from 0.007 to 0.22 percent uranium. A chip sample from the weathered outcrop at the top of this limestone half a mile to the southeast contained 0.17 percent equivalent uranium and 0.030 percent uranium. A dinosaur bone

from the middle part of the Morrison formation contained 0.044 percent equivalent uranium and 0.004 percent uranium.


Metatyuyamunite forms a conspicuous yellow coating along fracture planes cutting the oolitic limestone and has also replaced many of the oolites within the solid limestone even where fractures are not present.

Many radioactive spots in the basal limestone of the Sundance formation were examined in a reconnaissance fashion along the outcrop for a distance of half a mile south of the initial discovery. Samples were taken for analysis only at the northern and southern margins of this interval. Outcrops farther north and south were not studied.

There are not sufficient data to make even rough estimates of tonnage and grade of the occurrences. The extent of the limestone, the approximate boundaries of the area of above-normal radioactivity, and the possibilities of other radioactive zones have not been thoroughly investigated. Although dinosaur bones in the Morrison formation were radioactive wherever they were tested, no significant amount of radioactivity was observed in rocks adjacent to the bones.

## INTRODUCTION

The Mayoworth area is located in the southwestern part of Johnson County, Wyo. (fig. 1). Several detailed stratigraphic sections were measured by the writer in this area in 1944 and additional studies were made in 1949 and 1950 as part of oil and gas investigations of the Geological Survey. The first uranium claims were filed in July 1953, by J. S. Masek, Dan Oglesby, and Jack Emery of Casper, Wyo. Subsequently, reconnaissance



investigations of the area were made by private individuals and geologists of the U. S. Geological Survey and the U. S. Atomic Energy Commission (Geslin, 1953). The writer examined the uranium occurrences to study their geologic setting and to obtain data on their origin. No mining or detailed exploration has been done, as of April 1, 1954.

The writer is indebted to Robert S. Houston for the photograph of the polished section of mineralized limestone (fig. 4). Except where specified otherwise, the Denver Laboratory of the U. S. Geological Survey made the chemical analyses. Alice D. Weeks of the Geological Survey identified the uranium mineral as metatyuyamunite.

Stratigraphic and structural studies of the Mayoworth area and the region directly to the north have been made by several geologists (Love and others, 1945a; Richardson, 1950, and Hose, in preparation).

Fairchild Aerial Surveys, Inc., compiled topographic maps of the area, scale 1:24,000, with a 20-foot contour interval, for the Bureau of Reclamation. These maps are not published but are available to the public through the Bureau of Reclamation.

The reconnaissance examination of the Mayoworth area was made on behalf of the Division of Raw Materials of the U. S. Atomic Energy Commission.

## GEOGRAPHIC SETTING


The Mayoworth area lies along the western margin of the Powder River Basin. Directly to the west, the land surface rises onto the east



flank of the Bighorn Mountains. The altitude of the uranium discovery is about 5,450 feet, and on the crest of the mountains 10 miles to the west, the general altitude is about 8,000 (plate 1). The area is drained by intermittent streams, all tributaries to the North Fork of Powder River. There are no towns, and the Mayoworth post office, which was in the northeast corner of the area (fig. 1) has been discontinued. At Mayoworth, a graded county road that traverses the area from south to north intersects an oiled road from Kaycee, which is the closest town, 12 miles to the southeast. The topography is rough, for the alternating sets of hard and soft strata have been dissected into strike ridges and strike valleys. Vegetation is sparse and bedrock is comparatively well exposed. Livestock raising is the only industry.

### GEOLOGIC SETTING



The Mayoworth area is at the foot of the east flank of the Bighorn Mountains, where the rugged mountain topography begins to flatten out into the Powder River Basin (plate 1). The exposed rocks are of Triassic, Jurassic, and Early Cretaceous ages and have monoclinal dips of  $10^{\circ}$  to  $15^{\circ}$  to the northeast (fig. 1). It is believed that the rocks were folded at the close of Paleocene time, when the principal arching of the Bighorn Mountains occurred. There may have been slight subsequent movement here, but it cannot be proved or disproved. Data from adjacent localities indicate that the Powder River Basin was largely filled with Eocene, Oligocene, and probably younger rocks (Love, 1952,



EXPLANATION

- White River fm. (Oligocene)
- Wasatch fm. (lower Eocene)
- Fort Union fm. (Paleocene)
- Mesozoic rocks
- Paleozoic rocks
- Pre-Cambrian rocks

SECTION FROM BIGHORN MOUNTAINS THROUGH MAYOWORTH TO NORTH PUMPKIN BUTTE



INDEX MAP SHOWING LOCATION OF SECTION

plates 2 and 3, and p. 5). Remnants of Oligocene and Miocene (?) tuffaceous claystones and sandstones are present on the crest of the Bighorn Mountains northwest of Mayoworth at altitudes of 7,500 to 9,000 feet. These remnants were laid down on a rugged topography (plate 1) and are still essentially undeformed.

## STRATIGRAPHY

Figure 2 presents summary descriptions and thicknesses of the rock units in the vicinity of the uranium occurrences in the Mayoworth area. Richardson (1950) and Hose (in preparation) have described the stratigraphy of the Paleozoic and Mesozoic rocks of this general area in some detail, and there are published descriptions of lithology and correlation of sections of the Morrison, Cloverly, and Thermopolis formations (Love and others, 1945b).

The Chugwater formation, of Triassic age, directly underlies the Sundance formation in this area, is about 800 feet thick, and consists of 3 members. At the base is the Red Peak member, which is about 700 feet thick and composed of brick red soft shale, siltstone, and silty sandstone. The uppermost 20 feet is massive red silty sandstone in the vicinity of the uranium occurrences. Overlying the Red Peak member is the Alcova limestone member, which consists of gray to pink thin-bedded slabby limestone ranging in thickness from a feather edge to 2 feet. The Alcova limestone is lenticular and wedges out, only to reappear at the same stratigraphic horizon farther along the outcrop.




FIGURE 2.--STRATIGRAPHIC SECTION OF ROCKS NEAR  
MAYOWORTH, WYOMING



Overlying the Alcova limestone member where it is present is the Crow Mountain sandstone member which consists of about 100 feet of salmon pink massive to cross-bedded fine-grained sandstone. The member characteristically outcrops in cliffs. In places where the Alcova limestone member is absent, it is difficult to distinguish the Crow Mountain sandstone member from the uppermost sandstone in the Red Peak member. The upper part of the Crow Mountain sandstone is commonly silty and soft and forms a slope capped by the resistant basal limestone of the overlying Sundance formation.

The Crow Mountain sandstone member has been mistaken for the somewhat younger Nugget sandstone of areas farther west by many geologists because both sequences have almost identical lithology.

The Gypsum Spring formation is present along the east flank of the Bighorn Mountains farther north but wedges out at about the north boundary of the Mayoworth area.

The Sundance formation consists of two sequences, a lower one called the "lower Sundance," comprising about 200 feet of non-glaucinitic sandstone and shale with the uranium-bearing oolitic limestone at the base, and an upper one called the "upper Sundance" composed of greenish glauconitic shale and sandstone about 150 to 175 feet thick. Both sequences contain marine fossils. The basal limestone of the "lower Sundance" is oolitic, hard, and forms a conspicuous ledge in the Mayoworth area but thins and disappears both to the north and to the south. Its maximum thickness is about 20 feet. This limestone superficially

resembles the non-oolitic Alcova limestone member of the Chugwater formation and has been mistaken for it by some geologists. Peterson (1954) has described the Sundance rocks in this general region and figured oolitic beds in the upper part of the "lower Sundance."

The Morrison, Cloverly, and Thermopolis formations have been described (Love, and others, 1945b) and the lithology is summarized in figure 2.

### URANIUM OCCURRENCES

Uranium has been found in the basal limestone of the Sundance formation and in dinosaur bones in the overlying Morrison formation. Other rocks in the area were not examined in detail for uranium by the writer. An airborne survey has been made (Jones, 1952, p. 10) by the Atomic Energy Commission.

#### Description of localities

##### Locality 1

Locality 1 (NE 1/4 NW 1/4 SW 1/4 sec. 3, T. 44 N., R. 83 W.) is the site of the discovery claim staked by J. S. Masek and associates, in the marine basal limestone of the Sundance formation of Late Jurassic age. The outcrops are on a northeastward-facing dip slope (fig. 3). Strata strike N. 30° W., and dip 12° northeast. The following stratigraphic section was measured at the place of best exposed uranium mineralization. Unit 1 is the oldest.




Figure 3. --Uranium Locality 1 in oolitic basal limestone of Sundance formation. Slope in background is stripped dip slope on top of basal limestone. Arrow indicates camera case for scale. A selected sample at this point contained 0.71 percent uranium.




Figure 4. --Photomicrograph x 40 of polished surface of oolites in basal limestone of Sundance formation replaced by metatyuyamunite at Locality 1. Light-colored oolites and portions of oolites, and white irregular deposits between oolites are metatyuyamunite.

Unit No.	Thickness (in feet)	Lithologic character
Top of section		
5	20+	Shale, pale green, soft; forms valley at base of dip slope
4	4	Limestone, brown, oolitic, hard, but softer than underlying unit; irregularly bedded in upper half; contains metatyuyamunite in middle 2 feet (fig. 3); top of unit forms prominent dip slope (fig. 3); contains fragments of oysters, bryozoans, and other marine fossils
3	2.5	Limestone, brown, oolitic, very hard, evenly-bedded, weathering into conspicuous slabs one-half to 1 inch thick
2	2.5	Limestone, grayish-brown, massive, very sandy, with some small chert pebbles; highly oolitic

Contact between Sundance formation and Crow Mountain sandstone member of Chugwater formation. Contact is very sharp and even.

1	3+	Siltstone, brick red, sandy, soft. Underlying strata are not exposed at this locality.
---	----	--

Metatyuyamunite is visible in the middle 2 feet of unit 4 throughout a distance of 27 feet in an east-west direction and 7 feet in a north-south direction. The most conspicuous yellow color is on fracture faces, but, as is shown in figure 4, the metatyuyamunite has replaced oolites within unfractured limestone. The most radioactive spots are along ferruginous brown clayey partings, where a scintillation counter shows 1.5 mr/hr. A 1-pound selected sample of the limestone taken for mineral identification contained 0.70 percent equivalent uranium, 0.71 percent uranium, and 0.56 percent  $V_2O_5$ . The average uranium content of this limestone face



is much lower. Table 1 shows analyses of additional samples taken at locality 1. The replacement of the oolites indicates that uranium was introduced after the sediments were deposited. The limestone contains oysters, bryozoans, and other fossils of marine origin.

Approximately 100 feet to the southwest of the largest mineralized exposure, and at the same stratigraphic position, is a place about 6 feet in diameter where metatyuyamunite is visible. This place had not been dug out at the time of examination so its extent and thickness could not be determined.

On the same dip slope with these two mineralized spots are numerous other spots where radioactivity is considerably above background, but no metatyuyamunite is visible and no digging was done. At the time of examination, no drilling had been done in the area and the deepest pit was about 3 feet, so conclusions as to the economic possibilities of this locality are not warranted at present.

#### Locality 2

Locality 2 (SW 1/4 SE 1/4 SW 1/4 sec. 3, T. 44 N., R. 83 W.) is about half a mile southeast of locality 1, along strike and in the same oolitic limestone bed at the base of the Sundance formation. A scintillation counter showed a maximum reading of 2.0 mr/hr (as compared with 1.5 mr/hr at locality 1) at the contact between the brown oolitic limestone and the overlying green shale. At this place a 1-pound sample of the limestone contained 0.17 percent equivalent uranium, 0.30 percent

TABLE 1. --ANALYSES OF SAMPLES FROM MAYOWORTH AREA 1/

Laboratory sample no.	Locality	Equiv. U (percent)	Uranium (percent)	V <sub>2</sub> O <sub>5</sub> (percent)	Location (see fig. 1), lithology, and formation
99511	1	0.70	0.71	0.56	NE 1/4 NW 1/4 SW 1/4 sec. 3, T. 44N., R. 83 W., oolitic limestone in basal part of Sundance formation.
93857 <u>2/</u>	1	.015	.019	.08	"
03858 <u>2/</u>	1	.10	.017	.07	"
93859 <u>2/</u>	1	.012	.007	.12	"
94559 <u>2/</u>	1	.017	.025	.20	"
94560 <u>2/</u>	1	.17	.18	.17	"
94561 <u>2/</u>	1	.21	.22	.12	"
94562 <u>2/</u>	1	.12	.17	.24	"
94563 <u>2/</u>	1	.30	.040	.29	"
99510	2	.17	.030	.10	SW 1/4 SE 1/4 SW 1/4 sec. 3, T. 44N., R. 83 W., oolitic limestone in basal part of Sundance formation.
99512		.044	.004	.08	NE 1/4 sec. 14, T. 44 N., R. 83 W., dinosaur bone in Morrison formation.

1/ Samples analyzed in Denver Laboratory, U. S. Geological Survey.

Analysts: Furman, Mountjoy, Schuch, Wilson, Fennelly, McGurk, and Meadows.

2/ Samples collected by geologists of the Atomic Energy Commission, Douglas, Wyoming Sub-office.

uranium and 0.10 percent  $V_2O_5$ . The sample was taken from a bedding plane surface and the limestone was so hard that it could be dug to a depth of only about 3 inches with the tools at hand. No uranium was observed in this near-surface sample, but the relatively high radioactivity suggests that if a pit or drill hole were put down at this spot, uranium minerals might be found.

Many spots of radioactivity much higher than background were encountered along the dip slope of this limestone for the next quarter mile to the south. One showed a maximum of 1 mr/hr. Lack of time prevented more detailed reconnaissance or mapping of the extent of this oolitic limestone, but it is likely that the richest and most extensive uranium occurrences were not found.

In the middle part of the Morrison formation at a place about 2 miles southeast of locality 2 (NE 1/4 sec. 14, T. 44 N., R. 83 W.), radioactive dinosaur bones occur in considerable abundance in a medium-grained gray and brown sandstone (fig. 2). A sample of bones contained 0.044 percent equivalent uranium, 0.004 percent uranium, and 0.08 percent  $V_2O_5$ . The sandstone in which the bones are embedded shows radioactivity a little above background and the underlying green and dully variegated claystone is slightly more radioactive than the sandstone.

Neither the Morrison formation nor the overlying Cloverly formation, or the Muddy sandstone member of the Thermopolis shale has been examined in sufficient detail for radioactivity by the writer to justify any conclusion as to the possibility of uranium deposits in these rocks.

Carbonaceous material is present in the sandstones, and lenticular beds of lignitic material are present in several places. Jones (1952, p. 10) indicates that he made complete radiometric flight coverages of outcrops of the Sundance, Morrison, and Cloverly formations and the Muddy sandstone member, in this entire region without discovering any anomalies. This would suggest that the radioactivity in the vicinity of localities 1 and 2 is hard to detect from the air, an observation that has been corroborated by commercial geologists who flew the area after uranium was discovered.

#### ORIGIN OF URANIUM IN THE MAYOWORTH AREA

The origin of the uranium in the Mayoworth area has not been determined and can only be inferred from a study of regional relationships. As shown in figure 4, metatyuyamunite has replaced some of the limestone oolites, in addition to being concentrated along fracture planes that developed after the limestone was lithified. The area is essentially unfaulted, although a thrust fault is present a short distance to the north. The folding is believed to have taken place at the close of Paleocene time. It is reasonable to assume that most of the fracturing occurred at the time of folding. There is no evidence of vein deposits other than, perhaps, the metatyuyamunite concentrated along fractures, or of Mesozoic or Tertiary igneous activity of any kind in the region. Reflection seismograph and magnetometer surveys of the Powder River Basin have not indicated any buried intrusive rocks younger than pre-Cambrian.

The closest outcropping pre-Cambrian rocks are 6 miles to the north on an anticlinal nose called "The Horn," which is separated from the Mayoworth area by a thrust fault, south of which is a syncline (Love and Weitz, 1951).

Slightly more than a mile northeast of the map area (fig. 1), in the SE 1/4 SW 1/4 SE 1/4 sec. 24, T. 45 N., R. 83 W., the Stanolind Oil and Gas Co., Brock No. 1 dry hole was drilled to a depth of 4,011 feet, starting in the Frontier formation of Late Cretaceous age and bottoming in the Madison limestone of Mississippian age. A radioactivity log of this test shows no zones of abnormally high radioactivity in any formation penetrated.

A study of radioactivity logs in the Powder River Basin indicates that the basal part of the Sundance formation is typically not radioactive. However, a conspicuous exception is in the Little Buck Creek oil field, 130 miles to the southeast, where the basal sandstone in the Sundance formation, in a comparable stratigraphic position, and approximately the same age as the oolitic limestone in the Mayoworth area, is moderately radioactive at a depth of about 4,500 feet.

Because it is believed likely that the origin of radioactivity in the Sundance formation in both the Mayoworth and Little Buck Creek areas is similar, and because the sedimentary record at Little Buck Creek is more complete, it seems pertinent to make a comparison of the structural and stratigraphic relationships. At the north end of the Hartville uplift is a northward-plunging anticline in Paleozoic and Mesozoic rocks, named the Lusk Dome by Denson and Botinelly (1949). This dome is 12



miles south of the Little Buck Creek oil field. The White River formation of Oligocene age was deposited in deep valleys and on rugged topography cut in the rocks on this northward-plunging structural nose. The basal sandstone in the Sundance formation is very porous and permeable and outcrops of this sandstone are directly overlain by the White River formation. Radioactivity logs show that the White River formation in this area is radioactive, and 8 samples taken from it southeast of Little Buck Creek show equivalent uranium contents averaging 0.003 percent and with a maximum of 0.008 percent. Radioactivity anomalies in the White River formation have been reported by Mallory (1953) 6 miles to the north and 7 miles to the southwest of Little Buck Creek. An analysis from the latter locality contained 0.02 percent uranium.

Water samples taken by M. L. Troyer (personal communication, 1953) from the White River formation of this general area contain moderately high concentrations of uranium. It is believed that in past geologic time uranium was leached out of the White River formation as readily as at present, and was carried in solution in ground water down dip along the porous basal sandstone of the Sundance formation. This sandstone contains hydrocarbons in small quantity in the Little Buck Creek oil field, and it is possible that uranium was deposited where the hydrocarbons were concentrated. It is also conceivable that the structure of the area prohibited further migration of the uranium-bearing ground water.

It is possible to account for the uranium occurrence in the Mayoworth

area in the same manner. About 13 miles to the northwest, on top of the Bighorn Mountains, at a general altitude of approximately 8,000 feet are many remnants of tuffaceous claystone, sandstone, and conglomerate of the Oligocene White River formation (plate 1). These rocks are slightly radioactive (Love, 1952, p. 17). They were deposited on a surface of high relief. Similar remnants are present on Pumpkin Buttes, 40 miles to the east, at an altitude of 6,000 feet (plate 1). These remnants contain as much as 0.007 percent uranium and are thought to be the source rocks for the uranium deposits in the underlying Wasatch formation (Love, 1952, p. 17-19). The strata at Pumpkin Buttes are dated as early Oligocene (Chadronian) on the basis of the following vertebrate fossils (M. J. Hough, personal communication 1954): Hyracodon? priscidens, Hyracodon sp., Archaeotherium sp., Trigonias osborni, Mesohippus cf. M. westoni, Leptomeryx sp., and a rhinocerotid, probably Subhyracodon.

It is believed that the White River formation extended eastward from the crest of the Bighorn Mountains to Pumpkin Buttes (plate 1). The White River strata were deposited across the upturned and eroded edges of the Jurassic rocks at a point about 2,500 feet structurally higher than the uranium occurrence near Mayoworth. It is known that the uranium-bearing oolitic limestone grades laterally into coarse-grained sandstone. The limestone is directly underlain by the soft, porous, and permeable Crow Mountain sandstone member which is 100 feet thick. Uranium leached from the White River formation could easily have migrated in

solution in ground water down dip along these porous rocks and have been deposited in the oolitic limestone. The factors that caused deposition in the limestone are not known. Some of the brown color, which is associated with the greatest radioactivity, may be caused by the presence of hydrocarbons.

Metatyuyamunite is known from the White River formation at several localities and is the principal mineral in a few of the deposits in the underlying Wasatch formation of the Pumpkin Buttes area (M. L. Troyer, personal communication).

#### LITERATURE CITED

- Denson, N. M., and Botinelly, Theodore, 1949, Geology of the Hartville uplift, eastern Wyoming: U. S. Geol. Survey Oil and Gas Map OM-102.
- Love, J. D., 1952, Preliminary report on uranium deposits in the Pumpkin Buttes area, Powder River Basin, Wyoming: U. S. Geol. Survey Circ. 176.
- Love, J. D., and others, 1945a, Stratigraphic sections and thickness maps of Triassic rocks in central Wyoming: U. S. Geol. Survey Oil and Gas Chart 17.
- \_\_\_\_\_, \_\_\_\_\_, 1945b, Stratigraphic sections and thickness maps of Lower Cretaceous and non-marine Jurassic rocks of central Wyoming: U. S. Geol. Survey Oil and Gas Chart 13.
- Love, J. D., and Weitz, J. L., 1951, Geologic map of the Powder River Basin and adjacent areas, Wyoming: U. S. Geol. Survey Oil and Gas Map OM 122.
- Peterson, J. A., 1954, Marine Upper Jurassic, eastern Wyoming: Am. Assoc. Petrol. Geol. Bull., v. 38, p. 463-507.

## UNPUBLISHED REPORTS

- Geslin, H. E., 1953, Mayoworth district, Johnson County, Wyoming: U. S. Atomic Energy Comm., Prelim. Recon. Rept. DEB-RRD-726.
- Hose, R. K., in preparation, Geology of the Crazy Woman Creek area, Johnson County, Wyo.: U. S. Geol. Survey Bull.
- Jones, E. E., 1952, Airborne radiometric survey of the east flank of the Big Horn Mountains, Wyoming and Montana: U. S. Atomic Energy Comm. RME-4006.
- Mallory, N. S., 1953, Airborne radiometric survey of Lusk area, Niobrara, Platte, and Goshen Counties, Wyoming: U. S. Atomic Energy Comm. RME-46.
- Richardson, A. L., 1950, Geology of the Mayoworth region, Johnson County, Wyoming: Univ. of Wyo., Unpub. M. A. thesis.

USGS - TEI-437, Part II

PLANS

It is not the purpose of this study to make an economic evaluation of the uranium occurrences in the Mayoworth area, but rather, because it is a unique marine limestone deposit, to present the geologic setting, type of mineralization, characteristics of the host rock, general pattern of distribution, and theory of origin of the uranium.

Several organizations with small planes equipped with scintillation counters have flown along the outcrops of the basal limestone of the Sundance formation and adjacent formations. The Atomic Energy Commission (Jones, 1952, p. 10) reports a complete flight coverage of the Sundance, Morrison, and Cloverly formations and the Muddy sandstone member of the Thermopolis shale, along the entire east flank of the Big-horn Mountains, without finding any anomalies.

If additional work in the area by a government agency is desired, the following approach is suggested:

1. Outcrops of the basal limestone of the Sundance formation should be walked out, mapped, and examined in detail with a scintillation counter.
2. Areas of significantly high radioactivity might be drilled or pitted to determine extent, pattern, and grade of mineralization.

If these studies are made, it is hoped that they will provide data on the origin and factors determining the localization of the uranium.