

RECONNAISSANCE INVESTIGATION OF WATER QUALITY, BOTTOM SEDIMENT, AND BIOTA ASSOCIATED WITH IRRIGATION DRAINAGE IN THE SAN JUAN RIVER AREA, SAN JUAN COUNTY, NORTHWESTERN NEW MEXICO, 1990-91

By Paul J. Blanchard, U.S. Geological Survey;
Richard R. Roy, U.S. Fish and Wildlife Service; and
Thomas F. O'Brien, U.S. Fish and Wildlife Service

U.S. GEOLOGICAL SURVEY
Water-Resources Investigations Report 93-4065

U.S. GEOLOGICAL SURVEY
U.S. FISH AND WILDLIFE SERVICE
U.S. BUREAU OF RECLAMATION
U.S. BUREAU OF INDIAN AFFAIRS

Albuquerque, New Mexico
1993



U.S. DEPARTMENT OF THE INTERIOR

BRUCE BABBITT, Secretary

U.S. GEOLOGICAL SURVEY

Dallas L. Peck, Director

For additional information
write to:

District Chief
U.S. Geological Survey
Water Resources Division
4501 Indian School Road NE, Suite 200
Albuquerque, New Mexico 87110

Copies of this report can
be purchased from:

U.S. Geological Survey
Books and Open-File Reports
Federal Center
Box 25425
Denver, Colorado 80225

CONTENTS

	Page
Abstract.....	1
Introduction.....	2
Purpose and scope.....	4
Acknowledgments.....	5
General description of the study area.....	5
Department of Interior-sponsored irrigation projects.....	7
Climate.....	8
Geology.....	9
Soils.....	11
Hydrologic setting.....	11
Water supply.....	11
Hydrology of Department of Interior-sponsored irrigation projects....	13
Previous studies.....	17
Sample collection and analysis.....	18
Sampling sites.....	20
Sampling methods.....	30
Analytical support.....	31
Discussion of results.....	33
Concentrations of trace elements in water.....	33
Concentrations of trace elements in bottom sediment.....	39
Concentrations of trace elements in biota.....	41
Pond and wetland community members.....	42
Fish in the San Juan River.....	47
Birds.....	54
Concentrations of pesticides in water.....	59
Concentrations of pesticides in bottom sediment.....	59
Concentrations of pesticides in biota.....	59
Fish in the San Juan River.....	60
Birds.....	60
Concentrations of hydrocarbons in water.....	62
Summary	63
Selected references.....	66
Supplemental data.....	70

FIGURES

Page

Figure 1.	Map showing the San Juan River area, Department of Interior-sponsored irrigation projects, and streamflow-gaging stations.....	6
2.	Graph showing median of average monthly precipitation and 1990 monthly precipitation at four locations in the San Juan River area.....	8
3.	Map showing geology of the San Juan River area.....	10
4.	Map showing irrigation water delivery system on the Navajo Indian Irrigation Project.....	14
5.	Schematic diagram of the water distribution systems on the Hammond, Fruitland, Hogback, and Cudei Irrigation Projects..	16
6.	Map showing energy resource areas and production activities in the San Juan River area.....	19
7.	Map showing water-quality, bottom-sediment, and biota sampling sites on or adjacent to Department of Interior-sponsored irrigation projects.....	21
8.	Map showing water-quality and bottom-sediment sampling sites and fish-sampling reaches on the San Juan River and at the mouths of tributary streams.....	24
9.	Box plot showing concentrations of dissolved selenium in water samples from irrigation project sites.....	37
10.	Box plot showing distribution of concentrations of selenium in all species of suckers collected for the National Contaminant Biomonitoring Program (NCBP) in 1984, and in flannelmouthed suckers from the San Juan River in 1990.....	50
11.	Box plot showing distribution of concentrations of copper in carp collected for the National Contaminant Biomonitoring Program (NCBP) in 1984 and from the San Juan River in 1990.....	51
12.	Box plot showing distribution of concentrations of lead in all species of suckers collected for the National Contaminant Biomonitoring Program (NCBP) in 1984, and in flannelmouthed suckers from the San Juan River in 1990.....	52
13.	Box plot showing distribution of concentrations of mercury in all species of suckers collected for the National Contaminant Biomonitoring Program (NCBP) in 1984, and in flannelmouthed suckers from the San Juan River in 1990.....	53
14.	Box plot showing concentrations of selenium in adult birds collected from the San Juan River area.....	56

TABLES

		Page
Table 1.	Streamflow-gaging stations, period of record, and average discharge in the San Juan River area.....	12
2.	Schedule of major crop irrigated acreage on the Navajo Indian Irrigation Project.....	15
3.	Sampling ("I") sites located on or adjacent to irrigation projects.....	22
4.	San Juan River reaches from which fish samples were collected, and water and bottom-sediment sampling ("R") sites within each river reach.....	25
5.	Number of samples and types of analyses for media at sampling sites on irrigation projects, the San Juan River, and tributaries.....	26
6.	Number of bird samples collected for analysis of inorganic constituents at sites on irrigation projects.....	28
7.	Types of analyses conducted on fish samples from reaches of the San Juan River.....	29
8.	Laboratory reporting levels for selected constituents in water and bottom sediment.....	32
9.	Comparison of baseline concentrations of selected constituents in samples collected from rivers of the United States with concentrations in 28 samples from the San Juan River, diversions, and tributaries, and in 48 samples from irrigation project sites.....	34
10.	U.S. Environmental Protection Agency and State of New Mexico water-quality standards for selected constituents.....	35
11.	Concentrations of selected trace elements in soils of the Western United States, in soils from the San Juan Basin, in bottom sediment from 19 National Irrigation Water-Quality Program (NIWQP) study areas, and in bottom sediment from the San Juan River area.....	40
12.	Ranges of whole-body concentrations of selected trace elements in biota from pond and wetland sites.....	43
13.	Selenium concentration ranges and medians for pond and wetland community media.....	44
14.	Pond and wetland sites in which the concentrations of selenium in biota exceeded food-item criteria.....	45
15.	Comparison of concentrations of trace elements in fish samples collected for the National Contaminant Biomonitoring Program (NCBP) with samples collected from the San Juan River in 1990.....	48

TABLES--Concluded

		Page
Table 16.	Summary of selenium concentrations in adult bird liver and kidney tissue at each sampling site or group of sampling sites.....	55
17.	Number of bird embryo samples in each of three selenium-concentration categories at each sampling site or group of sampling sites.....	58
18.	Comparison of acetylcholinesterase (AChE) activity in brain tissue of bird samples collected in the San Juan River area with diagnostic ranges of AChE activity.....	61
19.	Cholinesterase activity in brain tissue and blood serum of adult drake mallard samples collected on the Navajo Indian Irrigation Project in mid-May 1990 and from mid-June to mid-July 1990.....	62
20.	Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990.....	71
21.	Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990.....	86
22.	Concentrations of selected constituents in bottom sediment: fall 1990.....	94
23.	Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990.....	102
24.	Concentrations of selected constituents in composite samples of whole-body fish from the San Juan River: spring and fall 1990.....	109
25.	Concentrations of selected constituents in individual edible-portion fish samples from the San Juan River: 1990.....	113
26.	Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990.....	117
27.	Concentrations of pesticides in water and bottom-sediment samples: 1990.....	129
28.	Concentrations of organochlorine compounds in composite whole-body flannelmouthed sucker samples: 1990.....	135
29.	Concentrations of organochlorine compounds in individual bird carcass samples: 1990.....	136
30.	Cholinesterase enzyme activity in brain tissue and blood serum of birds: 1990.....	140

CONVERSION FACTORS AND ABBREVIATED WATER-QUALITY UNITS

<u>Multiply</u>	<u>By</u>	<u>To obtain</u>
acre (acre)	0.4047	hectare
acre-foot (acre-ft)	0.001233	cubic hectometer
cubic foot per second (ft ³ /s)	0.02832	cubic meter per second
foot (ft)	0.3048	meter
gallon per minute (gal/min)	3.748	liter per minute
inch (in.)	25.40	millimeter
mile (mi)	1.609	kilometer
quart (qt)	0.937	liter

Temperature in degrees Celsius (°C) can be converted to degrees Fahrenheit (°F) as follows: °F = 1.8 (°C) + 32.

Specific conductance is reported in microsiemens per centimeter (μS/cm) at 25 degrees Celsius.

Chemical concentrations in water are reported in milligrams per liter (mg/L) or in micrograms per liter (μg/L), which are equivalent to parts per million and parts per billion, respectively, when concentrations are less than about 7,000 milligrams per liter.

Chemical concentrations in sediment are reported in micrograms per gram (μg/g) or in micrograms per kilogram (μg/kg), which are equivalent to parts per million and parts per billion, respectively.

Chemical concentrations in biota are reported in micrograms per gram (μg/g), or micrograms per kilogram (μg/kg), which are equivalent to parts per million and parts per billion, respectively.

RECONNAISSANCE INVESTIGATION OF WATER QUALITY, BOTTOM SEDIMENT,
AND BIOTA ASSOCIATED WITH IRRIGATION DRAINAGE IN THE SAN JUAN
RIVER AREA, SAN JUAN COUNTY, NORTHWESTERN NEW MEXICO, 1990-91

By Paul J. Blanchard, U.S. Geological Survey;
Richard R. Roy, U.S. Fish and Wildlife Service; and
Thomas F. O'Brien, U.S. Fish and Wildlife Service

ABSTRACT

Selenium is the trace element of major concern in the San Juan River area. Concentrations of selenium larger than established standards and criteria were present in water, bottom sediment, and biota in four areas on three irrigation projects: the middle and north ponds in Gallegos Canyon on the Navajo Indian Irrigation Project (NIIP) (two sites), the Ojo Amarillo Canyon drainage on the NIIP (two sites), a pond receiving irrigation drainage water on the West Hammond Irrigation Project (one site), and a drain on the eastern part of the Hogback Irrigation Project (one site). Ground-water return flow from irrigated areas contributes substantially to surface water at these sites.

Selenium concentrations in nine surface-water samples collected from these sites exceeded the U.S. Environmental Protection Agency Primary Drinking Water Standard Maximum Contaminant Level of 50 $\mu\text{g/L}$ (micrograms per liter). One additional sample concentration also exceeded the State of New Mexico standard of 5 $\mu\text{g/L}$ designated for the protection of fisheries.

Selenium concentrations in five bottom-sediment samples from the middle pond in Gallegos Canyon, Ojo Amarillo Canyon, and the Hogback Project ranged from 4.5 to 37 $\mu\text{g/g}$ (micrograms per gram). The geometric mean concentration of selenium in soils of the Western United States is 0.23 $\mu\text{g/g}$.

Selenium concentrations in biota at six sites in Gallegos and Ojo Amarillo Canyons, the West Hammond Pond, and the Hogback east drain ranged from 3.0 to 32.3 $\mu\text{g/g}$ in eight invertebrate samples, 4.22 to 51.3 $\mu\text{g/g}$ in five amphibian samples, and 13.6 to 41.7 $\mu\text{g/g}$ in six fish samples. Selenium concentrations in 18 of these 19 samples were within or larger than the 4- to 8- $\mu\text{g/g}$ dry-weight waterfowl food-item criterion. Six fish samples from these sites also had concentrations larger than the 12- $\mu\text{g/g}$ whole-body concentration above which reproductive failure can occur.

The largest median concentrations of selenium in bird liver and kidney tissue were in six bird samples from the Gallegos Canyon ponds (31.2 $\mu\text{g/g}$) and four bird samples from Ojo Amarillo Canyon ponds (20.5 $\mu\text{g/g}$). Embryo deformities usually occur when the median selenium concentration in a population is larger than 30 $\mu\text{g/g}$; however, the potential for embryo deformities exists when the concentration of selenium is between 10 and 30 $\mu\text{g/g}$. Due to lack of availability, however, only one embryo from the Gallegos and Ojo Amarillo Canyons was examined for teratogenesis. The results of embryo examinations conducted during this study, therefore, are inadequate to accurately determine conditions throughout the San Juan River area.

Eleven of 15 plant samples, 6 of 15 invertebrate samples, and 4 of 14 fish samples collected from irrigation project sites had concentrations of lead larger than the criterion for predator protection of about 1 $\mu\text{g/g}$ dry weight. Four of 13 common carp and flannelmouthed sucker samples had lead concentrations and 4 of 13 flannelmouthed sucker samples had mercury concentrations larger than the respective 85th-percentile concentrations in these species collected for the National Contaminant Biomonitoring Program (NCBP).

Concentrations of DDE were larger than laboratory reporting levels in 8 of 10 bottom-sediment samples, 6 of 6 flannelmouthed sucker samples, and 31 of 35 bird samples. In 8 of 16 killdeer samples, concentrations of DDE were equal to or larger than the 1.0- $\mu\text{g/g}$ wet-weight criterion for the protection of predators. No concentration in any of the 22 organochlorine compound analyses in the six fish samples was as large as the respective NCBP geometric mean concentration.

INTRODUCTION

During the last several years, there has been increasing concern about the quality of irrigation drainage and its potentially harmful effects on human health, fish, and wildlife. Concentrations of selenium greater than water-quality criteria for the protection of aquatic life (U.S. Environmental Protection Agency, 1987) have been detected in subsurface drainage from irrigated land in the western part of the San Joaquin Valley in California. In 1983, incidences of mortality, birth defects, and reproductive failures in waterfowl were discovered by the U.S. Fish and Wildlife Service at the Kesterson National Wildlife Refuge in the western San Joaquin Valley where irrigation drainage was impounded. In addition, potentially toxic trace elements and pesticide residues have been detected in other areas in western States that receive irrigation drainage.

Because of concerns expressed by the U.S. Congress, the U.S. Department of the Interior (DOI) started a program in October 1985 to identify the nature and extent of irrigation-induced water-quality problems that might exist in the western States. The DOI developed a management strategy and formed an interbureau group known as the "Task Group on Irrigation Drainage," which prepared a comprehensive plan for reviewing irrigation-drainage concerns for which DOI may have responsibility.

Initially, the task group identified 20 areas in 13 States that warranted reconnaissance-level investigations related to three specific activities: (1) irrigation or drainage facilities constructed or managed by the DOI, (2) National Wildlife Refuges managed by the DOI, and (3) other migratory-bird or endangered-species management areas that receive water from DOI-funded projects.

Nine of the 20 areas were selected for reconnaissance investigations during 1986-87:

Arizona-California:	Lower Colorado-Gila River Valley area
California:	Salton Sea area
	Tulare Lake Bed area
Montana:	Sun River Reclamation Project area
	Milk River Reclamation Project area
Nevada:	Stillwater Wildlife Management area
Texas:	Lower Rio Grande-Laguna Atascosa
	National Wildlife Refuge area
Utah:	Middle Green River Basin area
Wyoming:	Kendrick Reclamation Project area.

Reports for these nine reconnaissance investigations have been published. On the basis of results of these investigations, four detailed studies were initiated in 1988 for the Salton Sea area, Stillwater Wildlife Management area, Middle Green River Basin area, and the Kendrick Reclamation Project area.

Eleven more reconnaissance investigations were initiated in 1988:

California:	Sacramento Refuge Complex
California-Oregon:	Klamath Basin Refuge Complex
Colorado:	Gunnison and Uncompahgre River Basins
	and Sweitzer Lake
	Pine River Project
Colorado-Kansas:	Middle Arkansas River Basin
Idaho:	American Falls Reservoir
New Mexico:	Middle Rio Grande Project and Bosque del
	Apache National Wildlife Refuge
Oregon:	Malheur National Wildlife Refuge
South Dakota:	Angostura Reclamation Unit
	Belle Fourche Reclamation Unit
Wyoming:	Riverton Reclamation Project.

Evaluation of results in published reports of these investigations, and a continuing evaluation of all data for the Irrigation Drainage Program led to initiating three more detailed studies in 1990-91:

California-Oregon:	Klamath Basin Refuge Complex
Colorado:	Gunnison River Basin/Grand Valley Project
Montana:	Sun River area.

In October 1989, four reconnaissance investigations were begun and another was started in October 1990. The study areas are:

Oregon-Idaho:	Owyhee-Vale Projects
Nevada:	Humboldt Wildlife Management area
Colorado:	Dolores Project area
New Mexico:	San Juan River area
Washington:	Middle Columbia River Basin.

All reconnaissance investigations are conducted by interbureau study teams composed of a scientist from the U.S. Geological Survey as team leader, with additional Geological Survey, U.S. Fish and Wildlife Service, U.S. Bureau of Reclamation, and U.S. Bureau of Indian Affairs scientists representing several different disciplines. The investigations are directed toward determining whether irrigation drainage: (1) has caused or has the potential to cause significant harmful effects to human health, fish, and wildlife; or (2) may adversely affect the suitability of water for other beneficial uses.

Purpose and Scope

The purpose of this report is to present information for determining if irrigation drainage from the DOI-sponsored irrigation projects in the San Juan River area: (1) has caused or has the potential to cause significant harmful effects to human health, fish, or wildlife; or (2) may reduce the suitability of water for beneficial uses. The San Juan River area was selected for study because data from previous studies in the area indicated that concentrations of some inorganic and organic substances may be large enough to cause or have the potential to cause these harmful effects or to reduce the suitability of water for beneficial uses. Additionally, the geologic units of the area, consisting of primarily sedimentary formations of Cretaceous and Tertiary age, have the potential to yield significant amounts of selenium and other trace elements to water, bottom sediment, and biota.

The scope of this study included collection and analysis of water, bottom-sediment, and biota samples from the San Juan River upstream and downstream from and adjacent to the DOI-sponsored irrigation projects; from diversions from the San Juan River; and from wetlands, ponds, and streams within and at areas of discharge of the irrigation projects, including backwater habitats. Sample collection was conducted from April 1990 through December 1990. Samples were analyzed for concentrations of major ions, selected trace elements, and selected pesticides. Acute toxicity tests were conducted on water samples from selected sites to determine the toxicity of water to selected organisms. This report describes the areal distribution of concentrations of selected constituents in the various media and how these concentrations relate to irrigation drainage from the DOI-sponsored irrigation projects.

Acknowledgments

Appreciation is extended to Ernest Teller and Phillip Tollenaar of the Agricultural Testing and Research Laboratory, Navajo Agricultural Products Industry, for use of laboratory facilities; to Jeffrey Cole, Navajo Nation Fish and Wildlife, for assistance in obtaining sample collection permits; to Raymond Smith, U.S. Bureau of Indian Affairs, for assistance in field sampling and sample preparation; and to Leif Ahlm, State of New Mexico Department of Game and Fish, for providing housing and work space. The authors also thank Sky Bristol, volunteer, U.S. Fish and Wildlife Service, for contributions throughout the study.

GENERAL DESCRIPTION OF THE STUDY AREA

The San Juan River area is located in San Juan County, northwestern New Mexico (fig. 1). The area includes an approximately 90-mi reach of the San Juan River valley from Navajo Dam, about 30 mi upstream from Farmington, New Mexico, to the mouth of the Mancos River, about 25 mi downstream from Shiprock, New Mexico, and an adjacent upland area. The upland area is south of the San Juan River valley, approximately bounded by the Chaco River on the west, Hunter Wash on the south, and New Mexico State Highway 44 on the east.

The San Juan River and adjacent wetlands provide habitat for endangered species, native southwestern fish species, sportfish, and the plant and animal communities on which they depend. About 200 species of birds are at least partially dependent on the riparian habitat along the San Juan River; of these, about 100 species are directly dependent on this habitat for survival and reproduction (Meneely and others, 1979).

The Federally endangered bald eagle (Haliaeetus leucocephalus), peregrine falcon (Falco peregrinus), Colorado squawfish (Ptychocheilus lucius), and razorback sucker (Xyrauchen texanus) are known to live in the San Juan Basin (Meneely and others, 1979). Species designated by the State of New Mexico as endangered and known to inhabit the San Juan Basin include three mammal, eight bird, two amphibian, and four fish species (Meneely and others, 1979).

Wildlife surveys are conducted routinely in the San Juan River drainage by the New Mexico Department of Game and Fish. During the winter 1991-92 surveys, as many as 33 bald eagles, 17,900 Canada geese, and 11,800 ducks were observed in the San Juan River drainage (Donald MacCarter, New Mexico Department of Game and Fish, written commun., 1992).




Figure 1.--San Juan River area, Department of Interior-sponsored irrigation projects, and streamflow-gaging stations.

Department of Interior-Sponsored Irrigation Projects

Five DOI-sponsored irrigation projects are located in the area: the Navajo Indian Irrigation Project (NIIP) (fig. 1), the Hammond Irrigation Project, the Fruitland Irrigation Project, the Hogback Irrigation Project, and the Cudei Irrigation Project. The NIIP was authorized in 1962 and construction of the project began in 1973. It is operated and maintained by the Navajo Nation. The project is divided into 11 blocks, and each block typically contains about 8,000 to 12,000 acres of cropland. Presently (1992), development of 6 blocks is complete and about 50,000 acres are being irrigated; when all 11 blocks are developed, about 110,000 acres will be irrigated. Irrigation of the first six blocks began between 1976 and 1982 (Robert Krakow, U.S. Bureau of Indian Affairs, oral commun., 1990). Construction of the delivery system to the blocks is the responsibility of the U.S. Bureau of Reclamation; construction of the on-farm delivery and drainage systems are the responsibility of the U.S. Bureau of Indian Affairs in cooperation with the Navajo Nation.

The Hammond Irrigation Project is located in a narrow strip south of and adjacent to the San Juan River, from about 2 mi southwest of Blanco to about 2 mi southeast of Farmington (fig. 1). It was constructed by the U.S. Bureau of Reclamation; irrigation began in 1962 (U.S. Bureau of Reclamation, written commun., 1980). The project is operated and maintained by the Hammond Conservancy District. The project provides irrigation for about 3,900 acres. About 700 acres within the present project area were irrigated prior to 1962.

The Fruitland Irrigation Project is located south of and adjacent to the San Juan River, from about 2 mi west of Farmington to about 2 mi west of The Hogback (fig. 1). Irrigation in the project area began in 1910, and the present project was completed in the early 1940's. The project provides irrigation for about 3,300 acres (Jerry Thomas, U.S. Bureau of Indian Affairs, oral commun., 1991).

The Hogback Irrigation Project is located north of and adjacent to the San Juan River, from The Hogback, about 8 mi east of Shiprock, to about 10 mi northwest of Shiprock (fig. 1). Irrigation in the project area began in 1904 and most of the original project was completed by about 1940. A pumping plant and two main laterals were added in 1952. The project provides irrigation for about 7,000 acres (Jerry Thomas, oral commun., 1991).

The Cudei Irrigation Project is located south of and adjacent to the San Juan River, from about 5 mi northwest of Shiprock to about 2 mi northwest of Cudei (fig. 1). Irrigation in the project area began in about 1910. The project provides irrigation for about 540 acres (Jerry Thomas, oral commun., 1991).

Climate

The climate of the San Juan River area is semiarid to arid and is characterized by large daily fluctuations in temperature and small annual precipitation. For the period 1931 to 1978, the average maximum and minimum temperatures at Farmington were 42 and 14 °F in January and 94 and 57 °F in July (Dr. Kenneth E. Kunkel, New Mexico Department of Agriculture, written commun., 1984). The growing season is approximately 160 days.

Average annual precipitation on the San Juan River area ranges from 6.6 in. at Shiprock to 8.5 in. at Bloomfield. Nearly half of the annual precipitation falls during July through October, usually during intense thunderstorms. Average annual potential evaporation is 79 in. at Navajo Dam and 77 in. at Farmington (Marjorie Chafey, U.S. Weather Service, written commun., 1980).

In 1990, precipitation was about 131 percent of normal annual precipitation (U.S. Department of Commerce, 1990). Precipitation in April, May, August, and September 1990 was more than 0.50 in. more than average; precipitation was 0.25 in. less than average in July and October 1990. The average annual precipitation and average monthly precipitation are the median values of annual and monthly averages of four stations in the San Juan River area: Bloomfield, Farmington, Fruitland, and Shiprock. The periods of record at these stations range from 44 to 51 years; the last year included was 1981. The median values of average monthly and 1990 monthly precipitation are shown in figure 2.




Figure 2.--Median of average monthly precipitation and 1990 monthly precipitation at four locations in the San Juan River area.

Geology

The San Juan River area lies within the Navajo section of the Colorado Plateaus physiographic province (Fenneman, 1931). The Navajo section is characterized by mesas, buttes, cuesta ridges, and rock terraces separated by broad, open valleys and occasional canyons and hogbacks. The San Juan River area includes the broad, terraced San Juan River valley where the Hammond, Fruitland, Hogback, and Cudei Irrigation Projects are located, and a large, relatively flat mesa to the south of the San Juan River valley, where the NIIP is located. The San Juan River valley is intersected by The Hogback about 8 mi east of Shiprock (fig. 1). The Hogback is an approximately north trending monocline that dips steeply to the east.

The consolidated-rock surface geology of the San Juan River area includes sedimentary strata ranging from Cretaceous to Tertiary age (fig. 3). These strata typically consist of sequences of interbedded sandstone, mudstone, and shale units, and occasional coal deposits. Each of the shale units in these sequences has the potential to contribute dissolved trace elements, including selenium, to the surface-water environment.

The Mancos Shale of Cretaceous age crops out from the western boundary of the study area to just west of The Hogback. The Point Lookout Sandstone, Menefee Formation, Cliff House Sandstone, Lewis Shale, and Pictured Cliffs Sandstone, all of Cretaceous age, crop out within or immediately adjacent to The Hogback.

The Kirtland Shale and Fruitland Formation of Cretaceous age, consisting of a thick sequence of interbedded shale, sandstone, and coal deposits, crops out between The Hogback and Farmington. East of Farmington, the Ojo Alamo Sandstone of Tertiary and Cretaceous age, consisting of sandstone, conglomeratic sandstone, and shale, crops out in north-trending bands about 1 mi wide. The Nacimiento Formation of Tertiary age, consisting of carbonaceous mudstones and sandstones; and the San Jose Formation, consisting of an interbedded sequence of sandstone, siltstone, and variegated shale crop out in most of the study area east of the Ojo Alamo Sandstone. The Lewis Shale, Pictured Cliffs Sandstone, Kirtland Shale and Fruitland Formation, Ojo Alamo Sandstone, Nacimiento Formation, and San Jose Formation also crop out in the upland area south of the San Juan River.

The San Juan River valley is characterized by unconsolidated clay, silt, sand, and gravel, and terrace gravel and boulder deposits of Quaternary age. The clay, silt, sand, and gravel deposits probably do not exceed 100 ft in thickness, and the terrace deposits generally do not exceed 30 ft in thickness.




Figure 3.--Geology of the San Juan River area.

Soils

Soils in the San Juan River valley are derived from alluvial material deposited by the San Juan River and from weathering products of local geologic formations deposited in alluvial fans from side streams. Soil materials typically include sandstone, shale, siltstone, and mudstone. They typically are alkaline, vary in texture from clays to sands, and are poorly stratified. Soils range from poorly to well drained, and permeability ranges from moderately rapid to moderately slow.

Soils in the upland area where the NIIP is located typically are derived from eolian and alluvial material, are deep, and well to excessively drained. Permeability ranges from moderately rapid to rapid.

HYDROLOGIC SETTING

The headwaters of the San Juan River are in the San Juan Mountains in southwestern Colorado. Spring snowmelt from these mountains provides most of the surface water in the San Juan River area. Most runoff occurs during the spring and early summer snowmelt period, April through early July. Occasional summer thunderstorms also can produce locally large volumes of runoff, particularly in areas of lower altitude. Nearly all water (99 percent) used in San Juan County during 1985 was obtained from surface-water sources (Wilson, 1986).

Water Supply

About 520,000 acre-ft of water was used in San Juan County in 1985; nearly all of this was surface water used along the corridor of the San Juan River (Wilson, 1986). Irrigation accounted for 78 percent of water use, and power generation accounted for about 10 percent. Virtually all irrigation water is obtained from surface-water sources. The San Juan and Four Corners Power Plants near Shiprock are the primary users of water for power generation. Water supplied by public or private utilities to communities having populations of 2,500 or more, including Bloomfield, Farmington, and Shiprock, accounted for about 2 percent of water used in the county; nearly all of this water was obtained from surface-water sources.

Navajo Dam, on the San Juan River, is about 30 mi upstream from Farmington, and delineates the eastern boundary of the study area (fig. 1). Streamflow-gaging stations in the San Juan area are listed in table 1. The average flow in the San Juan River near Archuleta (09355500), about 7 mi downstream from Navajo Dam, was about 1,300 ft³/s prior to the operation of Navajo Dam in 1963, and has been about 1,200 ft³/s since operation of the dam began (U.S. Geological Survey, 1991).

Further downstream, the average flow in the San Juan River at Shiprock (09368000) is about 2,200 ft³/s, based on 64 years of record. Significant tributaries to the San Juan River in the study area and their average annual flow are the Animas River, 920 ft³/s; La Plata River, 29 ft³/s; and Chaco River, 48 ft³/s (U.S. Geological Survey, 1991).

Table 1.--Streamflow-gaging stations, period of record, and average discharge in the San Juan River area

[All stations in New Mexico]

Station number	Station name	Period of record (month/year)	Average discharge (cubic feet per second)	Comments
09355500	San Juan River near Archuleta	12/54 to present	1,304 (7 years) 1,202 (28 years) 920 (79 years)	Before closure of Navajo Dam After closure of Navajo Dam
09364500	Animas River at Farmington	06/04 to 10/05, 09/12 to present	920 (79 years)	NASQAN station
09365000	San Juan River at Farmington	06/04 to 09/06, 09/12 to present	2,356 (78 years)	
09367500	La Plata River near Farmington	03/38 to present	29.0 (52 years)	
09367950	Chaco River near Waterflow	Water years 1959-69, 11/25 to present	48.0 (14 years)	
09368000	San Juan River at Shiprock	01/11 to 10/11, 02/27 to present	2,200 (64 years)	NASQAN station; radiochemical network station

Average flow in the San Juan and Animas Rivers in water year 1990 (October 1, 1989, through September 30, 1990) was less than the average annual flow (U.S. Geological Survey, 1991). Flow in the San Juan River near Archuleta was about 45 percent of average annual flow, flow in the San Juan River at Shiprock was about 43 percent of average annual flow, and flow in the Animas River (09364500) was about 56 percent of average annual flow. Flow in the San Juan River is regulated by Navajo Dam; flow in the Animas River is unregulated.

Ground water can be obtained from several geologic units in the area, although the yield of water to wells and the quality of water vary substantially. Wells completed in bedrock units generally yield only a few gallons per minute. Wells completed in unconsolidated units in the San Juan River valley generally yield larger quantities of water, and locally yield more than 100 gal/min. The quality of ground water in some areas makes it unsuitable for domestic or livestock use.

Hydrology of Department of Interior-Sponsored Irrigation Projects

The five DOI-sponsored irrigation projects divert water from the San Juan River. That portion of the diverted water not consumed by evapotranspiration is returned by overland flow, seepage, or subsurface tile drains to the San Juan River or to the ground-water system in the San Juan River valley. The NIIP consists of a reservoir and a network of main canals, laterals, and pumping stations. The Hammond, Fruitland, Hogback, and Cudei Projects each consist of a diversion, a main canal, and a series of field laterals; the Hammond and Hogback Projects also have pumping plants and main laterals.

Irrigation water for the NIIP is diverted from Navajo Lake on the San Juan River and stored in and regulated by Cutter Reservoir, about 8 mi from Navajo Lake (U.S. Bureau of Reclamation, written commun., 1984). Water is delivered from Cutter Reservoir to the project area about 20 mi away by the Main Canal, which includes several tunnels and siphons. When the NIIP is complete, the project will include about 110 mi of open canals, and the delivery system will carry as much as 1,800 ft³/s. The maximum annual project water allocation is 508,000 acre-ft. The features of the NIIP delivery system are shown in figure 4.

Primary delivery canals and the irrigation blocks each canal supplies include the Main Canal (blocks 1 and 4), Coury Lateral (block 5), Gravity Main Canal (blocks 2 and 6), and Amarillo Canal (block 3) (fig. 4). The Coury Lateral, Gravity Main Canal, and Amarillo Canal are supplied by the Main Canal (U.S. Bureau of Reclamation, written commun., 1984).

Water is applied to cropland exclusively by sprinkler irrigation systems (Robert Krakow, oral commun., 1991). About 90 percent of the cropland is irrigated by center-pivot systems; the remaining 10 percent is irrigated by wheel-move or hand-move sprinkler systems. The drain system on the NIIP includes about 200 mi of channels to collect storm runoff, overland irrigation-return flow, and ground-water seepage from irrigated land. Gallegos Canyon and Ojo Amarillo Canyon washes (fig. 1) flow to the San Juan River.




Figure 4.--Irrigation water delivery system on the Navajo Indian Irrigation Project.

Diversions to the NIIP begin about April 1 and terminate about October 31 of each year. Irrigation begins about April 1 on about 18,000 acres planted in alfalfa, winter wheat, and small grains, about May 1 on about 15,000 acres planted in corn and potatoes, and between May 15 and June 15 on about 10,000 acres planted in beans. Irrigation ceases about July 15 on winter wheat and small grains, about September 15 on beans, about September 30 on corn, and about October 31 on alfalfa and potatoes. About 7,000 acres are planted in miscellaneous crops for which the irrigation season varies. The schedule of major crop acreage under irrigation on the NIIP is listed in table 2.

Table 2.--Schedule of major crop irrigated acreage on the Navajo Indian Irrigation Project

Date	Crops irrigated	Approximate acres irrigated
April 1 to May 1	Alfalfa, winter wheat, small grains	18,000
May 1 to about June 1	Alfalfa, winter wheat, small grains, corn, potatoes	33,000
June 1 to July 15	Alfalfa, winter wheat, small grains, corn, potatoes, beans	43,000
July 15 to September 15	Alfalfa, corn, potatoes, beans	33,000
September 15 to September 30	Alfalfa, corn, potatoes	23,000
September 30 to October 31	Alfalfa, potatoes	13,000

The delivery system on the Hammond Irrigation Project consists of the Hammond Diversion on the San Juan River, the Main Gravity Canal, pumping plants, and three major laterals (U.S. Bureau of Reclamation, written commun., 1980). The Main Gravity Canal is about 27 mi long and has an initial capacity of 90 ft³/s. Major diversions from the canal are made by the East and West Highline Laterals, which are served by the Hammond Pumping Plant, the auxiliary pumping plant, and the Gravity Extension Lateral. Croplands generally are served from turnouts on the canal and main laterals; additional short laterals deliver water to isolated croplands. A schematic diagram of the Hammond, Fruitland, Hogback, and Cudei Projects delivery systems is shown in figure 5.

Water is applied to Hammond Project croplands by flood irrigation and by hand-move and wheel-move sprinkler systems. Drainage from croplands includes ground-water seepage, overland flow, and underground flow through about 8 mi of tile drains located intermittently throughout the project area (Errol Jensen, U.S. Bureau of Reclamation, oral commun., 1990). Ponds and wetlands are located at the outlets of several drain-tile systems.




Figure 5.--Schematic diagram of the water distribution systems on the Hammond, Fruitland, Hogback, and Cudei Irrigation Projects.

The Fruitland Irrigation Project delivery system consists of the Fruitland Diversion on the San Juan River 2 mi downstream from Farmington, the Fruitland Irrigation Canal, and about 100 mi of field laterals. The canal is about 23 mi long and has an initial capacity of about 90 ft³/s (Jerry Thomas, oral commun., 1991). Water is applied primarily by flood irrigation, and drainage is by overland flow and seepage.

The Hogback Irrigation Project delivery system consists of the Hogback Diversion on the San Juan River at The Hogback, the Hogback Canal, a pumping plant, two main laterals, and about 135 mi of field laterals. The Hogback Canal is about 29 mi long and has an initial capacity of 300 ft³/s; typically, about 225 ft³/s is diverted to the project (Jerry Thomas, oral commun., 1991). Water is applied primarily by flood irrigation, and drainage is by overland flow and seepage.

The Cudei Irrigation Project delivery system consists of the Cudei Diversion on the San Juan River, about 5 mi downstream from Shiprock; the Cudei Ditch; and about 16 mi of field laterals. The Cudei Ditch is about 12 mi long and has an initial capacity of 30 ft³/s (Jerry Thomas, oral commun., 1991). Water is applied primarily by flood irrigation, and drainage is by overland flow and seepage.

Ponds and wetlands provide aquatic and riparian habitats on and adjacent to each of the irrigation projects, and irrigation drainage from each project contributes to the flow of the San Juan River. The ponds and wetlands support migratory waterfowl and shorebirds and the plant and animal communities on which they depend. About 15 ponds are located on the NIIP. About 10 ponds intended for stock watering have been created on the NIIP by damming small drainages. These ponds are filled by seepage of irrigation water, irrigation runoff, storm runoff, or diversion of irrigation application water. About five other ponds have been formed by diversion of irrigation application water to small enclosed drainages. Several ponds are part of the Hammond Project, and wetlands connect much of this project to the San Juan River. Wetlands also connect parts of the Fruitland and Hogback Projects to the San Juan River.

PREVIOUS STUDIES

Data-collection activities, interpretive studies, and Environmental Impact Statements addressing concentrations of potential contaminants in water, sediment, and biota in the San Juan River area have been conducted and prepared by several DOI agencies. These agencies include the U.S. Bureau of Reclamation, the U.S. Bureau of Indian Affairs, the U.S. Fish and Wildlife Service, and the U.S. Geological Survey. Larger-than-expected concentrations of trace elements have been reported by each agency. In addition, the Geological Survey and the Fish and Wildlife Service have reported detectable concentrations of pesticides in water and biota, respectively.

The Bureau of Reclamation reported that elevated levels of unspecified trace elements caused Farmington municipal water intake from the Animas River to be suspended twice between 1975 and 1980 because of accidental contributions of these trace elements from mining areas near the headwaters of the river (U.S. Bureau of Reclamation, 1980). The Bureau of Reclamation also has reported concentrations of lead in the San Juan River at Archuleta, about 7 mi downstream from Navajo Dam, to be larger than the U.S. Environmental Protection Agency (USEPA) Primary Drinking-Water Standard Maximum Contaminant Level (MCL) of 50 $\mu\text{g}/\text{L}$ (U.S. Environmental Protection Agency, 1986a). The Bureau of Indian Affairs has monitored ground-water quality on the NIIP since 1985 and has reported concentrations of selenium in ground water as large as 180 $\mu\text{g}/\text{L}$ (Robert Krakow, U.S. Bureau of Indian Affairs, written commun., 1990).

Water-quality data collected by the Geological Survey from 1970 through 1989 (U.S. Geological Survey, 1971-90) in the San Juan River area indicate that selenium was present in concentrations larger than 5 $\mu\text{g}/\text{L}$ in samples collected from 16 of 24 surface-water-quality stations, from 7 of 35 miscellaneous surface-water sites, and from 4 of 38 miscellaneous ground-water sites. Concentrations of several other trace elements were larger than their respective USEPA Primary Drinking-Water Standard MCL's in surface-water and ground-water samples.

O'Brien (1987) reported that of 13 starling samples collected in the San Juan River area, concentrations of cadmium in 13 samples, lead in 8 samples, and selenium in 10 samples were larger than the respective National Contaminant Biomonitoring Program (NCBP) geometric mean concentrations (White and others, 1977). Selenium concentrations in 6 of 15 fish samples were above the 85th-percentile concentration of samples from the NCBP, and selenium concentrations in 4 of the 15 samples were between the geometric mean and the 85th-percentile values (Lowe and others, 1985).

Water-quality data collected by the Geological Survey indicate that 2,4,-D concentrations have been larger than the laboratory reporting level of 0.01 $\mu\text{g/L}$ in water samples from the San Juan River at Shiprock (U.S. Geological Survey, 1984-87). O'Brien (1987) reported concentrations of DDE larger than the NCBP geometric mean value (Bunck and others, 1987) in 9 of 14 starling samples and concentrations of polychlorinated biphenyls (PCB's) larger than the laboratory reporting level in several species of fish.

SAMPLE COLLECTION AND ANALYSIS

Sample collection and analysis were designed to determine whether irrigation drainage: (1) has caused or has the potential to cause significant harmful effects to human health, fish, and wildlife; or (2) may adversely affect the suitability of water for other beneficial uses. The potential contaminants of primary interest are trace elements and pesticides.

Other major potential sources of contaminants in the San Juan River area include energy industry activities and non-DOI-sponsored irrigation. Energy industry activities include oil and gas exploration, extraction, and processing; coal mining; and electric power generation (fig. 6). These activities may contribute to degradation of water quality; additionally, energy industry activities can be the source of potential contaminants that subsequently could be mobilized and transported by irrigation drainage.

About 7,000 acres of irrigated land along the San Juan River in the San Juan River area are not part of DOI-sponsored irrigation projects (Quincy Cornelius, U.S. Bureau of Reclamation, retired, oral commun., 1991). This acreage primarily is located on the north side of the San Juan River valley between Navajo Dam and The Hogback. About 400 acres are located on the south side of the river, upstream from the Hammond Project. Another 21,000 acres of irrigated land along the Animas River in New Mexico are not part of DOI-sponsored irrigation projects. Irrigation drainage from any or all of these areas may contribute potential contaminants to the San Juan River area.




Figure 6.--Energy resource areas and production activities in the San Juan River area.

Sampling Sites

The irrigation project sampling network ("I" sites) was designed so that the number of sites on irrigation projects was approximately proportionate to irrigation project size (fig. 7; table 3). The following numbers of sites were chosen for each irrigation project: NIIP, 15; Hammond Project, 5; Hogback Project, 3; Fruitland Project, 1; and Cudei Project, 0. No sites were on the Cudei Project because of its comparatively small size; the San Juan River site most downstream, R-11 (fig. 8), was chosen to be downstream from the Cudei Project so that any measurable contributions of constituents by the Cudei Project to the San Juan River would be detected. Sampling sites on irrigation projects included selected ponds, marshes, and wetlands that support wildlife, and selected irrigation drains and canals that flow from irrigation projects into the San Juan River.

The San Juan River sampling network ("R" sites) included sites both upstream (site R-1) and downstream (site R-11) from DOI-sponsored irrigation in the study area; the upstream site (R-1) serves as a reference site for this study. Other "R" sites were at diversions of river water to DOI-sponsored irrigation projects and to the municipal-supply diversion at Shiprock, and at or near tributary mouths (fig. 8; table 4).

Media sampled at irrigation project sites included water, bottom sediment, aquatic plants, invertebrates, and amphibians or fish. Birds were also sampled at some of these sites. Fish were not collected from sites on the NIIP because they were not available. The analysis matrices for these media are listed in tables 5 and 6.

Media sampled at San Juan River sites included water and bottom sediment. In addition to sampling at specific sites, seven reaches of the San Juan River were sampled for fish. The analysis matrices for these media are listed in tables 5 and 7.

Water samples analyzed for physical properties, major ions, and trace elements were collected prior to or at the beginning of, during, and after the 1990 irrigation season; those analyzed for triazine and chlorophenoxy acid herbicide compounds were collected in May and June 1990; and those analyzed for organophosphate and carbamate insecticide compounds were collected in August 1990. Bottom-sediment samples were collected after the 1990 irrigation season.

Aquatic plant, invertebrate, amphibian, and fish samples in wetland habitats were collected in summer 1990 during maximum metabolic activity. San Juan River fish samples were collected in spring, prior to the 1990 irrigation season, and in fall, after the 1990 irrigation season. Bird samples were collected in late spring and early summer 1990, during the breeding season.




Figure 7.--Water-quality, bottom-sediment, and biota sampling sites on or adjacent to Department of Interior-sponsored irrigation projects.

Table 3.--Sampling ("I") sites located on or adjacent to irrigation projects

[Sampling sites shown in fig. 7]

Navajo Indian Irrigation Project

Gallegos Canyon drainage

- I-1 Gallegos Canyon drainage south pond
- I-2 Gallegos Canyon drainage middle pond
- I-3 Gallegos Canyon drainage north pond
- I-4 Gallegos Canyon 2 miles north of Navajo Highway 3003

Ojo Amarillo Canyon drainage

- I-5 Ojo Amarillo Canyon three-fourths mile north of Navajo Highway 3003
- I-6 Ojo Amarillo Canyon drainage ponds (1 mile north of Navajo Highway 3003)
 - I-6A Upstream drainage pond
 - I-6B Downstream drainage pond
- I-7 Ojo Amarillo Canyon 2 1/4 miles north of Navajo Highway 3003
- I-8 Ojo Amarillo Canyon 4 miles north of Navajo Highway 3003

Ponds in enclosed drainages

- I-9 Hidden Pond
- I-10 Avocet Pond
- I-11 West Avocet Pond
- I-12 Northwest Pond-block 3

Chinde Wash drainage

- I-13 Chinde Wash drainage southwest pond
- I-14 Chinde Wash drainage southeast pond
- I-15 Chinde Wash at Navajo Highway 5005

Hammond Project

East Hammond Project

- I-16 East Hammond Project east drain and wetland (about 8 miles east of New Mexico Highway 44)
- I-17 East Hammond Project west drain and wetland (about 3 1/2 miles east of New Mexico Highway 44)
- I-18 East Hammond Project pond one-tenth mile north of West Drain (Red Pond)
- I-19 East Hammond Project pond four-tenths mile northwest of West Drain (adjacent to oil production facility)

West Hammond Project

- I-20 West Hammond Project pond (about 2 1/2 miles west of New Mexico Highway 44)

Table 3.--Sampling ("I") sites located on or adjacent to irrigation projects--Concluded

Fruitland Project

I-21 Fruitland Project site


Hogback Project

I-22 Hogback Project east drain (about 2 3/4 miles west of
The Hogback)

I-22B West tributary to Hogback Project east drain

I-23 Hogback marsh (about 1 1/2 miles southeast of Shiprock)

I-24 Hogback Project west drain (about 3 miles northwest of Shiprock)



EXPLANATION	
A—A'	RIVER REACH
R-1	RIVER SAMPLING SITE AND NUMBER

Figure 8.--Water-quality and bottom-sediment sampling sites and fish-sampling reaches on the San Juan River and at the mouths of tributary streams.

Table 4.--San Juan River reaches from which fish samples were collected, and water and bottom-sediment sampling ("R") sites within each river reach

[River reaches and sampling sites shown in fig. 8]

Reach A Hammond Diversion to Blanco

R-1 San Juan River at Hammond Project Diversion (reference site; upstream from Department of Interior-sponsored irrigation)

Reach B Bloomfield to Lee Acres

Reach C Lee Acres to Farmington

R-2 San Juan River 1 mile upstream from mouth of Gallegos Canyon

R-3 Animas River at mouth

R-4 Fruitland Project Diversion¹

Reach D La Plata River to Ojo Amarillo Canyon

R-5 La Plata River at mouth

Reach E Fruitland to Hogback

R-6 San Juan River one-half mile downstream from Fruitland Bridge

R-7 Shumway Arroyo

R-8 Hogback Project Diversion¹

R-9 Chaco River one-half mile upstream from mouth¹

R-10 San Juan River at Shiprock Municipal Diversion¹

Reach F Shiprock to Cudei

Reach G Cudei to Mancos River

R-11 San Juan River 3 miles downstream from Cudei (downstream from Department of Interior-sponsored irrigation)

¹Water and bottom-sediment sampling site is outside of river reaches from which fish samples were collected.

Table 5.--Number of samples and types of analyses for media at sampling sites on irrigation projects, the San Juan River, and tributaries

[Site: see tables 3 and 4 and figs. 7 and 8 for names and locations.

I, analysis for inorganic constituents; O, analysis for organic pesticides; A, killifish, mosquitofish, fathead minnow; B, common carp, flannelmouthed sucker. Numbers in table are number of samples collected]

Site	Medium									
	Water		Bottom sediment		Aquatic plants	Invertebrates	Amphibians	Fish		
	I	O	I	O	I	I	I	A	B	
Irrigation project sites										
I-1	3	2	1	1	1	1	1	0	0	
I-2	3	2	1	1	1	1	1	0	0	
I-3	3	1	1	0	1	1	1	0	0	
I-4	3	2	1	0	0	0	0	0	0	
I-5	0	0	0	0	0	0	0	0	0	
I-6A	0	0	1	0	1	1	1	0	0	
I-6B	3	1	0	0						
I-7	1	1	1	1	1	1	1	0	0	
I-8	2	1	0	0	0	0	0	0	0	
I-9	0	0	0	0	0	0	0	0	0	
I-10	3	1	0	0	1	1	0	0	0	
I-11	1	0	0	0	1	0	1	0	0	
I-12	1	1	0	0	1	1	1	0	0	
I-13	3	2	0	0	1	1	1	0	0	
I-14	1	0	0	0	0	0	0	0	0	
I-15	1	0	0	0	0	0	0	0	0	
I-16	0	0	0	0	1	1	0	2	0	
I-17	3	0	1	1	0	0	0	0	0	
I-18	1	0	0	0	1	0	0	0	0	
I-20	3	0	1	1	1	1	0	2	0	
I-21	3	0	1	1	1	1	1	2	1	
I-22	4	0	1	1	1	2	0	2	2	
I-22B	1	0	0	0	0	0	0	0	0	
I-23	3	0	1	1	1	1	0	1	2	
I-24	3	0	1	1	0	0	0	0	0	

Table 5.--Number of samples and types of analyses for media at sampling sites on irrigation projects, the San Juan River, and tributaries--Concluded

Site	Medium									
	Water		Bottom sediment		Aquatic plants	Invertebrates	Amphibians	Fish		
	I	O	I	O	I	I	I	A	B	
San Juan River and tributary sites										
R-1	3	0	1	0	0	0	0	0	0	0
R-2	3	0	1	0	0	0	0	0	0	0
R-3	3	0	0	0	0	0	0	0	0	0
R-4	2	0	0	0	0	0	0	0	0	0
R-5	3	0	1	0	0	0	0	0	0	0
R-6	3	0	1	0	0	0	0	0	0	0
R-7	2	0	0	0	0	0	0	0	0	0
R-8	2	0	0	0	0	0	0	0	0	0
R-9	3	0	1	0	0	0	0	0	0	0
R-10	3	0	0	0	0	0	0	0	0	0
R-11	3	0	1	0	0	0	0	0	0	0

Table 6.--Number of bird samples collected for analysis of inorganic constituents at sites on irrigation projects

[Site: see table 3 and fig. 7 for names and locations]

Site	Bird samples					
	Avocet	Blackbird species	Coot	Killdeer	Mallard	Teal species
Adults						
I-1, I-2, I-3	0	1	1	1	2	1
I-6	0	1	0	1	2	0
I-9, I-10,	5	1	2	1	4	0
I-11, I-12						
I-16, I-17,	0	1	0	3	0	3
I-18, I-19						
I-20	0	1	0	0	2	0
I-21	0	1	0	1	1	3
I-23	0	1	5	0	0	0
Fledglings						
I-6	0	0	0	0	1	0
I-9, I-10,	0	0	0	0	3	0
I-11, I-12						
Embryos						
I-6	0	0	0	0	1	0
I-9, I-10,	5	0	0	0	0	0
I-11, I-12						
I-16, I-17,	0	0	0	2	0	0
I-18, I-19						
I-21	0	0	0	0	0	1
I-23	0	0	4	0	0	0

Table 7.--Types of analyses conducted on fish samples from reaches of the San Juan River

[S, spring sampling period; F, fall sampling period; I, analysis for inorganic constituents; O, analysis for organochlorine pesticides; river reach: see fig. 8 for location]

River reach	Common carp		Flannel-mouthed sucker		Brown trout		Channel catfish	
	S	F	S	F	S	F	S	F
A: Hammond Diversion to Blanco	I	I	I/O	I	I	I		
B: Bloomfield to Lee Acres		I		I				
C: Lee Acres to Farmington	I	I	I/O	I		I		
D: La Plata River to Ojo Amarillo Canyon	I	I	I/O	I				
E: Fruitland to Hogback	I	I	I/O	I			I	I
F: Shiprock to Cudei	I	I	I/O	I			I	I
G: Cudei to Mancos River	I	I	I/O	I			I	I

Sampling Methods

Water and bottom-sediment samples were collected according to procedures outlined by U.S. Geological Survey (1982b); Edwards and Glysson (1988); and Severson and others (1988). Biological samples were collected according to procedures outlined by the Fish and Wildlife Service (1985).

Water samples were collected from ponds, marshes, diversions from the San Juan River, and tributaries to the San Juan River, except the Animas River, by submerging a 9-qt churn splitter. Prior to collection of each sample, the churn splitter was thoroughly washed and rinsed with water from the site to be sampled. Equal-width increment, depth-integrated water samples were collected from the San Juan River and the Animas River using a DH-48 sampler. Water samples at these sites were collected at either 5- or 10-ft intervals across the entire width of the rivers.

Water temperature, specific conductance, pH, and dissolved oxygen were measured at the time of sample collection and discharge was measured where water was flowing. Samples collected for analysis of anions, trace elements, nitrogen species, and dissolved-uranium concentrations were filtered immediately following sample collection using a peristaltic pump and a 0.45-micrometer filter.

Except for mercury, samples collected for analysis of trace-element and uranium concentrations were preserved with a nitric acid solution; samples collected for analysis of mercury concentrations were preserved with a potassium dichromate/nitric acid solution. Samples were preserved immediately following filtration; the pH of the preserved samples was less than 2.0. Samples collected for analysis of nitrogen species concentrations were preserved with a mercuric chloride/sodium chloride solution and packed in ice immediately following filtration.

Water samples for analysis of pesticides were collected by submerging a 1-liter, baked, brown glass bottle. Prior to sample collection, the bottles were thoroughly rinsed with water from the site to be sampled. Samples were packed in ice immediately following collection.

All bottom-sediment sampling equipment was thoroughly washed with biodegradable detergent powder and water, rinsed with deionized water, and rinsed in water from the site to be sampled immediately prior to sample collection and processing. Composite samples were collected with an unpainted BMH-53 bottom-sediment sampler. The core barrel of the sampler was stainless steel and the plunger was brass. Nine to 12 equally spaced subsample cores were collected at each site, and the top 3 to 4 in. of each core were combined in a stainless steel bucket and thoroughly mixed with a stainless steel spoon.

Material to be analyzed for trace elements was subsampled and placed in a 500-milliliter polyethylene jar. Sample material to be analyzed for organochlorine compounds was gently worked through a 2-millimeter brass-plated sieve with a stainless steel spoon; material passing through the sieve was retained and placed in a 1-liter, baked, clear glass jar. No water was used during the sieving process. Each sample was packed in ice immediately following sieving.

Aquatic plants were collected by hand; fauna in wetland habitats were collected by light trap, dipnet, minnow net, and hand seine. Aquatic plant and invertebrate samples were rinsed with deionized water and weighed to the nearest gram. Amphibian samples were weighed to the nearest gram. Fish samples collected in wetland habitats were weighed and measured. All of these samples were sealed in plastic bags and placed on ice in the field, and subsequently frozen the same day as collected.

Fish in the San Juan River were collected by electrofishing. Samples were weighed and measured. Samples collected for trace-element analysis were sealed in plastic bags; those collected for organochlorine analysis were wrapped in aluminum foil. All of these samples were placed on ice in the field, and subsequently frozen the same day as collected.

External Condition Analysis (developed by Dr. John Hickey, U.S. Fish and Wildlife Service, oral and written commun., 1990) was conducted on fish samples. This procedure included observations of external signs of ill health, including lesions and scoliosis (curvature of the spine).

Adult and juvenile bird samples were collected by steel shot; avian eggs were collected by retrieval from nests. Livers and kidneys of adults and juveniles were analyzed for trace elements; carcasses were analyzed for organochlorine compounds. Samples were rinsed with deionized water, weighed to the nearest gram, sealed in plastic bags (livers and kidneys) or in aluminum foil (carcasses), placed on ice in the field, and subsequently frozen the same day as collected. Prior to each dissection, equipment was washed in detergent, rinsed with tap water, rinsed three times with deionized water, and air dried.

Bird embryos were analyzed for trace elements. Embryos were removed from the egg, placed in a sterile, acid rinsed jar, weighed to the nearest gram, placed on ice in the field, and frozen the same day as collected.

Analytical Support

All water samples were analyzed by the U.S. Geological Survey, Water Resources Division National Water Quality Laboratory in Arvada, Colorado. Bottom-sediment samples were analyzed for inorganic constituents by the U.S. Geological Survey, Geologic Division Laboratory in Lakewood, Colorado, and analyzed for pesticides by the U.S. Geological Survey, Water Resources Division National Water Quality Laboratory in Arvada. Samples collected for inorganic constituents were analyzed according to procedures outlined in Fishman and Friedman (1989); samples collected for pesticides were analyzed according to procedures outlined in Wershaw and others (1987); and samples collected for uranium were analyzed according to procedures outlined in Thatcher and others (1977). Laboratory quality control and quality assurance procedures were those described in Friedman and Erdmann (1982). Laboratory reporting levels for selected constituents are listed in table 8.

Table 8.--Laboratory reporting levels for selected constituents in water and bottom sediment

[$\mu\text{g/L}$, micrograms per liter; $\mu\text{g/g}$, micrograms per gram; $\mu\text{g/kg}$, micrograms per kilogram]

Constituent	<u>Analytical reporting limit</u>		
	Water ($\mu\text{g/L}$)	Bottom sediment ($\mu\text{g/g}$)	Bottom sediment ($\mu\text{g/kg}$)
Inorganic constituents			
Arsenic	1	0.1	
Boron	10	0.4	
Cadmium	1.0	2	
Chromium	1	1.0	
Copper	1	1.0	
Lead	1	4.0	
Mercury	0.1	0.02	
Molybdenum	1	2	
Selenium	1	0.1	
Strontium		2.0	
Uranium	1.0	0.1	
Vanadium	1	2.0	
Zinc	10	2.0	
Organic constituents			
Triazine herbicides	0.1		
Chlorophenoxy acid herbicides	0.1		
Carbamate insecticides	0.05		
Organophosphate insecticides	0.01		
Organochlorine insecticides:			
Toxaphene			10
Chlordane			1
PCB's			1
PCN's			1
Perthane			1
All other compounds			0.1

Biological samples were analyzed by laboratories under contract to the U.S. Fish and Wildlife Service, Patuxent Analytical Control Facility, Patuxent, Maryland. Analyses were conducted according to procedures outlined by the U.S. Fish and Wildlife Service (1990). The types of analyses and the laboratory conducting each are: inorganic constituents, Research Triangle Institute, Research Triangle Park, North Carolina; organochlorine compounds, Mississippi State Chemical Laboratory, Mississippi State University, Starkville, Mississippi; and cholinesterase enzyme assays, U.S. Fish and Wildlife Service, Patuxent Wildlife Research Center, Patuxent, Maryland. Arsenic, lead, and selenium were analyzed by graphite furnace atomic absorption, mercury was analyzed by cold vapor atomic absorption, and 18 other constituents were analyzed by inductively coupled plasma spectroscopy.

About 10 percent of water and bottom-sediment samples that were submitted were quality assurance/quality control samples. These samples consisted of split, duplicate, and blank samples. Results of the analyses of these samples are included in tables 20 through 22 (tables 20-30 are in the Supplemental data section in the back of the report.) All results of analysis of biological samples were subjected to quality assurance/quality control procedures by the U.S. Fish and Wildlife Service, Patuxent Analytical Control Facility, Patuxent, Maryland.

DISCUSSION OF RESULTS

Seventy-eight water samples were collected and analyzed during three sampling periods: prior to or at the beginning of the irrigation season in April 1990, during the irrigation season generally in August 1990, and following the irrigation season in November and December 1990. Results of these analyses are shown in tables 20 and 21.

Concentrations of Trace Elements in Water

Concentrations of dissolved constituents in water were compared to National Baseline Values for rivers in the United States. Data from which these baseline values were calculated are from two National monitoring programs: the National Stream-Quality Accounting Network (NASQAN) and the National Water-Quality Surveillance System (NWQSS). Data have been collected for NASQAN and NWQSS since 1973. Baseline values were calculated by determining the arithmetic mean concentration for a given water-quality property or constituent at each station for which information was available, and then ranking these mean values for all the stations; percentile values were then determined. These percentile values and median and maximum concentrations of trace elements in samples collected for the San Juan River study are shown in table 9.

Table 9.--Comparison of baseline concentrations of selected constituents in samples collected from rivers of the United States with concentrations in 28 samples from the San Juan River, diversions, and tributaries, and in 48 samples from irrigation project sites

[Baseline percentiles: determined from data in National Stream-Quality Accounting Network and National Water-Quality Surveillance System data bases. <, less than]

Trace element	Concentration (micrograms per liter)						
	Baseline percentiles			San Juan River, diversions, and tributaries		Irrigation project sites	
	25	50	75	Median	Maximum	Median	Maximum
Arsenic	<1	1	3	1	1	1	48
Cadmium	<2	<2	<2	<1	1	<1	2
Chromium	9	10	10	<1	3	<1	2
Lead	3	4	6	<1	1	<1	12
Mercury	0.2	0.2	0.2	<0.1	0.2	<0.1	0.2
Nitrate	0.2	0.41	0.89	0.2	6.3	0.2	19
Selenium	<1	<1	<1	<1	4	2	67
Zinc	12	15	21	7	13	<10	20

For samples collected from the San Juan River, diversions, and tributaries (the Animas, La Plata, and Chaco Rivers), the median concentration of each trace element except arsenic was equal to or less than the 25th-percentile baseline concentration. For samples collected from irrigation project sites, the median concentration of each trace element except arsenic and selenium was equal to or less than the 25th-percentile baseline concentration. For both groups of samples, the median concentration of arsenic was equal to the 50th-percentile baseline concentration. The median concentration of selenium in water from irrigation sites was 2 $\mu\text{g/L}$, compared with less than 1 $\mu\text{g/L}$ for the 25th-, 50th-, and 75th-percentile baseline concentrations.

If the distribution of concentrations of a given constituent in the San Juan River area data set were the same as in the data set from which the baseline values were calculated, then the number of samples expected to be larger than the 75th-percentile baseline concentration would be 7 in the group collected from the San Juan River, diversions, and tributaries (28 samples), and 12 in the group collected from irrigation project sites (48 samples). Except for selenium, the number of samples exceeding the 75th-percentile concentration was less than the expected number for all trace elements in both groups. Selenium concentrations were larger than the baseline 75th-percentile concentration in 28 of 48 samples from irrigation project sites (table 21).

To further evaluate water-quality conditions in the study area, concentrations of selected constituents were compared to applicable USEPA Primary Drinking-Water Standards and with State of New Mexico standards for several water uses (U.S. Environmental Protection Agency, 1986a, 1986b; New Mexico Water Quality Control Commission, 1988). These Federal and State standards for selected constituents are listed in table 10.

Table 10.--U.S. Environmental Protection Agency and State of New Mexico water-quality standards for selected constituents

[USEPA: U.S. Environmental Protection Agency; USEPA drinking-water standard: Federally enforceable Primary Drinking-Water Standard Maximum Contaminant Level (U.S. Environmental Protection Agency, 1986a), except as noted; State of New Mexico standard: New Mexico Water Quality Control Commission, 1988. $\mu\text{g/L}$: micrograms per liter. -- not applicable]

Constituent	USEPA drinking-water standard ($\mu\text{g/L}$)	State of New Mexico standard			
		Domestic ($\mu\text{g/L}$)	Irrigation ($\mu\text{g/L}$)	Livestock/wildlife ($\mu\text{g/L}$)	Fisheries ($\mu\text{g/L}$)
Arsenic	50	50	100	200	--
Boron	--	--	750	5,000	--
Cadmium	10	10	10	50	11.1
Chromium	100	50	100	1,000	1210
Copper	21,000	--	200	500	12
Lead	50	50	5,000	100	13.2
Mercury	2	2	--	10	0.012
Nitrate	10,000	10,000	--	--	--
Selenium	³ 50	50	20	50	5
Vanadium	--	--	100	100	--
Zinc	25,000	--	2,000	25,000	110

¹Hardness dependent: 100 milligrams per liter hardness used in calculation.

²Federally non-enforceable Secondary Drinking-Water Standard Maximum Contaminant Level (U.S. Environmental Protection Agency, 1986b).

³Federal Register, 1991.

Primary Drinking-Water Standard MCL's established by the USEPA are Federally enforceable water-quality standards. Secondary Drinking-Water Standard MCL's are not Federally enforceable, but establish recommended concentration limits above which aesthetic qualities and public acceptance of drinking water may be adversely affected.

Water-quality standards for several water uses, including domestic water supply, irrigation, livestock and wildlife watering, and for the protection of fisheries, based on chronic criteria, have been established for streams in New Mexico by the New Mexico Water Quality Control Commission (1988). Within the San Juan River study area, standards for protection of fisheries are applicable to the San Juan, Animas, and La Plata Rivers and to the mouth of the Chaco River.


In samples collected from the San Juan River and tributary mouths, the maximum concentration of each trace element was 10 percent or less of the applicable USEPA Drinking-Water Standard MCL. The maximum concentration of each trace element except mercury in samples collected from the San Juan River and tributary mouths also was equal to or less than the applicable State of New Mexico standard for the protection of fisheries. The State of New Mexico standard for mercury is 0.012 $\mu\text{g}/\text{L}$, whereas the laboratory reporting level for mercury was 0.1 $\mu\text{g}/\text{L}$. Thus, the number of samples with mercury concentrations exceeding this criterion is not known.

Concentrations of selenium in samples collected from the main stem of the San Juan River and from diversions were less than 1 $\mu\text{g}/\text{L}$ from the Hammond Project Diversion (site R-1) to and including the San Juan River downstream from Fruitland Bridge (site R-6). At the Shiprock Municipal Diversion (site R-10) and at the San Juan River near Cudei (site R-11), however, the maximum concentrations of selenium are 1 and 2 $\mu\text{g}/\text{L}$, respectively. The increase in selenium concentrations at and downstream from Shiprock is due to several possible reasons. The Mancos Shale, consisting mostly of marine shale, is at the surface in most of the San Juan River study area west of The Hogback, about 8 mi upstream from the Shiprock Diversion. The larger concentrations of selenium could be the result of natural processes acting on the Mancos Shale, irrigation drainage from the east Hogback Project, or a combination of natural processes and irrigation drainage.

Concentrations of trace elements typically were larger in water samples collected from irrigation project sites than in samples collected from the San Juan River and tributary mouths (table 9). The exceptions were chromium and mercury. Although larger maximum concentrations of trace elements typically occurred at irrigation project sites, selenium was the only trace element for which the maximum concentration was larger (one sample) than the applicable USEPA Primary Drinking-Water Standard MCL (U.S. Environmental Protection Agency, 1986a).

Concentrations of cadmium were larger than the 1.1- $\mu\text{g}/\text{L}$ State of New Mexico standard for the protection of fisheries at two sites and the concentration of lead was larger than the 3.2- $\mu\text{g}/\text{L}$ standard for the protection of fisheries at one site, but the applicable standard was exceeded in only one of three samples collected at each of these sites. The State of New Mexico water-quality standards for the protection of fisheries are based on chronic criteria; the applicable standards do not appear to be chronically exceeded.

A statistical summary of selenium concentrations in water from irrigation project sites is shown in figure 9. All concentrations of selenium that are far outlying values occurred in three locations: Gallegos Canyon drainage on the NIIP (sites I-2 and I-4), Ojo Amarillo Canyon on the NIIP (sites I-7 and I-8), and the Hogback Project east drain (site I-22). The median concentration of selenium at each location was: I-2, 25 $\mu\text{g}/\text{L}$; I-4, 12 $\mu\text{g}/\text{L}$; I-7/I-8, 42 $\mu\text{g}/\text{L}$; and I-22, 12 $\mu\text{g}/\text{L}$.



EXPLANATION




Figure 9.--Concentrations of dissolved selenium in water samples from irrigation project sites.

The median concentrations of selenium at these sites did not exceed the 50- $\mu\text{g/L}$ USEPA Primary Drinking-Water Standard MCL but did exceed the 5- $\mu\text{g/L}$ State of New Mexico standard for the protection of fisheries. One sample collected at these sites exceeded the USEPA MCL, and all samples exceeded the State of New Mexico standard for protection of fisheries.

Maximum concentrations of selenium in water samples from Gallegos Canyon drainage south pond (site I-1, 7 $\mu\text{g/L}$) and the West Hammond Project pond (site I-20, 6 $\mu\text{g/L}$) also exceeded the 5- $\mu\text{g/L}$ State of New Mexico standard for protection of fisheries; however, the median selenium concentration at both sites was 3 $\mu\text{g/L}$. This standard does not appear to be chronically exceeded at these sites.

These data show that in specific geographical areas or at specific locations on irrigation projects, concentrations of dissolved selenium chronically exceeded the State of New Mexico standard for protection of fisheries of 5 $\mu\text{g/L}$ (New Mexico Water Quality Control Commission, 1988). These areas are not included in waters designated by the State of New Mexico as fisheries; however, the concentrations of selenium at these sites do indicate a potential for harmful effects to the aquatic communities that inhabit them, and to wildlife that feed on these aquatic communities.

In summer 1990, water samples from 22 sites throughout the San Juan River area were screened for acute toxicity using photobacteria. Of 149 tests conducted on the 22 sites, 22 water samples from 7 sites induced a toxic response in the photobacteria.

The results of the acute-toxicity screening were used to select eight sites for comparative 48-hour acute-toxicity tests using *Daphnia magna* and captively reared Colorado squawfish larvae from the Dexter National Fish Hatchery in Dexter, New Mexico (outside the study area). The sites selected were the Gallegos Canyon drainage middle pond (I-2), Gallegos Canyon (I-4), Ojo Amarillo Canyon (I-7), block 3 northwest pond (I-12), Chinde Wash drainage southeast pond (I-14), East Hammond Project east drain and wetland (I-16), West Hammond Project pond (I-20), and the Hogback Project east drain (I-22). The acute-toxicity tests were conducted according to the protocols established by the U.S. Environmental Protection Agency (1985).

None of these tests indicated acute toxicity to either *Daphnia magna* or Colorado squawfish larvae. The maximum concentration of selenium in water samples collected from the test sites was 42 $\mu\text{g/L}$ from Ojo Amarillo Canyon (site I-7). Kemp and others (1973) established a concentration of selenium of 50,000 $\mu\text{g/L}$ to be lethal to 50 percent of a test population of Colorado squawfish over a 96-hour period: 96-hour LC/50 = 50,000 $\mu\text{g/L}$ (LC = lethal concentration). Therefore, at concentrations of selenium in the San Juan River area, toxicity to aquatic species would be chronic rather than acute.

Concentrations of Trace Elements in Bottom Sediment

Bottom-sediment samples were collected from four sites on the San Juan River; from the mouths of two tributaries; from six sites on the NIIP; from one site each on the East Hammond, West Hammond, and Fruitland Projects; and from three sites on the Hogback Project for a total of 18 samples. One replicate and one split sample were analyzed for quality assurance. These samples were from the south pond in Gallegos Canyon (site I-1) and from Ojo Amarillo Canyon (site I-7).

Two size fractions of bottom sediment were analyzed for each of the 18 samples: the fraction less than 0.062 millimeter; and the fraction less than 2 millimeters, which includes the fraction less than 0.062 millimeter. The fraction less than 0.062 millimeter was used for the following interpretation because the median concentrations of arsenic, cadmium, chromium, copper, lead, molybdenum, selenium, strontium, vanadium, and zinc in the fraction less than 0.062 millimeter were equal to or larger than the median concentrations of these trace elements in the fraction less than 2 millimeters. The results of analysis of both size fractions of these samples are listed in table 22.

Concentrations of selected constituents were compared to values in soils of the United States west of the 97th parallel (Shacklette and Boerngen, 1984), to values (except selenium) in 47 soil samples collected in the San Juan Basin, New Mexico (Severson and Gough, 1981), and to concentrations measured as part of 19 studies of the National Irrigation Water-Quality Program (NIWQP) (Severson and others, 1991). Six of Severson's and Gough's (1981) 47 sites were within the San Juan River study area. The 95-percent expected-value ranges of concentrations (the concentrations within which 95 percent of the results of analyses are expected to be included) and the geometric mean concentrations of selected trace elements determined in soils of the Western United States and soil samples from the San Juan Basin are listed in table 11. The range of concentrations in the fractions less than 0.062 millimeter and less than 2 millimeters of samples collected as part of the NIWQP, and the range of concentrations and the median concentrations of the less-than-0.062-millimeter fraction of samples from the San Juan River area also are listed in table 11.

Two different indicators of the central value for concentrations of trace elements were used. The geometric mean was used by Severson and Gough (1981) and by Shacklette and Boerngen (1984). In the San Juan River study, the median value of concentrations was used.

Concentrations of 22 of 198 individual analyses for trace elements (18 samples analyzed for the 11 trace elements listed in table 11 for San Juan Basin soils) in bottom sediment from the San Juan River area were larger than the respective upper expected-value concentration in soils in the San Juan Basin (Severson and Gough, 1981). These included nine strontium, five lead, four chromium, two copper, and two zinc analyses. The largest concentrations of strontium were from the Gallegos Canyon drainage middle and north ponds (sites I-2 and I-3) and the West Hammond Project pond (site I-20); the concentrations of strontium at these three sites were, respectively, about 3.6, 2.4, and 2.2 times the upper expected value of 410 $\mu\text{g/g}$ (tables 11 and 22). The concentration of lead at the Hogback marsh (site I-23) was twice the upper expected value of 22 $\mu\text{g/g}$. None of the other concentrations in the 18 individual samples were more than 1.5 times the respective upper expected value.

Table 11.--Concentrations of selected trace elements in soils of the Western United States, in soils from the San Juan Basin, in bottom sediment from 19 National Irrigation Water-Quality Program (NIWQP) study areas, and in bottom sediment from the San Juan River area

[Concentrations are in micrograms per gram; San Juan River area bottom sediment consists of a size fraction less than 0.062 millimeter. <, less than; --, no data]

Trace elements	Concentration in Western U.S. soils		Concentration in San Juan Basin soils		Concentration range in bottom sediment from 19 NIWQP study areas		Concentration in bottom sediment from the San Juan River area	
	Expected percent range	Geometric mean	Expected percent range	Geometric mean	<0.062 millimeter	<2.0 millimeter	<0.062 millimeter	Median
Arsenic	1.2 - 22	5.5	2.3 - 13	5.4	0.6 - 59	0.6 - 120	2.1 - 5.1	3.6
Cadmium	--	--	--	--	--	--	<2	<2
Chromium	8.5 - 200	41	7.9 - 41	18	1.0 - 300	20 - 330	2.4 - 53	31
Copper	4.9 - 90	21	2.3 - 33	8.8	3.0 - 180	5.0 - 520	13 - 36	21.5
Lead	5.2 - 55	17	6.5 - 22	12.5	<4.0 - 250	<4.0 - 500	15 - 44	19
Mercury	0.0085 - 0.25	0.046	0.01 - 0.07	0.02	<0.02 - 20	<0.02 - 18	0.02 - 0.04	0.02
Molybdenum	0.18 - 4.0	0.85	0.4 - 3.5	1.3	<2.0 - 54	<2.0 - 73	<2 - 3	<2
Nickel	3.4 - 66	15	3.1 - 24	8.5	<2.0 - 160	8.0 - 170	10 - 20	12
Selenium	0.039 - 1.4	0.23	--	--	0.1 - 120	0.1 - 85	0.1 - 37	0.65
Strontium	43 - 930	200	85 - 410	180	69 - 1,400	59 - 110,600	160 - 1,500	365
Uranium	1.2 - 5.3	2.5	1.4 - 5.3	2.6	--	--	3.56 - 16.7	5.95
Vanadium	18 - 270	70	18 - 110	42.5	5.0 - 220	20 - 310	42 - 110	66
Zinc	17 - 180	55	13 - 100	38	10 - 860	23 - 1,600	41 - 150	65.5

The maximum concentration of selenium in six samples collected from the San Juan River and in two tributary samples collected from the mouths of the La Plata and Chaco Rivers (sites R-5 and R-9) was 0.4 $\mu\text{g/g}$, less than the upper expected value of 1.4 $\mu\text{g/g}$ selenium in soils of the Western United States (Shacklette and Boerngen, 1984). The median concentration of selenium in these six samples was 0.25 $\mu\text{g/g}$, similar to the geometric mean selenium concentration of 0.23 $\mu\text{g/g}$ in soils of the Western United States.

The maximum concentration of selenium in 12 samples collected from sites on irrigation projects was 37 $\mu\text{g/g}$ at the Gallegos Canyon drainage middle pond (site I-2). Eight of these 12 samples had concentrations of selenium larger than the upper expected value of 1.4 $\mu\text{g/g}$ for soils of the Western United States. The bottom-sediment samples having the largest concentrations of selenium, in $\mu\text{g/g}$, are from the following sites:

Site	Selenium concentration
I-2 Gallegos Canyon drainage middle pond	37
I-22 Hogback Project east drain	6.0
I-24 Hogback Project west drain	5.5
I-7 Ojo Amarillo Canyon	5.0
I-23 Hogback marsh	4.5

These sites include three of the four locations where selenium concentrations in water exceeded established standards. The concentration of selenium in all other bottom-sediment samples was less than 2 $\mu\text{g/g}$.

Maximum concentrations of other trace elements in the San Juan River area typically were about one order of magnitude smaller than those in the less-than-0.062-millimeter size fraction from the 19 NIWQP study areas (table 11). Exceptions include mercury and strontium; maximum mercury concentrations were about three orders of magnitude smaller in the San Juan River area than in the 19 NIWQP study areas, and maximum strontium concentrations were about the same as in the 19 NIWQP study areas.

Concentrations of Trace Elements in Biota

Plants, invertebrates, amphibians, and fish were collected where available from pond and wetland areas associated with irrigation. Fish also were collected from several reaches of the San Juan River, and birds were collected throughout the study area.

Pond and Wetland Community Members

Fifteen plant samples, 15 invertebrate samples, 9 amphibian samples, and 14 fish samples from pond and wetland areas were collected and analyzed. Plant samples consisted of Potamogeton species and Chara species. Invertebrate samples consisted of both single- and mixed-taxa composites of Odonata, Coleoptera, Decapoda, Gastropoda, and Hemiptera. Amphibian samples consisted of the aquatic phase of the tiger salamander (Ambystoma tigrinum), commonly referred to as waterdog, and one tadpole sample (Rana species). Fish samples consisted of mosquitofish (Gambusia affinis), plains killifish (Fundulus zebrinus), fathead minnow (Pimephales promelas), common carp (Cyprinus carpio), and flannelmouthed sucker (Catostomus latipinnis). Results of these analyses are listed in table 23.

Eleven constituents were present in all or nearly all samples at concentrations larger than laboratory reporting levels (table 12). Antimony, beryllium, molybdenum, and tin rarely were present in concentrations larger than laboratory reporting levels in any of the media sampled (table 12). Antimony and beryllium each were present at concentrations at or above these levels in one plant sample, molybdenum was present in five plant samples and two invertebrate samples, and tin was present in four plant samples.

Cadmium, cobalt, nickel, and vanadium rarely were present or were not present at concentrations larger than laboratory reporting levels in amphibians or fish; arsenic rarely was present at concentrations larger than its laboratory reporting level in fish (table 12). Mercury was not present at concentrations larger than its laboratory reporting level in any plant samples but was present in about one-half of the faunal samples.

Toxicity criteria for whole-body concentrations of selenium in fish and in food items consumed by waterfowl and fish have been empirically established. Lemly and Smith (1987) established 12 $\mu\text{g/g}$ dry weight as a whole-body concentration in fish above which reproductive failure may occur. They also established 5 $\mu\text{g/g}$ dry weight in food items as a concentration above which ingestion by fish may result in reproductive failure or mortality. Heinz and others (1989) established a dietary threshold of 4 to 8 $\mu\text{g/g}$ dry weight in food items as a concentration range above which ingestion by waterfowl may impair reproduction. Ranges and medians of dry-weight concentrations of selenium in the various media sampled from pond and wetland communities are listed in table 13.

The maximum concentration of selenium in each medium except plants exceeded food-item criteria concentrations by factors ranging from about 6 to 10 (Lemly and Smith, 1987) for fish and by factors ranging from about 4 to 6 (Heinz and others, 1989) for waterfowl. The sampling sites for which concentrations of selenium in the pond and wetland community members exceeded the various food-item criteria are listed in table 14.

Table 12.--Ranges of whole-body concentrations of selected trace elements in biota from pond and wetland sites
 [No., number of samples having concentrations larger than respective laboratory reporting level; <, less than]

Trace element	15 plant samples			15 invertebrate samples			9 amphibian samples			14 fish samples		
	No.	Minimum	Maximum	No.	Minimum	Maximum	No.	Minimum	Maximum	No.	Minimum	Maximum
Antimony	1	<5.00	6.62	0	<5.00	<5.00	0	<5.00	<5.00	0	<5.00	<5.00
Arsenic	14	<0.35	13.2	14	<.3	4.77	9	0.557	5.14	3	<0.3	0.813
Barium	15	10.8	932	15	2.54	931	9	4.20	296	14	1.21	24.6
Beryllium	1	<.100	0.238	0	<0.100	<0.100	1	<0.100	1.48	0	<0.100	<0.100
Boron	15	5.00	208	14	<1.50	8.56	7	<1.50	48.1	8	<1.50	3.69
Cadmium	5	<0.100	0.362	9	<0.100	0.735	1	<0.100	0.700	0	<0.100	<0.100
Chromium	15	0.618	2.92	9	0.500	2.28	8	<0.500	28.1	14	0.756	181
Cobalt	14	<0.500	3.75	7	<0.500	3.99	3	<0.500	21.0	1	<0.500	0.881
Copper	15	0.774	81.4	15	6.50	139	9	2.43	24.6	13	<0.500	17.8
Lead	13	<0.35	6.03	15	0.206	25.4	8	<0.2	16.8	11	<0.2	1.62
Mercury	0	<0.05	<0.05	7	<0.05	0.628	4	<0.05	0.330	4	<0.05	0.397
Molybdenum	5	<0.500	2.63	2	<0.500	0.646	1	<0.500	1.71	0	<0.500	<0.500
Nickel	13	<0.500	3.59	7	<0.500	2.61	1	<0.500	13.1	2	<0.500	1.30
Selenium	11	<0.5	9.90	15	0.359	32.3	9	2.40	51.3	13	<0.3	41.7
Strontium	15	45.0	-2,700	15	16.0	457	9	90.4	421	14	71.7	341
Tin	4	<5.00	7.22	0	<6.00	<6.00	1	<5.00	8.89	0	<0.600	<0.600
Vanadium	14	<0.500	9.76	8	<0.500	9.39	2	<0.500	67.3	5	<0.500	3.13
Zinc	15	3.67	74.4	15	9.22	353	9	51.9	107	14	25.0	182

Table 13.--Selenium concentration ranges and medians
for pond and wetland community media

[<, less than]

Medium	<u>Concentration (micrograms per gram dry weight)</u>		
	Minimum	Maximum	Median
Plants	0.5	9.90	1.16
Invertebrates	.359	32.3	3.12
Amphibians	2.40	51.3	4.22
Fish ¹	<.3	41.7	3.77
Fish ²	2.00	35.1	2.32

¹Mosquitofish, killifish, and fathead minnow.

²Common carp and flannelmouthed sucker.

Table 14.--Pond and wetland sites in which the concentrations of selenium in biota exceeded food-item criteria

[See fig. 7 for site locations. Selenium concentration in micrograms per gram ($\mu\text{g/g}$) dry weight. Criteria: 4 to 8 $\mu\text{g/g}$ as a waterfowl food item (Heinz and others, 1989); 5 $\mu\text{g/g}$ as a fish food item (Lemly and Smith, 1987)]

Site number	Site name	Selenium concentration
Plants (15 samples)		
I-2	Gallegos Canyon drainage middle pond	9.90
I-22	Hogback Project east drain	5.10
Invertebrates (15 samples)		
I-2	Gallegos Canyon drainage middle pond	32.3
I-22	Hogback Project east drain	17.4
I-22	Hogback Project east drain	11.1
I-6	Ojo Amarillo Canyon drainage ponds	10.2
I-20	West Hammond Project pond	9.62
I-3	Gallegos Canyon drainage north pond	8.75
I-1	Gallegos Canyon drainage south pond	4.42
Amphibians (8 samples)		
I-2	Gallegos Canyon drainage middle pond	51.3
I-3	Gallegos Canyon drainage north pond	23.5
I-6	Ojo Amarillo Canyon drainage ponds	14.7
I-1	Gallegos Canyon drainage south pond	5.24
I-6	Ojo Amarillo Canyon drainage ponds	4.22
Fish: mosquitofish, killifish, and fathead minnow (9 samples)		
I-22	Hogback Project east drain	41.7
I-22	Hogback Project east drain	27.2
I-20	West Hammond Project pond	15.5
I-20	West Hammond Project pond	13.6
Fish: common carp and flannelmouthed sucker (5 samples)		
I-22	Hogback Project east drain	35.1
I-22	Hogback Project east drain	28.5

In summary, all plant and animal samples from the Gallegos Canyon drainage middle pond and the Hogback Project east drain (sites I-2 and I-22) had concentrations of selenium that exceeded the 5- $\mu\text{g/g}$ criterion for fish and that were within or exceeded the 4- to 8- $\mu\text{g/g}$ criterion for waterfowl. All animal samples from Gallegos Canyon drainage north pond, the Ojo Amarillo Canyon drainage ponds, and the West Hammond Project pond (sites I-3, I-6, and I-20) had concentrations of selenium that exceeded the 5- $\mu\text{g/g}$ criterion for fish and that were within or exceeded the 4- to 8- $\mu\text{g/g}$ criterion for waterfowl. Fish samples from the West Hammond Project pond and the Hogback Project east drain (sites I-20 and I-22) also had concentrations of selenium that exceeded the whole-body 12- $\mu\text{g/g}$ concentration above which reproduction can be impaired. Median concentrations of selenium in water at and near some of these locations (I-2, I-4, I-7, I-8, and I-22) also were larger than established standards, and concentrations in bottom sediment (sites I-2, I-7, and I-22) were as large or larger than the upper expected concentration in soils of the Western United States.

A waterdog sample from the Gallegos Canyon drainage south pond (site I-1) had a selenium concentration that exceeded the 5- $\mu\text{g/g}$ criterion for fish, and an invertebrate sample from this site had a selenium concentration within the 4- to 8- $\mu\text{g/g}$ criterion for waterfowl. Approximately 15 percent of mosquitofish collected from the Hogback Project east drain (site I-22) were observed to have scoliosis.

The generally accepted safe maximum concentration of lead in animal food items is 0.3 $\mu\text{g/g}$ wet weight, or approximately 1 $\mu\text{g/g}$ dry weight (Irwin, 1988). In the San Juan River area, 11 of 15 plant samples, 6 of 15 invertebrate samples, 1 of 9 amphibian samples, and 4 of 14 fish samples collected from pond and wetland habitats had concentrations of lead larger than 1 $\mu\text{g/g}$ dry weight (table 23). Plant samples from Avocet Pond and the Chinde Wash drainage southwest pond (sites I-10 and I-13); invertebrate samples from the Chinde Wash drainage southwest pond, the East Hammond Project east drain and wetland, and the Fruitland Project site (sites I-13, I-16, and I-21); and the amphibian sample (tadpole) from the Fruitland Project site (site I-21) had concentrations of lead larger than 3 $\mu\text{g/g}$ dry weight. The median concentrations of lead were: plants, 1.37 $\mu\text{g/g}$; invertebrates, 0.884 $\mu\text{g/g}$; amphibians, 0.296 $\mu\text{g/g}$; and fish, 0.440 $\mu\text{g/g}$ dry weight.

The maximum recommended concentration of mercury in predator food items is 0.1 $\mu\text{g/g}$ dry weight (Eisler, 1987). In the San Juan River area, 7 of 15 invertebrate samples, 2 of 9 amphibian samples, and 3 of 14 fish samples collected from wetland habitats had concentrations of mercury larger than 0.1 $\mu\text{g/g}$ dry weight. Invertebrate samples from the block 3 Northwest Pond, the Chinde Wash drainage southwest pond, and the Hogback marsh (sites I-12, I-13, and I-23); the amphibian sample from the Chinde Wash southwest pond (site I-13); and fish samples from the Hogback marsh (site I-23) had concentrations of mercury larger than 0.2 $\mu\text{g/g}$ dry weight. Median concentrations in all media were less than the laboratory reporting level of 0.05 $\mu\text{g/g}$.

Fish in the San Juan River

Composite fish samples were collected for analysis of trace-element concentrations from six reaches of the San Juan River in spring 1990 and from seven reaches in fall 1990. Each composite sample typically consisted of five individuals of a single species. Composite samples of common carp and flannelmouthed sucker were collected from each reach during each sampling period. In addition, three brown trout (Salmo trutta) and six channel catfish (Ictalurus punctatus) composite samples were collected during the two sampling periods from reaches where they were available. The results of the analyses of these samples are listed in table 24.

The results of analysis of common carp samples were compared with those of common carp samples collected for the NCBP from 1981 to 1984; the results of analysis of flannelmouthed sucker samples were compared with those of samples of the sucker family (Catostomidae) collected for the NCBP from 1981 to 1984. Concentrations of trace elements are considered to be elevated if they are larger than the 85th percentile of the NCBP data set (Schmitt and Brunbaugh, 1990). As part of the NCBP, 81 samples of common carp and 55 samples of seven species of sucker were collected from sites throughout the United States and analyzed for concentrations of seven trace elements: arsenic, cadmium, copper, lead, mercury, selenium, and zinc (Schmitt and Brunbaugh, 1990).

A subset of the NCBP nationwide data set was created that contained results of analysis of 42 common carp samples and 25 sucker species samples collected in the 17 westernmost contiguous States. This subset was created to determine if any marked differences exist between data from the entire United States and data from the Western United States, and if so, to determine which data set is more appropriate to compare with data collected during this study.

The 85th percentiles for each of seven trace elements of this western subset were calculated and compared with those of the nationwide data set (table 15). For common carp, five of seven 85th-percentile values varied less than 10 percent between the two data sets. In the western subset, the concentration of selenium was higher and the concentration of lead was lower than in the nationwide subset. For sucker species, three of seven 85th-percentile values varied less than 10 percent between the two data sets: copper, lead, and zinc. In the western subset, the concentration of arsenic was higher and the concentrations of cadmium, mercury, and selenium were lower than in the nationwide subset. The larger number of trace elements in sucker species for which the variation between the data sets was more than 10 percent could be due in part to the inclusion of several species of the sucker family, which might have different metabolic characteristics.

Table 15.--Comparison of concentrations of trace elements in fish samples collected for the National Contaminant Biomonitoring Program (NCBP) with samples collected from the San Juan River in 1990

[Concentrations are in micrograms per gram wet weight; <, less than]

Trace element	San Juan River						
	NCBP (1990) 85th-percentile concentration		Concentration			Number of samples with concentration larger than the NCBP 85th percentile ¹	
	Nationwide	Western	Minimum	Maximum	Median	Nationwide	Western
	<u>Common carp</u>						
Arsenic	0.15	0.14	0.07	0.10	0.09	0	0
Cadmium	.14	.14	.02	.17	.09	2	2
Copper	1.12	1.02	.79	1.87	1.32	11	12
Lead	.30	.25	<.06	1.69	.19	4	4
Mercury	.11	.10	.06	.19	.08	3	3
Selenium	1.25	1.70	.61	1.56	.84	2	0
Zinc	73.7	68.8	15.1	90.3	66.4	3	4
	<u>Sucker species</u>						
Arsenic	0.17	0.20	<0.09	0.19	0.10	1	0
Cadmium	.05	.04	<.03	.45	.05	0	2
Copper	1.01	.99	.58	1.47	.79	2	3
Lead	.22	.20	<.06	.90	.20	4	5
Mercury	.18	.13	.05	.32	.13	4	6
Selenium	.40	.35	.45	1.06	.69	13	13
Zinc	20.8	21.5	12.4	42.1	15.8	2	2

¹The total number of samples collected was 13 for both common carp and sucker species.

The maximum and median concentrations of a given trace element in the San Juan River were compared with the 85th-percentile concentrations of the two NCBP data sets to determine if concentrations of that element were elevated in the San Juan River. If the distribution of concentrations of a given trace element from the San Juan River data set (13 samples) is the same as that of either NCBP data set, then the expected number of samples to have concentrations larger than the NCBP 85th percentile would be about 2:

$$(1.00-0.85) \times 13 = 1.95$$

If the concentrations of more than two samples from the San Juan River data set are larger than the NCBP 85th-percentile value, then the San Juan River data set is skewed toward a larger-than-expected number of samples having concentrations larger than the NCBP 85th percentile. The small sample size (13) limits the rigorous use of this criterion; in most cases, however, this criterion approximately supports comparison of median concentrations of trace elements in the San Juan River with 85th-percentile concentrations in NCBP data (table 15).


Concentrations of selenium in flannelmouthed sucker are elevated in the San Juan River when compared with selenium concentrations in all species of suckers in the NCBP data set. In all 13 samples, concentrations of selenium were larger than the 85th-percentile concentration of the nationwide and western NCBP data sets (table 15). The median concentration of selenium in flannelmouthed suckers collected from the San Juan River was approximately twice the 85th-percentile concentration of the western NCBP data set (fig. 10). Selenium concentrations in common carp ranged from 0.77 to 1.56 $\mu\text{g/g}$ wet weight in samples collected during the spring and from 0.61 to 1.35 $\mu\text{g/g}$ wet weight in samples collected during the fall. The median values of the spring and fall samples were 0.91 and 0.80 $\mu\text{g/g}$ wet weight, respectively. Selenium concentrations in flannelmouthed sucker ranged from 0.47 to 0.80 $\mu\text{g/g}$ wet weight in samples collected in the spring and from 0.45 to 1.06 $\mu\text{g/g}$ wet weight in samples collected from the same sites in the fall. The median values of the spring and fall samples were 0.69 and 0.68 $\mu\text{g/g}$ wet weight, respectively. These small differences in minimum, median, and maximum concentrations between spring and fall data suggest that neither the common carp nor flannelmouthed sucker was exposed to substantially larger concentrations of selenium during the irrigation season.

The largest concentrations of selenium in common carp and flannelmouthed sucker typically occurred in samples from reaches A and B (fig. 8; table 24). Reach A is located upstream from DOI-sponsored irrigation in the study area, and reach B is located along the Hammond Irrigation Project from Bloomfield to just downstream from Lee Acres. Selenium concentrations in these fish decreased in a downstream direction: the smallest concentrations of selenium typically occurred in reaches D and E, which are located from downstream from the mouth of the La Plata River to The Hogback (fig. 8). The NIIP and the Fruitland Irrigation Project are adjacent to these reaches on the south side of the San Juan River, and non-DOI-sponsored irrigation projects are adjacent to these reaches on the north side of the river.

Concentrations of copper in common carp are elevated in the San Juan River. Eleven of 13 samples had copper concentrations larger than the 85th-percentile concentration of the nationwide NCBP data set; 12 samples had copper concentrations larger than the 85th-percentile concentration of the western NCBP data set (table 15). The median concentration of copper in common carp collected from the San Juan River was larger than the 85th-percentile concentration of both the nationwide and western NCBP data sets (fig. 11).

Concentrations of lead in flannelmouthed sucker are elevated in the San Juan River. Four of 13 samples of flannelmouthed sucker had concentrations of lead larger than the 85th-percentile concentration of the nationwide NCBP data set (table 15); 5 samples had concentrations of lead larger than the 85th-percentile concentration of the western NCBP data set. The median concentration of lead in flannelmouthed suckers collected from the San Juan River was about the same as the 85th-percentile concentration of both the nationwide and western NCBP data sets (fig. 12).

Concentrations of mercury in flannelmouthed sucker also are elevated in the San Juan River. Four of 13 samples had mercury concentrations larger than the 85th-percentile concentration of the nationwide NCBP data set (table 15); 6 samples had concentrations of mercury larger than the western NCBP data set. The median mercury concentration in flannelmouthed suckers collected from the San Juan River was about the same as the 85th-percentile concentration of the western NCBP data set (fig. 13).



EXPLANATION





Figure 10.--Distribution of concentrations of selenium in all species of suckers collected for the National Contaminant Biomonitoring Program (NCBP) in 1984, and in flannelmouthed suckers from the San Juan River in 1990.



EXPLANATION





Figure 11.--Distribution of concentrations of copper in carp collected for the National Contaminant Biomonitoring Program (NCBP) in 1984 and from the San Juan River in 1990.



EXPLANATION

○ — FAR-OUTLYING VALUES: MORE THAN 3.0 TIMES INTERQUARTILE RANGE BEYOND BOX.

x — OUTLYING VALUES: 1.5 TO 3.0 TIMES INTERQUARTILE RANGE BEYOND BOX.





Figure 12.--Distribution of concentrations of lead in all species of suckers collected for the National Contaminant Biomonitoring Program (NCBP) in 1984, and in flannelmouthed suckers from the San Juan River in 1990.



EXPLANATION




Figure 13.--Distribution of concentrations of mercury in all species of suckers collected for the National Contaminant Biomonitoring Program (NCBP) in 1984, and in flannelmouthed suckers from the San Juan River in 1990.

Filets of 15 common carp collected in spring 1990, and of 35 common carp, 16 channel catfish, and 5 brown bullhead (Ameiurus nebulosus) collected in fall 1990 were analyzed to determine the concentrations of constituents in the edible portions of these fish. Results of these analyses were distributed to the New Mexico Health Department and New Mexico Environment Department. In October 1991, these agencies jointly issued specific fish consumption guidelines because of mercury contamination in three reaches of the San Juan River from the Hammond Project Diversion to the mouth of the Mancos River (James Piatt, New Mexico Environment Department, written commun., 1992).

The guidelines advised pregnant women to consume no more than one meal per month of common carp up to 24 in. in length if caught in any of the three reaches, or consume no more than one meal per month of catfish up to 31 in. if caught between the Hammond Project Diversion and The Hogback, up to 22 in. if caught between The Hogback and Cudei, or up to 29 in. if caught between Cudei and the mouth of the Mancos River. Channel catfish between 31 and 41 in. caught between the Hammond Project Diversion and The Hogback, or between 29 and 37 in. caught between Cudei and the mouth of the Mancos River "...should not be eaten by pregnant women, breast-feeding women, women who plan to have children, or anyone under 18 years of age. Everyone else should eat no more than 26 meals of these fish in a year and no more than 13 of the 26 meals should be consumed in 1 month. The remaining meals should be evenly spaced over the remainder of the year."

External conditions were analyzed on all fish sampled during the spring and fall collections except for common carp. Fish were examined for external lesions, including cataracts, melanomas, papillomas, and ulcers.

Twenty-eight percent of flannelmouthed sucker and 35 percent of channel catfish sampled had external lesions. The largest incident rate of lesions in both species was in reach F (Shiprock to Cudei)--50 percent for flannelmouthed sucker and 37 percent for channel catfish. Selenium concentrations in water samples collected from the San Juan River at the Shiprock Municipal Diversion (site R-10) and from the San Juan River 3 mi downstream from Cudei (site R-11) ranged from less than 1 to 2 $\mu\text{g}/\text{L}$. The concentration of selenium was 0.3 $\mu\text{g}/\text{g}$ in the fraction of the sediment sample less than 0.062 millimeter collected from the San Juan River 3 mi downstream from Cudei (site R-11). These small concentrations in water and bottom sediment, along with larger concentrations of selenium in carp from reach A and larger concentrations of selenium in flannelmouthed sucker from reaches A and B, suggest that the incident rate of lesions in reach F is not related to selenium concentrations.

Birds

Forty-six adult migratory waterbird samples, 4 juvenile mallards, and 13 avian eggs were collected from ponds and wetlands on the four irrigation projects. Species collected include American avocet (Recurvirostra americana), American coot (Fulica americana), mallard (Anas platyrhynchos), cinnamon teal (Anas cyanoptera), green-winged teal (Anas crecca), and killdeer (Charadrius vociferus). Six adult red-winged blackbird samples (Agelaius phoeniceus) and one yellow-headed blackbird sample (Xanthocephalus xanthocephalus) also were collected.

Composites of liver and kidney tissue from adult and juvenile birds and whole embryos were analyzed for concentrations of trace elements. Liver and kidney were used instead of livers only to maximize sample volume and, at the same time, minimize the number of birds taken. Ohlendorf and others (1990) reported a statistically significant correlation between selenium concentrations in livers and kidneys of adult coots.


Collection sites were grouped by geographical area on the NIIP and the East Hammond Project. On the NIIP, the groups included the Gallegos Canyon drainage ponds (sites I-1, I-2, and I-3) and ponds in enclosed drainages (sites I-9, I-10, I-11, and I-12). On the East Hammond Project, the east and west drains and adjacent wetlands (sites I-16 and I-17) were grouped together. Other waterbird collection sites included the West Hammond Project pond (site I-20), the Fruitland Project site (site I-21), and the Hogback marsh (site I-23) (see fig. 7 for site locations). The results of analysis of these samples are listed in table 26 of the Supplemental data section. Statistical summaries of selenium concentrations are shown in figure 14 for species of adult birds and listed in table 16 for adult birds at each site or site group.

Table 16.--Summary of selenium concentrations in adult bird liver and kidney tissue at each sampling site or group of sampling sites

[See fig. 7 for site locations]

Site(s) (number of samples)	Concentration of selenium in liver and kidney tissue, in micrograms per gram dry weight		
	Minimum	Maximum	Median
I-1, I-2, I-3 (6)	19.7	103	31.2
I-6 (4)	14.1	31.2	20.5
I-9, I-10, I-12 (14)	2.74	22.0	12.5
I-16, I-17 (7)	7.68	26.4	14.4
I-20 (3)	3.82	25.9	4.80
I-21 (6)	6.49	22.7	16.2
I-23 (6)	3.83	12.0	7.43

Concentrations of selenium varied substantially for a given species at a given site or group of sites. For example, selenium concentrations in two adult mallard samples collected from the West Hammond Project pond (site I-20) were 3.82 and 25.9 $\mu\text{g/g}$, and selenium concentrations in two adult teal samples collected from site I-17 were 7.68 and 26.4 $\mu\text{g/g}$. In samples collected from the enclosed drainages on the NIIP (sites I-9 through I-12), selenium concentrations ranged from 2.84 to 22.0 $\mu\text{g/g}$ in four adult mallard samples and from 5.79 to 21.4 $\mu\text{g/g}$ in three juvenile mallard samples.



EXPLANATION




Figure 14.--Concentrations of selenium in adult birds collected from the San Juan River area.

This variation may be the result of movement of these birds from one wetland habitat to another within the study area or to wetland habitats near but outside the study area. These habitats may have large differences in selenium available in water, sediment, and food items. During this study, adult birds were observed moving from one pond to another in the Gallegos Canyon drainage (sites I-1, I-2, and I-3). Bellrose (1976, p. 229-243) reported that female mallards may move their broods as much as 2 mi to new wetland habitats in response to drought or unstable water conditions, and that adult mallards may use several marshes during courtship and nesting.

Skorupa and others (1990) reported a clear relation between selenium concentrations in livers of adult waterbird populations and the occurrence of deformities in embryos (teratogenesis). Selenium concentrations less than 10 $\mu\text{g/g}$ dry weight in livers of adult waterbird populations usually did not cause teratogenesis, whereas those more than 30 $\mu\text{g/g}$ dry weight usually did. Concentrations between 10 and 30 $\mu\text{g/g}$ in livers may or may not have caused teratogenesis. The potential for teratogenesis was species-specific, and observation was required on a case-by-case basis.

The median concentration of 31.2 $\mu\text{g/g}$ selenium in adult bird liver and kidney samples from the Gallegos Canyon drainage ponds (sites I-1, I-2, and I-3) indicates that teratogenesis can be expected to occur in waterbird populations that inhabit Gallegos Canyon. The median selenium concentration in samples from four other sites or site groups (table 16) indicates that teratogenesis may or may not be occurring, but the potential for teratogenesis exists at these sites. In the entire San Juan River area, median concentrations of selenium in livers and kidneys of 5 avocet samples (15.3 $\mu\text{g/g}$), 7 teal species samples (16.4 $\mu\text{g/g}$), 7 killdeer samples (16.4 $\mu\text{g/g}$), and 11 mallard samples (17.9 $\mu\text{g/g}$) indicate the existing potential for teratogenesis in these species.

One individual and three composite juvenile mallard samples were collected from ponds on the NIIP. One juvenile, collected from the Ojo Amarillo Canyon ponds drainage (site I-6), was found dead. The bird was one of two in a composite sample; the concentration of selenium in liver and kidney tissue of this sample was 28.2 $\mu\text{g/g}$. A necropsy did not reveal the cause of death or evidence of physical trauma.

Thirteen avian egg samples were collected from five sites or site groups: one individual mallard sample from the Ojo Amarillo Canyon drainage ponds (site I-6), three individual and two composite avocet samples from ponds in enclosed drainages on the NIIP (sites I-9, I-10, I-11, and I-12), one individual and one composite killdeer sample from the East Hammond Project east and west drains and adjacent wetlands (sites I-16 and I-17), one composite cinnamon teal sample from the Fruitland Project site (site I-21), and four individual coot samples from a single nest at the Hogback marsh (site I-23). Each composite sample was made up of offspring of the same adult female, and all four individual coot samples collected from the Hogback marsh (site I-23) were offspring of the same adult female.

No evidence of teratogenesis was observed in bird embryo samples in the San Juan River area; however, only 7 of the 13 samples collected were fully formed and appropriate for inspection. One of these samples was from the Ojo Amarillo Canyon drainage ponds, and none were from Gallegos Canyon drainage ponds, the West Hammond Project pond, or the Hogback Project east drain, where selenium concentrations in water, bottom sediment, and other biota routinely were larger than established standards and criteria. The embryos examined during this study, therefore, do not accurately reflect conditions throughout the study area.

Skorupa and others (1990), Skorupa and Ohlendorf (1991), and Skorupa and others (U.S. Fish and Wildlife Service, written commun., 1991) reported a clear relation between selenium concentrations in waterbird embryos and the occurrence of teratogenesis. In individual embryos the selenium concentrations less than 9 $\mu\text{g/g}$ dry weight usually did not cause teratogenesis, whereas those more than 60 $\mu\text{g/g}$ dry weight usually did. Concentrations of selenium between 9 and 60 $\mu\text{g/g}$ may or may not have caused teratogenesis and required observation on a case-by-case basis. The number of waterbird embryos (mallard, avocet, killdeer, and teal species and coot) having concentrations of selenium in each of these three concentration categories is listed in table 17.

Table 17.--Number of bird embryo samples in each of three selenium-concentration categories at each sampling site or group of sampling sites

[See fig. 7 for site location]

Site(s) (species)	Concentration of selenium in waterbird embryos, <u>in micrograms per gram, dry weight</u>		
	Less than 9	Between 9 and 60	More than 60
I-6 (mallard)	0	1 (17.6)	0
I-9 to I-12 (avocet)	5	0	0
I-16, I-17 (killdeer)	2	0	0
I-21 (teal species)	1	0	0
I-23 (coot)	4	0	0

Of the 13 waterbird egg samples collected, 12 samples had selenium concentrations less than 9 $\mu\text{g/g}$. One mallard sample collected near the Ojo Amarillo ponds (site I-6) had a concentration of 17.6 $\mu\text{g/g}$ dry weight. This sample; however, was the only egg collected from the four locations where selenium concentrations in water, bottom sediment, and other biota routinely were larger than established standards and criteria; additional eggs from these four locations were not available. Therefore, as stated earlier, selenium concentrations in embryos analyzed as part of this study do not accurately reflect conditions throughout the study area.

External examinations of the seven fully formed embryos were conducted: one mallard from the Ojo Amarillo Canyon drainage ponds (site I-6), two avocets from the block 3 Northwest Pond on the NIIP (site I-12), and four coots from the Hogback marsh (site I-23). All embryos were alive and appeared normal. Three additional coot embryos from a single nest in the Hogback marsh (site I-23) were incubated, hatched, raised, and released. Only one of the embryos examined, however, was collected from the four locations where selenium concentrations in water, bottom sediment, and other biota routinely were larger than established standards and criteria.

Concentrations of Pesticides in Water

Water samples were collected from seven sites on the NIIP and analyzed for 12 triazine and other nitrogen-containing herbicides and 6 chlorophenoxy acid herbicides (table 27). Of these herbicides, the following were present in concentrations at or larger than the laboratory reporting level: cyanazine at three sites in the Gallegos Canyon area, 2,4-D at one site in the Gallegos Canyon area and two sites in the Ojo Amarillo Canyon area, and dicamba at one site in the Gallegos Canyon area.

Water samples collected from seven sites on the NIIP were analyzed for 10 carbamate insecticides and 12 organophosphorus insecticides (table 27). At the block 3 Northwest Pond (site I-12), concentrations of methyl parathion and parathion were 0.14 $\mu\text{g/L}$ and 0.61 $\mu\text{g/L}$, respectively. None of these insecticides were present in concentrations at or larger than their respective laboratory reporting levels at any of the other sampled sites.

Concentrations of Pesticides in Bottom Sediment

Bottom-sediment samples from nine sites on the four irrigation projects were analyzed for concentrations of 17 organochlorine compounds, including pesticides, pesticide metabolites, and polychlorinated biphenyls (PCB's) (table 27). Concentrations at or larger than compound laboratory reporting levels included DDE at the Gallegos Canyon drainage middle pond (site I-2), Ojo Amarillo Canyon (site I-7), and the East Hammond Project west drain and adjacent wetlands (site I-17); DDD and DDE at the West Hammond Project pond (site I-20); DDD, DDE, and chlordane at the Fruitland Project site (site I-21), the Hogback marsh (site I-23), and the Hogback Project west drain (site I-24); and DDT, DDD, DDE, and chlordane at the Hogback Project east drain (site I-22). The maximum concentration of each of these compounds, in micrograms per kilogram, was DDT, 0.1; DDD, 0.2; DDE, 0.4; and chlordane, 2.0.

Concentrations of Pesticides in Biota

Fish and bird samples were collected for analysis of pesticides. Results of these analyses are listed in tables 28 and 29 (Supplemental data section). Acetylcholinesterase (AChE) and butyrylcholinesterase (BChE) inhibition assays were conducted on brain tissue and blood serum, respectively, of bird samples collected throughout the study area to qualitatively determine exposure to organophosphate and carbamate insecticides. The results of these assays are listed in table 30.

Fish in the San Juan River

Six flannelmouthed sucker whole-body composite samples were collected from San Juan River reaches A, and C through G; samples were analyzed for concentrations of 22 organochlorine compounds including pesticides, pesticide metabolites, and PCB's (table 28). Of the 132 total analytical measurements, the concentrations of organochlorine compounds in 96 analyses were less than the laboratory reporting level of 0.01 $\mu\text{g/g}$ wet weight, and no concentration of any organochlorine compound was more than the NCBP (1984) geometric mean concentration of that compound (Schmitt and others, 1990). The maximum concentration of any organochlorine compound was 0.21 $\mu\text{g/g}$ wet weight total PCB's in a sample collected from reach D of the San Juan River.

Birds

Each of 35 migratory bird samples collected from throughout the study area was analyzed for 22 organochlorine compounds (table 29). The bird samples included 16 adult killdeer, 7 adult Cassin's kingbirds (Tyrannus vociferans), 3 adult eastern kingbirds (Tyrannus tyrannus), 7 juvenile mallards, 1 juvenile coot, and 1 juvenile yellow-headed blackbird. Of 770 total analytical measurements, concentrations of organochlorine compounds in 722 measurements were less than the laboratory reporting level of 0.01 $\mu\text{g/g}$ wet weight. Except for DDE, the concentrations of organochlorine compounds in the remaining measurements were all less than the 1.0- $\mu\text{g/g}$ wet weight criterion for protection of predators (National Academy of Sciences, 1973).

DDE was present in concentrations at or larger than the laboratory reporting level of 0.01 $\mu\text{g/g}$ wet weight in 31 of the 35 bird samples, and in concentrations at or larger than the 1.0- $\mu\text{g/g}$ wet weight criterion for protection of predators (National Academy of Sciences, 1973) in eight samples. All eight of these samples were killdeer. The maximum concentration of DDE in killdeer was 2.4 $\mu\text{g/g}$ wet weight, and the median value was 0.98 $\mu\text{g/g}$.

Neither DDT nor any of its metabolites other than DDE were present in concentrations larger than the laboratory reporting level of 0.01 $\mu\text{g/g}$ in any migratory bird sample. The higher frequency of concentrations of DDE at and larger than the laboratory reporting level suggests that these birds have not been exposed to recent applications of DDT.

Cholinesterase assays were conducted on brain tissue and blood serum of migratory birds to determine possible exposure to organophosphate and carbamate insecticides (table 30). Five AChE inhibition assays were conducted on brain tissue, and three BChE inhibition assays were conducted on blood serum of adult drake mallard samples collected from wetland habitats on the NIIP in mid-May 1990. Thirty-five additional AChE and 10 additional BChE inhibition assays were conducted on brain tissue and blood serum, respectively, from bird samples collected on wetland habitats throughout the study area from mid-June to mid-July 1990. This group included five assays of brain tissue and two assays of blood serum from adult drake mallard samples collected from wetland habitats on the NIIP.

Hill (1988) established diagnostic ranges of AChE activity for several migratory bird species, including mallards and coots. Values of AChE activity less than the lower limit of the expected range of activity for a given species may indicate exposure to AChE activity-inhibiting compounds, which primarily are organophosphate and carbamate insecticides. The expected range is defined as the mean value plus or minus two standard deviations for the species being evaluated.

Comparison of results of assays conducted in the San Juan River area with those reported by Hill (1988) indicates that mallards in the San Juan River area in general, and on the NIIP specifically, may have been exposed to an unidentified AChE activity-inhibiting compound. The assays also suggest that mallards from the middle ponds in Gallegos Canyon (site I-2) may have been more severely exposed than mallards at other sites on the NIIP (table 30). American coots, conversely, did not appear to have been exposed to such a compound (table 18).

Table 18.--Comparison of acetylcholinesterase (AChE) activity in brain tissue of bird samples collected in the San Juan River area with diagnostic ranges of AChE activity

[AChE activity in micromoles per minute per gram, wet weight; diagnostic range established by Hill (1988); expected range, mean plus or minus two standard deviations]

Species	Activity					
	San Juan River area			Diagnostic range		
	Number of samples	Range	Mean	Number of samples	Expected range	Mean
Mallard	13	6.7 - 11.5	9.7	11	9 - 15	12
American coot	6	20.7 - 24.5	22.7	5	15 - 21	18

Comparison of AChE activity in adult drake mallards collected from the NIIP during the two sampling periods suggests less effect from exposure to AChE activity-inhibiting compounds in the mid-June to mid-July sampling period than in the mid-May sampling period (table 19). Comparison of BChE activities in these samples indicates a less clear trend. The trend of AChE activity may be the result of no exposure to AChE-inhibiting compounds between the sampling periods and a partial recovery from earlier exposure; continued exposure to the same compounds at a smaller dose; or exposure to other compounds that resulted in less AChE inhibition.

Table 19.--Cholinesterase activity in brain tissue and blood serum of adult drake mallard samples collected on the Navajo Indian Irrigation Project in mid-May 1990 and from mid-June to mid-July 1990

[Activity in micromoles of acetylthiocholine iodide hydrolyzed of brain tissue per minute per gram, wet weight; milliunits of acetylthiocholine iodide hydrolyzed per minute per milliliter of blood serum]

Sample type	Activity					
	Mid-May			Mid-June to mid-July		
	Number of samples	Range	Median	Number of samples	Range	Median
Brain tissue	5	6.7 - 10.3	8.9	5	7.6 - 11.5	10.3
Blood serum	3	537 - 824	608	2	660 - 708	684

Concentrations of Hydrocarbons in Water

Water samples from all three ponds in the Gallegos Canyon drainage (sites I-1, I-2, and I-3), from the East Hammond Project pond one-tenth mi north of the west drain (site I-18), and from a wetland near the Gallegos Canyon drainage south pond (site I-1) that receives runoff from the area surrounding an oil production well were collected and analyzed for hydrocarbon compounds by gas chromatographic/flame ionization detection (GC/FID scans). These sites were chosen because of their proximity to oil and gas production activity.

On the basis of results of these initial GC/FID scans, the East Hammond Project pond one-tenth mi north of the west drain (site I-18) and the wetland near the Gallegos Canyon drainage south pond (site I-1) were selected for further analysis by gas chromatography/mass spectrometry for 34 hydrocarbon compounds. The results of these two analyses indicate that none of the 34 compounds were present in concentrations at or larger than their respective laboratory reporting levels.

SUMMARY

Data collected in 1990 and compared to established standards and criteria indicate that selenium is the major trace element of concern in all sampled media (water, bottom sediment, and biota) at six sites in four locations within the San Juan River study area. These locations are the Gallegos Canyon drainage middle and north ponds on the NIIP (sites I-2 and I-3), two sites in the Ojo Amarillo Canyon drainage on the NIIP (I-6 and I-7/I-8), the West Hammond Project pond (I-20), and the Hogback Project east drain (I-22).

Concentrations of selenium in all media from these locations routinely exceeded established standards and criteria. The concentration of selenium in 11 water samples from these locations exceeded the State of New Mexico standard of 5 $\mu\text{g/L}$ for the protection of fisheries. The water at these locations supports pond and wetland communities and provides habitat for waterfowl. A wetland at the outfall of the Hogback Project east drain provides habitat for San Juan River fish. The concentration of selenium in water from these locations has the potential to cause significant harmful effects to fish and wildlife.

Concentrations of selenium in 8 of 12 bottom-sediment samples collected from irrigation projects exceeded the baseline concentration for soils in the Western United States. The median selenium concentration in these 12 samples was 1.75 $\mu\text{g/g}$ compared with a geometric mean concentration of 0.23 $\mu\text{g/g}$ in soils in the Western United States. Selenium concentrations in five bottom-sediment samples from the Gallegos Canyon drainage middle pond on the NIIP, Ojo Amarillo Canyon, and the Hogback Project ranged from 4.5 to 37 $\mu\text{g/g}$.

Plant samples from the middle pond of Gallegos Canyon and from the Hogback Project east drain and invertebrate samples from three sites in the Gallegos Canyon drainage, one site in the Ojo Amarillo Canyon drainage, the Hogback Project east drain, and the West Hammond pond had concentrations of selenium within or larger than the 4- to 8- $\mu\text{g/g}$ dietary threshold criterion for waterfowl food items. The selenium concentration at five of the six sites of invertebrate samples also was larger than the 5- $\mu\text{g/g}$ dietary threshold criterion for fish food items.

The concentration of selenium in five waterdog samples from Gallegos Canyon and Ojo Amarillo Canyon drainages on the NIIP was within or larger than the 4- to 8- $\mu\text{g/g}$ dietary threshold criterion for waterfowl food items. The selenium concentration in four of these five samples was larger than the 5- $\mu\text{g/g}$ dietary threshold criterion for fish food items.

Selenium concentrations in six fish samples (mosquitofish, killifish, fathead minnow, common carp, and flannelmouthed sucker) collected from the Hogback Project east drain (site I-22) and the West Hammond pond (site I-20) were larger than the dietary threshold criteria for waterfowl or fish food items. Selenium concentrations in these fish also were larger than the 12- $\mu\text{g/g}$ whole-body concentration above which reproductive failure could occur. All 13 samples of flannelmouthed sucker had concentrations of selenium larger than the 85th-percentile concentration for the NCBP, and the median concentration of samples collected from the San Juan River was approximately twice the 85th-percentile concentration in suckers collected for the NCBP.

The selenium concentration in all but 2 of the 13 samples was less than the 4- to 8- $\mu\text{g/g}$ criterion for waterfowl food items; the selenium concentration in all but 1 of the 13 samples was less than the 5- $\mu\text{g/g}$ criterion for fish food items. Samples with selenium concentrations larger than these criteria were from river reach A, from the Hammond Project Diversion to Blanco, which is upstream from DOI-sponsored irrigation. Concentrations of selenium in common carp and flannelmouthed sucker did not vary significantly between spring and fall samples, suggesting that fish were not being exposed to larger selenium concentrations during the irrigation season.

Eleven of 15 plant samples, 6 of 15 invertebrate samples, 1 of 9 amphibian samples, and 4 of 14 fish samples collected from sites on irrigation projects had concentrations of lead larger than the criterion for animal protection of about 1 $\mu\text{g/g}$ dry weight. Four of 13 samples of both common carp and flannelmouthed sucker had lead concentrations larger than the 85th-percentile concentration in these species collected for the NCBP. Four of 13 samples of flannelmouthed sucker had mercury concentrations larger than the 85th-percentile concentration in suckers collected for the NCBP.

Forty-six adult waterbird samples consisting of six species were collected from seven sites or site groups on irrigation projects. Median selenium concentrations in liver and kidney tissue were determined for birds collected from each of the seven areas. The median selenium concentration in Gallegos Canyon (31.2 $\mu\text{g/g}$ dry weight) was larger than the 30- $\mu\text{g/g}$ concentration above which teratogenesis can be expected to occur. No waterfowl embryos were available from Gallegos Canyon drainage to confirm or deny that teratogenesis was occurring. The median selenium concentrations in Ojo Amarillo Canyon (20.5 $\mu\text{g/g}$ dry weight) and at three other sites or site groups (12.5 to 16.2 $\mu\text{g/g}$ dry weight) were within the 10- to 30- $\mu\text{g/g}$ range where the potential for teratogenesis exists.

Sixteen of 310 determinations for four classes of pesticides in selected water samples from the NIIP (40 compounds) indicated concentrations larger than reporting levels. The largest concentration of any of these compounds was 4.9 $\mu\text{g/g}$ atrazine in the sample from the Gallegos Canyon drainage south pond (site I-1).

Eighteen of 170 determinations for organochlorine compounds in bottom sediment (analysis for 17 compounds in each of 10 samples) indicated concentrations larger than laboratory reporting levels. The largest concentration of any of these compounds was 2.0 $\mu\text{g/g}$ chlordane in a sample from the Hogback Project west drain (site I-24).

Thirty-six of 132 determinations for organochlorine compounds in flannelmouthed sucker (analysis for 22 compounds in each of six samples) indicated concentrations at or larger than the laboratory reporting level of 0.01 $\mu\text{g/g}$ wet weight. No concentration of any compound was as large as its respective NCBP geometric mean concentration. The largest organochlorine compound concentration was 0.21 $\mu\text{g/g}$ wet weight total PCB's in a sample from river reach D.

Forty-eight of 770 determinations for organochlorine compounds in bird samples (analysis for 22 compounds in each of 35 samples) indicated concentrations at or larger than the laboratory reporting level of 0.01 $\mu\text{g/g}$ wet weight; 31 of these were DDE. Concentrations of DDE in eight killdeer samples were at or larger than the 1.0- $\mu\text{g/g}$ wet-weight criterion for protection of predators. The maximum concentration of DDE in killdeer was 2.4 $\mu\text{g/g}$ wet weight.

Results of cholinesterase enzyme activity assays for brain tissue and blood serum suggest that mallards in the San Juan River area in general, and in Gallegos Canyon on the NIIP specifically, may have been exposed to unidentified cholinesterase activity-inhibiting compounds.

SELECTED REFERENCES

- Bellrose, F.C., 1976, Ducks, geese, and swans of North America: Harrisburg, Pa., Stackpole Books, p. 229-243.
- Bunck, C.M., Prouty, R.M., and Krynitsky, A.J., 1987, Residues of organochlorine pesticides and polychlorinated biphenyls in starlings (*Sturnus vulgaris*) from the continental United States, 1982: Environmental Monitoring and Assessment 8, p. 59-75.
- Dane, C.H., and Bachman, G.O., 1965, Geologic map of New Mexico: U.S. Geological Survey, 2 sheets, scale 1:500,000.
- Edwards, T.K., and Glysson, G.D., 1988, Field methods for measurement of fluvial sediment: U.S. Geological Survey Open-File Report 86-531, 118 p.
- Eisler, Ronald, 1987, Mercury hazards to fish, wildlife, and invertebrates-- A synoptic review: U.S. Fish and Wildlife Service Biological Report 85 (1.10), 90 p.
- Federal Register, 1990: v. 55, no. 99, May 22, 1990, p. 21, 154-161.
- _____1991: v. 56, no. 20, January 30, 1991, p. 3526-3597.
- Fenneman, N.M., 1931, Physiography of the western United States: New York, McGraw-Hill, 534 p.
- Fishman, M.J., and Friedman, L.C., eds., 1989, Methods for determination of inorganic substances in water and fluvial sediments: U.S. Geological Survey Techniques of Water-Resources Investigations, book 5, chap. A1, 545 p.
- Friedman, L.C., and Erdmann, D.E., 1982, Quality assurance practices for the chemical and biological analyses of water and fluvial sediments: U.S. Geological Survey Techniques of Water-Resources Investigations, book 5, chap. A6, 181 p.
- Heinz, G.H., Hoffman, D.J., and Gold, L.G., 1989, Impaired reproduction of mallards fed an organic form of selenium: Journal of Wildlife Management 53 (2), p. 418-428.
- Hill, E.F., 1988, Brain cholinesterase activity of apparently normal wild birds: Journal of Wildlife Diseases 24 (1), p. 51-61.
- Irwin, R.J., 1988, Impacts of toxic chemicals on Trinity River fish and wildlife: U.S. Fish and Wildlife Service, Fort Worth, Tex., 82 p.
- Kemp, H.T., Little, R.L., Holoman, V.L., and Darby, R.L., 1973, Water quality criteria data book - Volume 5--Effects of chemicals on aquatic life: U.S. Environmental Protection Agency 18050, 502 p.
- Lemly, D.A., and Smith, G.J., 1987, Aquatic cycling of selenium-- Implications for fish and wildlife: U.S. Fish and Wildlife Service Leaflet 12, 10 p.

SELECTED REFERENCES--Continued

- Lowe, T.P., May, T.W., Brumbaugh, W.G., and Kane, D.A., 1985, National Contaminant Biomonitoring Program--Concentrations of 7 elements in freshwater fish, 1978-81: Archives of Environmental Toxicology 14, p. 363-388.
- Meneely, S.C., Duzan, S.L., and Schemnitz, S.D., 1979, Impacts of uranium mining and milling upon fish and wildlife resources of the New Mexico San Juan Basin Region: Las Cruces, New Mexico State University, Department of Fishery and Wildlife Sciences, 214 p.
- National Academy of Sciences, National Academy of Engineering, 1973, Section III--Freshwater aquatic life and wildlife, water quality criteria: Ecological Research Series, EPA-R3-73-033, p. 106-113.
- New Mexico Water Quality Control Commission, 1988, Water-quality standards for interstate and intrastate streams in New Mexico as amended through March 8, 1988: New Mexico State modifying rule no. 88-1, 48 p.
- O'Brien, T.F., 1987, Organochlorine and heavy metal contaminant investigation, San Juan River Basin, New Mexico: U.S. Fish and Wildlife Service, Albuquerque, N. Mex., 21 p.
- Ohlendorf, H.M., Hothem, R.L., Bunck, C.M., and Marois, K.C., 1990, Bioaccumulation of selenium in birds at Kesterson Reservoir, California: Archives of Environmental Contamination and Toxicology, v. 19, p. 495-507.
- Ong, Kim, O'Brien, T.F., and Rucker, M.D., 1991, Reconnaissance investigation of water quality, bottom sediment, and biota associated with irrigation drainage in the middle Rio Grande valley and Bosque del Apache National Wildlife Refuge, New Mexico, 1988-89: U.S. Geological Survey Water-Resources Investigations Report 91-4036, 113 p.
- Schmitt, C.J., and Brumbaugh, W.G., 1990, National Contaminant Biomonitoring Program--Concentrations of arsenic, cadmium, copper, lead, mercury, selenium, and zinc in U.S. freshwater fish, 1976-84: Archives of Environmental Contaminant Toxicology 19, p. 731-747.
- Schmitt, C.J., Zajicek, J.L., and Peterman, P.A., 1990, National Contaminant Biomonitoring Program--Residues of organochlorine chemicals in U.S. freshwater fish: Archives of Environmental Contaminant Toxicology 19, p. 748-781.
- Severson, R.C., and Gough, L.P., 1981, Geochemical variability of natural soils and reclaimed mine-spoil soils in the San Juan Basin, New Mexico: U.S. Geological Survey Professional Paper 1134-C, 39 p.
- Severson, R.C., Stewart, K.C., and Harms, T.F., 1991, Partitioning of elements between two size sediment fractions in samples from nineteen areas of the Western United States: U.S. Geological Survey Open-File Report 91-381, 18 p.

SELECTED REFERENCES--Continued

- Severson, R.C., Wilson, S.A., and McNeal, J.M., 1988, Analysis of bottom material collected at nine areas in the Western United States for the DOI irrigation drainage task group: U.S. Geological Survey Open-File Report 87-490, 24 p.
- Shacklette, H.T., and Boerngen, J.G., 1984, Element concentrations in soils and other surficial materials of the conterminous United States: U.S. Geological Survey Professional Paper 1270, 10 p.
- Skorupa, J.P., and Ohlendorf, H.M., 1991, Contaminants in drainwater and avian risk thresholds, in The economics and management of water and drainage in agriculture, Ariel Dinar and David Zilberman, eds.: Kluwer Academic Publishers, p. 345-368.
- Skorupa, J.P., Ohlendorf, H.M., and Hothem, R.L., 1990, Selenium bioaccumulation and biological risk--Some interpretive guidelines for waterbirds derived from field sampling: Conference of the Western Section and Northwest Section of the Wildlife Society, February 22-25, 1990, Reno, Nev.
- Thatcher, L.L., Janzer, V.J., and Edwards, K.W., 1977, Methods for determination of radioactive substances in water and fluvial sediments: U.S. Geological Survey Techniques of Water-Resources Investigations, book 5, chap. A5, 95 p.
- U.S. Bureau of Reclamation, 1980, Final environmental statement, Animas-La Plata Project: Colorado-New Mexico Upper Colorado Region.
- U.S. Department of Commerce, 1990, Climatological data, New Mexico: National Oceanic and Atmospheric Administration, v. 94, nos. 1-12.
- U.S. Environmental Protection Agency, 1985, Methods for measuring the acute toxicity of effluents to freshwater and marine organisms (3d ed.): U.S. Environmental Protection Agency Report 600/4-85-013, 216 p.
- ____ 1986a, Maximum contaminant levels (Subpart B of Part 141, National interim primary drinking-water regulations): U.S. Code of Federal Regulations, Title 40, Parts 100 to 149, revised as of July 1, 1986, p. 524-528.
- ____ 1986b, Secondary maximum contaminant levels (Section 143.3 of Part 143, National secondary drinking-water regulations): U.S. Code of Federal Regulations, Title 40, Parts 100 to 149, revised as of July 1, 1986, p. 587-590.
- ____ 1987, Ambient water-quality criteria for selenium--1987: U.S. Environmental Protection Agency Report 440/5-87-006, 121 p.
- U.S. Fish and Wildlife Service, 1985, Field operations manual for resource contaminant assessment: U.S. Fish and Wildlife Service, J. Hickey, ed., 333 p.

SELECTED REFERENCES--Concluded

- U.S. Fish and Wildlife Service, 1990, Patuxent Analytical Control Facility reference manual: U.S. Fish and Wildlife Service, Laurel, Md., 120 p.
- U.S. Geological Survey, 1971-75, Water resources data for New Mexico, 1970-74--Part 2. Water-quality records: U.S. Geological Survey Water-Data Reports NM-70-2 to NM-74-2 (published annually).
- _____ 1976-91, Water resources data for New Mexico, water years 1975-90: U.S. Geological Survey Water-Data Reports NM-75-1 to NM-90-1 (published annually).
- _____ 1982b, Chemical and physical quality of water and sediment, in National handbook of recommended methods for water-data acquisition: Office of Water Data Coordination, Reston, Va., chap. 5, 194 p.
- Wershaw, R.L., Fishman, M.J., Grabbe, R.R., and Lowe, L.E., 1987, eds., Methods for determination of organic substances in water and fluvial sediments: U.S. Geological Survey Techniques of Water-Resources Investigations, book 5, chap. A3, 80 p.
- White, D.H., Bean, J.R., and Longcore, J.R., 1977, Nationwide residues of mercury, lead, cadmium, arsenic, and selenium on starlings, 1973: Pesticide Monitoring Journal, v. II, no. 1, p. 35-39.
- Wilson, Brian, 1986, Water use in New Mexico: New Mexico State Engineer Office Technical Report 46, 84 p.

SUPPLEMENTAL DATA

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990

[Site number, see figs. 7 and 8 and tables 3 and 4; deg C, degrees Celsius; $\mu\text{S}/\text{cm}$, microsiemens per centimeter at 25 degrees Celsius; mg/L, milligrams per liter; $\mu\text{g}/\text{L}$, micrograms per liter; --, not determined; <, less than; >, greater than]

Site number	Date	Time	Discharge, instantaneous (cubic feet per second) (00061)	Temperature water (deg C) (00010)	Specific conductance ($\mu\text{S}/\text{cm}$) (00095)	pH (standard units) (00400)	Oxygen, dissolved (mg/L) (00300)	Solids, residue at 180 deg C, dissolved as CaCO_3 (70300)	Hardness, total as CaCO_3 (00900)	Alkalinity, lab as CaCO_3 (90410)	Calcium, dissolved as Ca (mg/L) (00915)	Magnesium, dissolved as Mg (mg/L) (00925)
I-1	04-14-90	1430	0.01	16.5	1,490	8.5	8.7	2,060	910	110	290	46
	08-04-90	1400	0.27	22.5	560	8.5	10.3	370	220	181	63	14
	12-03-90	1000	0.01	3.5	1,790	8.0	--	2,230	480	357	140	32
	04-14-90	1700	0.17	16.5	3,000	8.0	13.0	2,290	840	192	280	35
I-2	08-04-90	1700	0.07	27.0	3,130	8.9	--	2,390	880	75	290	39
I-3	12-03-90	1300	0.25	5.5	2,940	7.8	14.0	2,250	860	244	290	33
	04-16-90	1600	--	17.0	1,550	8.8	17.0	1,080	390	105	99	35
	08-06-90	1000	--	23.0	1,400	7.7	6.4	920	380	147	95	35
	11-17-90	0900	0.56	7.5	1,650	7.8	9.1	1,170	520	174	150	36
I-4	04-16-90	1500	--	24.0	3,160	8.4	6.5	2,420	560	160	170	32
I-6B	08-02-90	1600	1.4	32.0	3,480	8.2	5.6	2,540	810	125	260	38
	11-17-90	1100	--	13.0	2,490	8.3	8.5	1,880	560	181	180	26
	04-18-90	0930	--	13.0	2,260	7.9	6.5	1,490	610	79	170	46
	08-05-90	1400	--	26.0	4,620	8.7	7.9	3,690	1,600	45	450	110
I-7	12-03-90	1400	--	5.0	520	9.0	16.6	334	170	74	50	12
I-7	08-01-90	0900	0.38	16.0	3,450	8.2	8.3	3,010	980	83	350	81
I-8	04-16-90	1100	1.4	11.5	3,920	8.4	9.1	2,680	1,200	226	270	74
I-8	11-16-90	1700	1.3	9.0	3,910	7.4	9.4	3,080	1,000	289	280	72
I-10	04-18-90	1200	--	13.5	650	8.2	6.8	380	210	318	54	18
	07-07-90	1300	--	--	--	--	--	896	130	570	32	11

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Time	Discharge, instantaneous (cubic feet per second) (00061)	Temperature water (deg C) (00010)	Specific conductance (µS/cm) (00095)	pH (stand-ard units) (00400)	Oxygen, dissolved (mg/L) (00300)	Solids, residue at 180 deg C, dissolved (mg/L) (70300)	Hardness, total as CaCO ₃ (00900)	Alkalinity, lab as CaCO ₃ (90410)	Calcium, dissolved as Ca) (00915)	Magnesium, dissolved (mg/L as Mg) (00925)
I-10	12-02-90	1600	--	3.5	440	8.4	11.9	263	180	162	51	12
I-11	08-21-90	1000	--	21.0	240	9.7	8.0	146	65	66	16	6.1
I-12	08-21-90	1300	--	22.0	800	7.6	2.8	532	190	154	49	16
I-13	04-15-90	1600	--	22.0	355	11.0	11.6	197	35	87	9.1	3.0
	08-05-90	1200	--	18.0	840	9.6	7.8	574	29	284	7.0	2.9
I-14	12-02-90	1500	--	4.0	340	9.0	13.4	195	75	109	20	6.2
I-15	08-21-90	1500	--	28.5	580	9.4	14.0	405	57	286	12	6.5
I-17	09-14-90	1300	--	25.5	470	8.4	6.8	287	94	90	27	6.5
	04-14-90	1030	--	11.5	1,100	8.5	--	718	240	282	82	9.3
	08-03-90	1000	--	17.0	680	8.2	5.6	252	130	128	41	6.9
I-17	12-04-90	1000	--	9.0	1,030	7.1	--	748	260	382	87	10
I-18	12-04-90	1030	--	2.0	>20,000	7.8	--	40,800	1,200	1,330	400	60
I-20	04-13-90	1430	0.29	14.0	--	8.2	18.0	996	290	240	75	25
	08-04-90	1000	0.27	21.5	1,980	8.3	--	1,530	600	163	190	31
	12-03-90	1700	0.23	8.0	2,860	7.4	11.8	2,330	1,100	252	340	49
I-21	04-17-90	1700	0.16	18.5	6,740	8.2	12.3	4,510	490	419	97	60
	08-01-90	1200	0.92	22.5	1,900	7.9	8.5	1,240	320	196	94	20
	11-16-90	1600	0.26	13.0	5,890	8.1	12.6	4,640	760	392	210	58
I-22	04-17-90	1100	0.14	14.0	2,800	7.7	8.3	2,370	1,300	281	270	140
	08-01-90	1400	0.68	21.5	2,000	7.5	6.0	1,520	970	214	240	90

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Time	Dis-charge, instan-taneous (cubic feet per second) (00061)	Temper-ature (deg C) (00010)	Spe-cific con-duct-ance ($\mu\text{S}/\text{cm}$) (00095)	pH (stand-ard units) (00400)	Oxygen, dis-solved (mg/L) (00300)	Solids, residue at 180 deg C, dis-solved (mg/L) (70300)	Hard-ness, total (mg/L as CaCO_3) (00900)	Alka-linity lab (mg/L as CaCO_3) (90410)	Calcium, dis-solved (mg/L as Ca) (00915)	Magne-sium, dis-solved (mg/L as Mg) (00925)
I-22	11-16-90	1000	0.08	8.5	2,670	7.5	7.2	2,210	1,400	171	310	140
I-22B	09-14-90	1100	--	18.0	1,550	7.4	5.4	1,260	700	234	170	67
I-23	06-20-90	1100	--	23.5	850	7.7	4.8	560	350	179	100	24
	08-02-90	1400	--	24.0	1,060	7.7	4.5	728	420	139	120	29
	12-02-90	1400	--	5.5	2,140	7.2	13.0	1,710	940	289	240	82
I-24	04-17-90	1430	0.08	18.0	1,160	8.4	13.5	756	440	227	110	40
	08-02-90	1100	2.0	19.5	915	8.1	7.3	590	390	155	100	33
	12-02-90	1030	0.09	3.0	1,170	8.2	11.6	802	480	224	130	38
R-1	04-26-90	1300	260	11.0	310	8.4	10.0	171	110	90	33	6.5
	07-30-90	0900	190	11.5	300	8.5	9.1	175	120	92	36	6.9
	11-13-90	1000	385	6.0	300	8.3	11.0	180	110	91	34	6.6
R-2	04-27-90	0930	450	9.0	520	8.3	9.7	322	150	106	49	7.8
	07-30-90	1200	300	19.5	460	8.5	8.2	283	170	109	53	8.3
	11-13-90	1400	584	9.5	430	7.4	9.7	277	150	102	47	7.9
R-3	04-27-90	1400	210	14.5	570	8.4	8.4	341	230	121	74	11
	07-30-90	1400	10	26.5	695	8.4	7.5	426	280	150	91	14
	11-14-90	0800	358	5.5	610	7.3	11.2	384	250	121	80	12
R-4	04-30-90	1000	--	10.5	615	8.4	9.0	340	190	115	61	9.5
	08-03-90	1700	--	25.5	548	8.6	7.3	342	190	119	61	9.6
R-5	04-28-90	1000	5.4	10.5	4,470	8.2	8.8	3,450	1,300	234	330	120

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Time	Dis-charge, instantaneous (cubic feet per second) (00061)	Temperature (deg C) (00010)	Specific conductance (µS/cm) (00095)	pH (standard units) (00400)	Oxygen, dissolved (mg/L) (00300)	Solids, residue at 180 deg C, dissolved (mg/L) (70300)	Hardness, total (mg/L as CaCO ₃) (00900)	Alkalinity, lab (mg/L as CaCO ₃) (90410)	Calcium, dissolved (mg/L as Ca) (00915)	Magnesium, dissolved (mg/L as Mg) (00925)
R-5	08-02-90	0900	0.16	18.5	1,550	8.1	7.5	958	430	136	120	31
	11-16-90	1300	0.87	10.5	4,160	7.2	9.5	3,370	1,300	114	330	110
	04-27-90	1700	630	16.0	600	8.4	7.8	377	200	120	65	10
	07-30-90	1630	370	27.0	580	9.0	9.5	362	210	128	65	11
	11-14-90	1100	1,100	8.0	580	7.4	10.1	379	210	157	67	11
R-7	04-29-90	1430	0.17	15.0	5,040	8.4	15.8	3,840	1,200	176	220	150
	11-16-90	1200	0.06	4.5	7,230	6.9	9.6	5,990	2000	335	410	230
	04-29-90	1600	--	12.0	652	8.5	8.9	379	220	124	69	11
	08-03-90	1500	--	26.5	685	8.8	9.2	444	260	151	80	14
	04-28-90	2000	12	15.5	1,440	8.4	7.4	918	170	149	53	9.7
R-10	07-31-90	1500	2.7	31.5	1,650	8.8	7.9	1,210	470	109	99	53
	11-15-90	0900	5.2	4.5	1,730	7.5	11.1	1,250	450	143	110	42
	04-29-90	1730	--	11.0	709	8.5	9.0	403	220	125	70	12
	08-02-90	1300	--	25.0	780	8.6	8.1	548	290	150	85	18
	12-02-90	1300	--	3.0	680	7.6	11.6	434	250	132	76	14
R-11	04-28-90	1700	710	16.5	685	8.3	7.8	435	220	128	69	12
	07-31-90	1000	190	21.0	830	8.6	8.1	518	310	133	91	21
	11-15-90	1300	1,090	9.5	630	7.5	9.9	403	240	128	73	13

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Sodium, dis-solved (mg/L as Na) (00930)	Sodium ad-sorp-tion ratio (00931)	Sodium (percent) (00932)	Potas-sium, dis-solved (mg/L as K) (00935)	Bromide, dis-solved (mg/L as Br) (71870)	Chlo-ride, dis-solved (mg/L as Cl) (00940)	Sulfate, dis-solved (mg/L as SO ₄) (00945)
I-1	04-14-90	240	3	36	3.1	0.090	18	1,200
	08-04-90	48	1	32	4.1	0.060	6.7	110
	12-03-90	210	4	48	7.1	0.44	71	410
I-2	04-14-90	370	6	49	1.5	1.7	160	1,000
	08-04-90	390	6	49	0.70	1.5	200	1,200
I-3	12-03-90	340	5	46	1.6	1.5	130	970
	04-16-90	180	4	50	2.2	0.50	83	500
	08-06-90	170	4	49	7.9	<0.010	84	440
	11-17-90	160	3	40	2.5	0.89	86	490
	04-16-90	480	9	65	4.5	0.91	100	1,200
I-6B	08-02-90	500	8	57	5.2	1.3	140	1,600
	11-17-90	360	7	58	3.9	1.4	110	960
	04-18-90	220	4	44	3.9	1.7	180	650
	08-05-90	450	5	38	9.1	4.7	560	1,800
	12-03-90	37	1	31	6.7	0.10	22	140
I-7	08-01-90	380	5	41	1.1	0.55	160	1,400
I-8	04-16-90	600	8	57	2.0	1.4	180	1,700
I-8	11-16-90	550	8	55	2.3	1.7	220	1,300
I-10	04-18-90	58	2	36	9.3	--	13	7.6
	07-07-90	210	8	77	9.9	0.090	26	19
I-11	12-02-90	25	0.8	23	6.0	0.020	8.9	55
	08-21-90	21	1	41	1.6	<0.010	2.8	47
I-12	08-21-90	88	3	48	17	0.050	37	200
	04-15-90	52	4	75	1.8	--	1.1	52
I-13	08-05-90	180	14	92	5.1	0.10	17	100
	12-02-90	44	2	54	4.0	<0.010	12	51
I-14	08-21-90	120	7	80	7.4	0.030	6.2	14
I-15	09-14-90	67	3	60	1.8	0.050	5.5	130
I-17	04-14-90	170	5	60	1.2	<0.010	7.6	320
	08-03-90	31	1	34	2.1	0.090	4.5	66

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Sodium, dis-solved (mg/L as Na) (00930)		Sodium ad-sorp-tion ratio (00931)		Sodium (percent) (00932)		Potas-sium, dis-solved (mg/L as K) (00935)		Bromide, dis-solved (mg/L as Br) (71870)		Chlo-ride, dis-solved (mg/L as Cl) (00940)		Sulfate, dis-solved (mg/L as SO ₄) (00945)	
I-17	12-04-90	160	4	57	1.7	0.17	12	160							
I-18	12-04-90	11,000	140	95	39	2.3	470	26,000							
I-20	04-13-90	200	5	59	7.7	0.20	65	390							
	08-04-90	240	4	46	3.2	0.050	12	810							
	12-03-90	290	4	37	4.2	0.12	27	1,600							
I-21	04-17-90	1,200	24	84	4.0	0.26	160	2,700							
	08-01-90	290	7	66	3.7	0.060	50	630							
	11-16-90	1,200	19	77	4.3	0.27	180	2,600							
I-22	04-17-90	190	2	25	4.5	0.050	31	1,300							
	08-01-90	120	2	21	6.4	0.050	19	910							
I-22B	11-16-90	160	2	20	5.7	0.070	28	1,400							
I-23	09-14-90	95	2	23	8.0	0.030	20	660							
	06-20-90	42	1	21	3.8	0.020	11	250							
	08-02-90	72	2	27	5.1	0.040	24	340							
	12-02-90	150	2	26	5.8	0.070	53	900							
I-24	04-17-90	87	2	30	0.80	0.030	26	350							
	08-02-90	53	1	23	1.4	0.040	18	230							
	12-02-90	75	1	25	1.8	0.070	28	310							
R-1	04-26-90	18	0.7	26	1.5	--	3.1	57							
	07-30-90	19	0.8	25	2.0	0.010	3.4	58							
R-2	11-13-90	18	0.7	25	2.1	<0.010	3.2	49							
	04-27-90	43	2	37	2.0	--	4.3	130							
	07-30-90	35	1	31	2.2	0.020	4.7	120							
	11-13-90	33	1	32	2.1	<0.010	3.7	98							
R-3	04-27-90	23	0.7	18	2.3	<0.010	11	120							
	07-30-90	40	1	23	3.3	0.050	23	170							
	11-14-90	29	0.8	20	2.6	0.040	22	150							
R-4	04-30-90	35	1	28	2.1	<0.010	10	130							
	08-03-90	41	1	31	2.5	0.020	11	150							
R-5	04-28-90	580	7	49	4.0	0.69	170	2,000							

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Sodium, dissolved (mg/L as Na) (00930)	Sodium adsorption ratio (00931)	Sodium (percent) (00932)	Potassium, dissolved (mg/L as K) (00935)	Bromide, dissolved (mg/L as Br) (71870)	Chloride, dissolved (mg/L as Cl) (00940)	Sulfate, dissolved (mg/L as SO ₄) (00945)
R-5	08-02-90	180	4	48	2.9	0.20	120	410
	11-16-90	530	6	47	4.3	0.98	230	1,900
	04-27-90	40	1	30	2.4	<0.010	9.3	140
	07-30-90	45	1	32	2.6	0.030	12	160
R-6	11-14-90	40	1	29	2.6	0.030	15	130
	04-29-90	770	10	59	5.0	0.30	280	2,200
	11-16-90	1,100	11	55	8.0	0.66	480	2,800
	04-29-90	39	1	28	2.3	<0.010	8.0	140
R-8	08-03-90	53	1	31	3.2	0.030	16	190
	04-28-90	230	8	74	5.3	0.030	41	500
R-9	07-31-90	190	4	47	7.9	0.12	58	700
	11-15-90	220	5	51	6.6	0.25	55	670
	04-29-90	44	1	30	3.6	<0.010	10	160
	08-02-90	60	2	31	3.3	0.030	19	230
R-10	12-02-90	50	1	30	2.8	0.040	19	180
	04-28-90	51	1	33	2.7	<0.010	15	200
	07-31-90	63	2	30	3.2	0.030	20	260
R-11	11-15-90	44	1	29	2.5	0.030	15	170

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Nitro- gen,		Boron,		Uranium	
		NO ₂ +NO ₃ , dis- solved (mg/L as N) (00631)	solved (µg/L as B) (01020)	dis- solved (µg/L as U) (22703)	natural, dis- solved (µg/L as U) (28011)	total, natural, total (µg/L as U) (28011)	
I-1	04-14-90	3.70	220	15	--	--	
	08-04-90	0.200	110	--	<1.0	--	
I-2	12-03-90	3.80	320	--	12	--	
	04-14-90	6.00	340	10	--	--	
	08-04-90	5.10	390	--	10	--	
I-3	12-03-90	19.0	330	--	11	--	
	04-16-90	<0.100	390	13	--	--	
	08-06-90	<0.100	350	--	5.3	--	
	11-17-90	1.90	350	--	4.8	--	
I-4	04-16-90	8.10	440	21	--	--	
I-6B	08-02-90	7.10	540	--	18	--	
	11-17-90	8.20	300	--	17	--	
	04-18-90	<0.100	180	5.9	--	--	
	08-05-90	<0.100	390	--	2.2	--	
	12-03-90	<0.100	60	--	2.1	--	
	08-01-90	16.0	420	--	82	--	
I-7	04-16-90	16.0	380	73	--	--	
I-8	11-16-90	17.0	370	--	87	--	
I-10	04-18-90	<0.100	110	<1.0	--	--	
	07-07-90	<0.100	220	--	3.7	--	
	12-02-90	<0.100	50	--	<1.0	--	
I-11	08-21-90	<0.100	30	--	<1.0	--	
I-12	08-21-90	<0.100	250	--	1.4	--	
I-13	04-15-90	<0.100	80	1.3	--	--	
	08-05-90	<0.100	300	--	--	--	
	12-02-90	0.200	60	--	<1.0	--	
I-14	08-21-90	<0.100	70	--	2.8	--	
I-15	09-14-90	0.300	30	--	2.3	--	
I-17	04-14-90	3.10	140	6.9	--	--	
	08-03-90	0.300	30	--	<1.0	--	

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Nitrogen, NO ₂ + NO ₃ , dis-solved (mg/L as N) (00631)		Boron, natural, dis-solved (µg/L as B) (01020)		Uranium, natural, dis-solved (µg/L as U) (22703)		Uranium, natural, total (µg/L as U) (28011)	
I-17	12-04-90	8.10	120	--	5.3				
I-18	12-04-90	<0.050	2,000	--	360				
I-20	04-13-90	<0.100	370	6.8	--				
	08-04-90	3.20	200	--	8.0				
	12-03-90	4.50	260	--	13				
I-21	04-17-90	<0.100	380	20	--				
	08-01-90	<0.100	110	--	6.5				
	11-16-90	0.100	400	--	27				
I-22	04-17-90	0.300	390	27	--				
	08-01-90	0.600	270	--	15				
I-22B	11-16-90	1.50	380	--	14				
I-23	09-14-90	0.600	210	--	7.0				
	06-20-90	<0.100	90	--	2.2				
	08-02-90	<0.100	110	--	5.1				
	12-02-90	<0.100	170	--	8.6				
I-24	04-17-90	0.300	130	7.3	--				
	08-02-90	<0.100	100	--	6.7				
	12-02-90	1.00	120	--	13				
R-1	04-26-90	<0.100	20	1.1	--				
	07-30-90	<0.100	20	--	1.3				

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Nitro- gen, NO ₂ +NO ₃ , dis- solved (mg/L as N) (00631)	Boron, dis- solved (µg/L as B) (01020)	Uranium	
				dis- solved (µg/L as U) (22703)	natural, total (µg/L as U) (28011)
R-2	11-13-90	0.200	20	--	<1.0
	04-27-90	<0.100	30	1.2	--
	07-30-90	<0.100	40	--	<1.0
R-3	11-13-90	0.200	40	--	<1.0
	04-27-90	0.200	50	2.1	--
R-4	07-30-90	<0.100	80	--	2.0
	11-14-90	0.200	70	--	1.6
	04-30-90	<0.100	40	<1.0	--
R-5	08-03-90	0.200	50	--	<1.0
	04-28-90	<0.100	190	11	--

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Nitrogen, $\text{No}_2 + \text{No}_3$ dissolved (mg/L as N) (00631)	Boron, natural, dissolved ($\mu\text{g/L}$ as B) (01020)		Uranium, natural, dissolved ($\mu\text{g/L}$ as U) (22703)		Uranium, natural, total ($\mu\text{g/L}$ as U) (28011)	
			(01020)	(22703)	(22703)	(28011)		
R-5	08-02-90	<0.100	140	--	--	3.6		
	11-16-90	0.140	170	--	--	7.2		
R-6	04-27-90	0.300	50	2.2	--	--		
	07-30-90	<0.100	50	--	--	1.8		
	11-14-90	0.300	50	--	--	2.2		
R-7	04-29-90	1.00	320	13	--	--		
	11-16-90	6.30	420	--	21	--		
R-8	04-29-90	0.300	50	2.1	--	--		
	08-03-90	<0.100	70	--	--	4.3		
R-9	04-28-90	2.80	190	--	--	--		
	07-31-90	0.900	480	--	--	6.0		
R-10	11-15-90	2.90	380	--	--	8.9		
	04-29-90	0.300	50	1.3	--	--		
	08-02-90	<0.100	60	--	--	5.5		
	12-02-90	0.500	60	--	--	2.6		
R-11	04-28-90	0.400	60	2.3	--	--		
	07-31-90	<0.100	70	--	--	3.8		
	11-15-90	0.300	60	--	--	2.9		

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall, 1990--Continued

Site number	Date	Time	Discharge, instantaneous (cubic feet per second) (00061)	Temperature water (deg C) (00010)	Specific conductance (µS/cm) (00095)	pH standard units) (00400)	Oxygen, dissolved (mg/L) (00300)	Quality assurance/quality control samples	
I-2	12-03-90	1300	0.25	5.5	2,940	7.8	14.0		
	12-03-90	1300	0.25	5.5	2,940	7.8	14.0		
I-3	08-06-90	1000	--	23.0	1,400	7.7	6.4		
	08-06-90	1010	--	23.0	1,400	7.7	6.4		
I-4	11-17-90	1100	--	13.0	2,490	8.3	8.5		
	11-17-90	1110	--	13.0	2,490	8.5	8.5		
I-6B	04-18-90	0930	--	13.0	2,260	7.9	6.5		
	04-18-90	0940	--	13.0	2,260	7.9	6.5		
I-7	08-01-90	0900	0.38	16.0	3,450	8.2	8.3		
	08-01-90	0910	0.38	16.0	3,450	8.2	8.3		
I-17	08-03-90	1000	--	17.0	680	8.2	5.6		
	08-03-90	1000	--	17.0	--	8.2	5.6		
I-22	11-16-90	1000	0.08	8.5	2,670	7.5	7.2		
	11-16-90	1010	0.08	8.5	2,670	7.5	7.2		
R-2	04-27-90	0930	450	9.0	520	8.3	9.7		
	04-27-90	0930	450	9.0	520	8.3	9.7		
R-4	04-30-90	1000	--	10.5	615	8.4	9.0		
	04-30-90	1005	--	10.5	615	8.4	9.0		
Trip blank	08-05-90	1500	--	--	--	--	--		
Equipment blank	08-05-90	1510	--	--	--	--	--		
Trip blank	12-03-90	1430	--	--	--	--	--		
Equipment blank	12-03-90	1440	--	--	--	--	--		

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall, 1990--Continued

Site number	Date	Solids,		Hardness, total (mg/L as CaCO ₃) (00900)	Alkalinity, (mg/L as CaCO ₃) (90410)	Calcium, dissolved (mg/L as Ca) (00915)	Magnesium, dissolved (mg/L as Mg) (00925)	Sodium, dissolved (mg/L as Na) (00930)
		residue at 180 deg C, dissolved (mg/L) (70300)	lab dissolved (mg/L)					
I-2	12-03-90	2,250	860	244	290	33	340	
	12-03-90	2,220	860	215	290	34	350	
I-3	08-06-90	920	380	147	95	35	170	
	08-06-90	936	370	147	94	34	160	
I-4	11-17-90	1,880	560	181	180	26	360	
	11-17-90	1,850	560	277	180	26	370	
I-6B	04-18-90	1,490	610	79	170	46	220	
	04-18-90	1,530	610	80	170	46	220	
I-7	08-01-90	2,680	1,200	226	350	81	380	
	08-01-90	2,780	1,200	210	350	82	400	
I-17	08-03-90	252	130	128	41	6.9	31	
	08-03-90	240	130	128	42	7.1	32	
I-22	11-16-90	2,210	1,400	171	310	140	160	
	11-16-90	2,350	1,400	234	310	140	160	
R-2	04-27-90	322	150	106	49	7.8	43	
	04-27-90	329	150	110	49	7.7	43	
R-4	04-30-90	340	190	115	61	9.5	35	
	04-30-90	324	190	118	61	9.5	35	
Trip blank	08-05-90	<1	0	<1.0	0.03	0.08	<0.20	
Equipment blank	08-05-90	<1	1	<1.0	0.11	0.07	<0.20	
Trip blank	12-03-90	9	3	4.1	0.80	0.17	<0.20	
Equipment blank	12-03-90	2	3	4.0	0.87	0.15	<0.20	

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Sodium ad-sorption ratio (00931) (00932)	Sodium percent as K) (00935)	Potassium, dissolved (mg/L) (71870)	Bromide, dissolved (mg/L) (00940)	Chloride, dissolved (mg/L) (00945)	Sulfate, dissolved (mg/L) (00945)
Quality assurance/quality control samples							
I-2	12-03-90	5	46	1.6	1.5	130	970
	12-03-90	5	47	1.6	1.6	140	1,100
I-3	08-06-90	4	49	7.9	<0.010	84	440
	08-06-90	4	48	7.9	0.55	84	450
I-4	11-17-90	7	58	3.9	1.4	110	960
	11-17-90	7	59	4.1	1.1	84	960
I-6B	04-18-90	4	44	3.9	1.7	180	650
	04-18-90	4	44	4.0	3.4	220	750
I-7	08-01-90	5	41	1.1	0.55	160	1,400
	08-01-90	5	42	1.1	1.3	160	1,400
I-17	08-03-90	1	34	2.1	0.090	4.5	66
	08-03-90	1	34	2.2	0.060	4.5	68
I-22	11-16-90	2	20	5.7	0.070	28	1,400
	11-16-90	2	20	5.3	0.070	31	1,300
R-2	04-27-90	2	37	2.0	--	4.3	130
	04-27-90	2	37	1.9	--	5.2	140
R-4	04-30-90	1	28	2.1	<0.010	10	130
	04-30-90	1	28	2.2	<0.010	9.8	140
Trip blank	08-05-90	--	--	<0.10	<0.010	0.20	<1.0
Equipment blank	08-05-90	--	--	<0.10	<0.010	<0.10	<1.0
Trip blank	12-03-90	--	--	0.20	0.010	<0.10	<1.0
Equipment blank	12-03-90	--	--	0.10	0.020	<0.10	<1.0

Table 20.--Streamflow, selected properties, and concentrations of selected constituents in water samples: spring, summer, and fall 1990--Concluded

Site number	Date	Nitrogen		Boron		Uranium	
		gen, No ₂ +No ₃ solved (mg/L as N) (00631)	dis- solved (µg/L as B) (01020)	dis- solved (µg/L as U) (22703)	dis- solved (µg/L as U) (28011)		
I-2	12-03-90	19.0	330	--	11		
	12-03-90	19.0	330	--	17		
I-3	08-06-90	<0.100	350	--	5.3		
	08-06-90	<0.100	340	--	3.7		
I-4	11-17-90	8.20	300	--	17		
	11-17-90	7.90	310	--	8.5		
I-6B	04-18-90	<0.100	180	5.9	--		
	04-18-90	<0.100	180	6.3	--		
I-7	08-01-90	16.0	420	--	82		
	08-01-90	16.0	410	--	93		
I-17	08-03-90	0.300	30	--	<1.0		
	08-03-90	0.300	30	--	<1.0		
I-22	11-16-90	1.50	380	--	14		
	11-16-90	1.20	380	--	20		
R-2	04-27-90	<0.100	30	1.2	--		
	04-27-90	<0.100	40	<1.0	--		
R-4	04-30-90	<0.100	40	<1.0	--		
	04-30-90	<0.100	50	80	--		
Trip blank	08-05-90	<0.100	<10	--	<1.0		
Equipment blank	08-05-90	<0.100	<10	--	<1.0		
Trip blank	12-03-90	<0.100	160	--	<1.0		
Equipment blank	12-03-90	<0.100	160	--	<1.0		

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990

[Site number, see figs. 7 and 8 and tables 3 and 4;
 $\mu\text{g/L}$, micrograms per liter; --, not measured; <, less than]

Site number	Date	Time	Dis-charge, instantaneous (cubic feet per second) (00061)	Arsenic, dis-solved ($\mu\text{g/L}$ as As) (01000)	Cadmium, dis-solved ($\mu\text{g/L}$ as Cd) (01025)	Chromium, dis-solved ($\mu\text{g/L}$ as Cr) (01030)	Copper, dis-solved ($\mu\text{g/L}$ as Cu) (01040)
I-1	04-14-90	1430	0.01	<1	<1.0	2	1
	08-04-90	1400	0.27	2	<1.0	<1	10
	12-03-90	1000	0.01	<1	<1.0	<1	1
I-2	04-14-90	1700	0.17	<1	<1.0	2	31
	08-04-90	1700	0.07	1	<1.0	<1	1
I-3	12-03-90	1300	0.25	<1	<1.0	<1	1
	04-16-90	1600	--	<1	2.0	<1	3
	08-06-90	1000	--	3	<1.0	<1	1
	11-17-90	0900	0.56	1	<1.0	<1	2
I-4	04-16-90	1500	--	<1	<1.0	2	2
	08-02-90	1600	1.4	1	<1.0	1	4
I-6B	11-17-90	1100	--	<1	<1.0	1	3
	04-18-90	0930	--	<1	<1.0	2	<1
	08-05-90	1400	--	3	<1.0	<1	1
	12-03-90	1400	--	<1	<1.0	<1	2
I-7	08-01-90	0900	0.38	<1	<1.0	<1	1
I-8	04-16-90	1100	1.4	<1	<1.0	2	1
I-8	11-16-90	1700	1.3	<1	<1.0	<1	2
I-10	04-18-90	1200	--	7	2.0	2	<1
	07-07-90	1300	--	48	<1.0	1	32
I-11	12-02-90	1600	--	5	<1.0	<1	1
	08-21-90	1000	--	2	<1.0	<1	2
	08-21-90	1300	--	5	1.0	<1	12
I-12	04-15-90	1600	--	3	<1.0	2	4
	08-05-90	1200	--	17	<1.0	<1	13
I-13	12-02-90	1500	--	1	<1.0	<1	3
	08-21-90	1500	--	4	1.0	<1	7
I-14	09-14-90	1300	--	<1	<1.0	<1	6
I-15	04-14-90	1030	--	<1	<1.0	1	3
	08-03-90	1000	--	1	<1.0	<1	3

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Time	Dis-charge, instantaneous (cubic feet per second) (00061)	Arsenic, dis-solved ($\mu\text{g/L}$ as As) (01000)	Cadmium, dis-solved ($\mu\text{g/L}$ as Cd) (01025)	Chro-mium, dis-solved ($\mu\text{g/L}$ as Cr) (01030)	Copper, dis-solved ($\mu\text{g/L}$ as Cu) (01040)
I-17	12-04-90	1000	--	<1	<1.0	<1	3
I-18	12-04-90	1030	--	2	<10	<5	<10
I-20	04-13-90	1430	0.29	1	<1.0	1	1
	08-04-90	1000	0.27	<1	<1.0	<1	1
	12-03-90	1700	0.23	<1	<1.0	<1	2
I-21	04-17-90	1700	0.16	1	<1.0	2	<1
	08-01-90	1200	0.92	2	<1.0	<1	2
	11-16-90	1600	0.26	1	<1.0	<1	1
I-22	04-17-90	1100	0.14	<1	<1.0	1	1
	08-01-90	1400	0.68	1	<1.0	<1	1
	11-16-90	1000	0.08	<1	<1.0	<1	1
I-22B	09-14-90	1100	--	<1	<1.0	<1	3
I-23	06-20-90	--	--	1	<1.0	1	1
	08-02-90	1400	--	1	<1.0	<1	2
	12-02-90	1400	--	<1	<1.0	<1	5
I-24	04-17-90	1430	0.08	1	<1.0	1	1
	08-02-90	1100	2.0	1	<1.0	<1	2
	12-02-90	1030	0.09	<1	<1.0	<1	2
R-1	04-26-90	1300	260	<1	<1.0	1	1
	07-30-90	0900	190	1	<1.0	<1	2
	11-13-90	1000	385	<1	<1.0	<1	2
R-2	04-27-90	0930	450	<1	<1.0	1	8
	07-30-90	1200	300	1	<1.0	<1	2
	11-13-90	1400	584	<1	<1.0	<1	1
R-3	04-27-90	1400	210	<1	1.0	1	1
	07-30-90	1400	10	<1	<1.0	<1	4
R-4	04-30-90	1000	--	<1	<1.0	1	1
	08-03-90	1700	--	1	<1.0	<1	2
	11-14-90	0800	358	<1	<1.0	<1	2
R-5	04-28-90	1000	5.4	<1	<1.0	3	1

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Time	Dis-charge, instantaneous (cubic feet per second) (00061)	Arsenic, dissolved ($\mu\text{g/L}$ as As) (01000)	Cadmium, dissolved ($\mu\text{g/L}$ as Cd) (01025)	Chromium, dissolved ($\mu\text{g/L}$ as Cr) (01030)	Copper, dissolved ($\mu\text{g/L}$ as Cu) (01040)
R-5	08-02-90	0900	0.16	1	<1.0	<1	2
	11-16-90	1300	0.87	<1	<1.0	<1	1
R-6	04-27-90	1700	630	1	<1.0	2	1
	07-30-90	1630	370	1	<1.0	<1	2
	11-14-90	1100	1,100	<1	<1.0	<1	2
R-7	04-29-90	1430	0.17	<1	<1.0	2	2
	11-16-90	1200	0.06	<1	<1.0	1	<1
R-8	04-29-90	1600	--	1	1.0	1	1
	08-03-90	1500	--	1	<1.0	<1	2
R-9	04-28-90	2000	12	1	1.0	1	12
	07-31-90	1500	2.7	1	<1.0	<1	5
R-10	11-15-90	0900	5.2	1	<1.0	<1	5
	04-29-90	1730	--	1	<1.0	2	3
	08-02-90	1300	--	1	<1.0	<1	4
	12-02-90	1300	--	<1	<1.0	<1	2
R-11	04-28-90	1700	710	1	1.0	<1	2
	07-31-90	1000	190	1	<1.0	<1	2
	11-15-90	1300	1,090	<1	<1.0	<1	3

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Lead, dissolved ($\mu\text{g/L}$ as Pb) (01049)	Mercury, dissolved ($\mu\text{g/L}$ as Hg) (71890)	Molybdenum, dissolved ($\mu\text{g/L}$ as Mo) (01060)	Selenium, dissolved ($\mu\text{g/L}$ as Se) (01145)	Vanadium, dissolved ($\mu\text{g/L}$ as V) (01085)	Zinc, dissolved ($\mu\text{g/L}$ as Zn) (01090)
I-1	04-14-90	<1	<0.1	1	7	2	<10
	08-04-90	<1	0.1	<1	<1	5	<3
	12-03-90	<1	<0.1	<1	3	3	3
I-2	04-14-90	1	<0.1	4	25	6	<10
	08-04-90	<1	0.2	<1	16	7	<10
I-3	12-03-90	<1	<0.1	<1	35	5	<10
	04-16-90	<1	<0.1	3	5	3	10
	08-06-90	<1	0.1	<1	2	5	16
	11-17-90	<1	<0.1	3	5	2	5
I-4	04-16-90	<1	<0.1	8	8	--	<10
	08-02-90	<1	0.1	11	12	6	20
I-6B	11-17-90	<1	<0.1	1	15	4	<10
	04-18-90	<1	<0.1	2	2	7	<10
	08-05-90	<1	0.2	<1	<1	27	10
	12-03-90	<1	<0.1	<1	<1	2	<3
I-7	08-01-90	<1	0.1	9	42	6	10
I-8	04-16-90	<1	<0.1	6	33	7	<10
I-8	11-16-90	<1	<0.1	6	67	8	<10
I-10	04-18-90	<1	<0.1	<1	<1	7	<3
	07-07-90	<1	<0.1	11	<1	14	3
I-11	12-02-90	<1	<0.1	2	<1	5	<3
	08-21-90	1	<0.1	<1	<1	4	<3
I-12	08-21-90	<1	<0.1	<1	1	6	7
I-13	04-15-90	<1	<0.1	3	<1	--	7
	08-05-90	<1	0.2	8	<1	12	6
I-14	12-02-90	12	<0.1	2	<1	6	<3
	08-21-90	<1	<0.1	<1	<1	9	<3
I-15	09-14-90	<1	<0.1	<1	1	2	<3
I-17	04-14-90	<1	<0.1	1	<1	2	12
	08-03-90	<1	0.2	<1	<1	3	4

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Lead, dissolved ($\mu\text{g/L}$ as Pb) (01049)	Mercury, dissolved ($\mu\text{g/L}$ as Hg) (71890)	Molybdenum, dissolved ($\mu\text{g/L}$ as Mo) (01060)	Selenium, dissolved ($\mu\text{g/L}$ as Se) (01145)	Vanadium, dissolved ($\mu\text{g/L}$ as V) (01085)	Zinc, dissolved ($\mu\text{g/L}$ as Zn) (01090)
I-17	12-04-90	<1	<0.1	5	1	1	<3
I-18	12-04-90	<10	<0.1	15	<1	16	<10
I-20	04-13-90	<1	<0.1	2	2	4	<3
	08-04-90	<1	0.2	<1	3	1	5
	12-03-90	<1	<0.1	<1	6	1	10
I-21	04-17-90	<1	<0.1	8	<1	--	<10
	08-01-90	<1	0.2	1	<1	3	15
	11-16-90	<1	0.1	9	<1	6	10
I-22	04-17-90	<1	<0.1	6	21	2	<10
	08-01-90	<1	0.1	2	11	2	10
	11-16-90	<1	<0.1	6	12	2	10
I-22B	09-14-90	1	<0.1	<1	9	4	8
I-23	06-20-90	<1	<0.1	2	<1	1	5
	08-02-90	<1	0.2	1	<1	1	13
	12-02-90	<1	<0.1	2	<1	1	<10
I-24	04-17-90	<1	<0.1	4	2	1	7
	08-02-90	<1	0.2	2	2	<1	8
	12-02-90	<1	<0.1	<1	3	1	7
R-1	04-26-90	<1	<0.1	6	<1	1	8
	07-30-90	<1	0.1	<1	<1	2	5
	11-13-90	<1	<0.1	1	<1	2	4
R-2	04-27-90	<1	<0.1	4	<1	<1	<3
	07-30-90	<1	<0.1	<1	<1	2	7
	11-13-90	<1	<0.1	<1	<1	2	5
R-3	04-27-90	<1	<0.1	1	<1	<1	6
	07-30-90	<1	0.1	<1	<1	<1	10
	11-14-90	<1	<0.1	1	<1	<1	9
R-4	04-30-90	<1	<0.1	1	<1	1	7
	08-03-90	<1	<0.1	<1	<1	1	8
R-5	04-28-90	<1	<0.1	2	<1	4	<10

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Lead, dissolved ($\mu\text{g/L}$ as Pb) (01049)	Mercury, dissolved ($\mu\text{g/L}$ as Hg) (71890)	Molybdenum, dissolved ($\mu\text{g/L}$ as Mo) (01060)	Selenium, dissolved ($\mu\text{g/L}$ as Se) (01145)	Vanadium, dissolved ($\mu\text{g/L}$ as V) (01085)	Zinc, dissolved ($\mu\text{g/L}$ as Zn) (01090)
R-5	08-02-90	<1	0.2	<1	<1	1	6
	11-16-90	<1	<0.1	2	<1	1	<10
R-6	04-27-90	<1	<0.1	1	<1	<1	4
	07-30-90	1	<0.1	<1	<1	2	10
	11-14-90	<1	<0.1	1	<1	<1	13
R-7	04-29-90	<1	<0.1	2	3	7	<10
	11-16-90	<1	<0.1	2	2	9	<10
R-8	04-29-90	<1	<0.1	1	<1	1	6
	08-03-90	<1	<0.1	<1	<1	1	<3
R-9	04-28-90	<1	<0.1	6	4	4	9
	07-31-90	<1	0.2	4	2	3	7
R-10	11-15-90	<1	<0.1	2	3	3	<3
	04-29-90	<1	<0.1	1	<1	1	4
	08-02-90	<1	0.2	1	1	2	11
	12-02-90	<1	<0.1	<1	1	<1	3
R-11	04-28-90	<1	<0.1	2	<1	1	9
	07-31-90	<1	0.2	<1	2	2	9
	11-15-90	<1	<0.1	1	<1	1	6

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990--Continued

Site number	Date	Time	Dis-charge, instantaneous (cubic feet per second) (00061)	Arsenic, dis-solved ($\mu\text{g/L}$ as As) (01000)	Cadmium, dis-solved ($\mu\text{g/L}$ as Cd) (01025)	Chromium, dis-solved ($\mu\text{g/L}$ as Cr) (01030)	Copper, dis-solved ($\mu\text{g/L}$ as Cu) (01040)
Quality assurance/quality control samples							
I-2	12-03-90	1300	0.25	<1	<1.0	<1	1
	12-03-90	1300	0.25	<1	<1.0	<1	1
I-3	08-06-90	1000	--	3	<1.0	<1	1
	08-06-90	1010	--	2	<1.0	<1	<1
I-4	11-17-90	1100	--	<1	<1.0	1	3
	11-17-90	1110	--	<1	<1.0	<1	3
I-6B	04-18-90	0930	--	<1	<1.0	2	<1
	04-18-90	0940	--	<1	<1.0	2	1
I-7	08-01-90	0900	0.38	<1	<1.0	<1	1
	08-01-90	0910	0.38	<1	<1.0	1	1
I-17	08-03-90	1000	--	1	<1.0	<1	3
	08-03-90	1000	--	1	<1.0	<1	3
I-22	11-16-90	1000	0.08	<1	<1.0	<1	1
	11-16-90	1010	0.08	<1	<1.0	<1	1
R-2	04-27-90	0930	450	<1	<1.0	1	8
	04-27-90	0930	450	<1	<1.0	1	2
R-4	04-30-90	1000	--	<1	<1.0	1	1
	04-30-90	1005	--	<1	<1.0	<1	1
Trip blank Equipment blank	08-05-90	1500	--	<1	<1.0	<1	<1
	08-05-90	1510	--	<1	<1.0	<1	1
Trip blank Equipment blank	12-03-90	1430	--	4	<1.0	<1	1
	12-03-90	1440	--	4	<1.0	<1	1

Table 21.--Streamflow and concentrations of trace elements in water samples: spring, summer, and fall 1990--Concluded

Site number	Date	Lead, dissolved ($\mu\text{g/L}$ as Pb) (01049)	Mercury, dissolved ($\mu\text{g/L}$ as Hg) (71890)	Molybdenum, dissolved ($\mu\text{g/L}$ as Mo) (01060)	Selenium, dissolved ($\mu\text{g/L}$ as Se) (01145)	Vanadium, dissolved ($\mu\text{g/L}$ as V) (01085)	Zinc, dissolved ($\mu\text{g/L}$ as Zn) (01090)
Quality assurance/quality control samples							
I-2	12-03-90	<1	<0.1	<1	35	5	<10
	12-03-90	<1	<0.1	<1	34	5	10
I-3	08-06-90	<1	0.1	<1	2	5	16
	08-06-90	<1	0.2	<1	2	5	4
I-4	11-17-90	<1	<0.1	1	15	4	<10
	11-17-90	<1	<0.1	7	15	4	10
I-6B	04-18-90	<1	<0.1	2	2	7	<10
	04-18-90	<1	<0.1	1	2	10	<10
I-7	08-01-90	<1	0.1	9	42	6	10
	08-01-90	<1	0.1	8	42	6	10
I-17	08-03-90	<1	0.2	<1	<1	3	4
	08-03-90	<1	0.2	<1	<1	3	<3
I-22	11-16-90	<1	<0.1	6	12	2	10
	11-16-90	<1	<0.1	2	17	1	<10
R-2	04-27-90	<1	<0.1	4	<1	<1	<3
	04-27-90	<1	<0.1	1	<1	2	6
R-4	04-30-90	<1	<0.1	1	<1	1	7
	04-30-90	<1	<0.1	1	<1	1	<3
Trip blank	08-05-90	<1	0.1	<1	<1	<1	12
Equipment blank	08-05-90	<1	0.1	<1	<1	<1	11
Trip blank	12-03-90	<1	<0.1	<1	<1	8	9
Equipment blank	12-03-90	<1	<0.1	<1	<1	8	5

Table 22.—Concentrations of selected constituents in bottom sediment: fall 1990

[Site number, see figs. 7 and 8, tables 3 and 4;
ppm, parts per million; %, percent; <, less than]

Site number	Date (time)	Holmium (Ho) (ppm)	Calcium (Ca) (%)	Magnesium (Mg) (%)	Sodium (Na) (%)	Potassium (K) (%)	Phosphorus (P) (%)	Aluminum (Al) (%)	Arsenic (As) (ppm)	Barium (Ba) (ppm)	Beryllium (Be) (ppm)
Less than 0.062 millimeter size fraction											
I-1	12-03-90 (1000)	<4	3.9	0.59	0.87	1.7	0.07	5.1	3.6	700	1
I-2	11-07-90 (1600)	<4	14	0.62	0.67	1.2	0.08	4.3	2.1	490	1
I-3	11-09-90 (1300)	<4	8.9	1.1	0.47	1.5	0.07	7.1	5.1	690	2
I-4	12-03-90 (1600)	<4	1.3	0.32	1.2	2.0	0.06	4.9	4.9	1,800	1
I-6A	11-08-90 (1600)	<4	5.9	1.0	0.68	1.6	0.06	7.8	4.9	900	2
I-7	11-08-90 (1000)	<4	4.5	0.90	1.6	1.7	0.06	7.4	2.5	980	2
I-17	11-07-90 (1000)	<4	1.7	0.66	1.1	2.2	0.07	6.2	2.6	790	2
I-20	11-07-90 (1300)	<4	7.1	0.75	0.78	1.9	0.07	5.9	2.6	650	1
I-21	11-06-90 (0900)	<4	5.1	0.94	1.0	1.7	0.06	7.2	3.6	550	2
I-22	11-06-90 (1600)	<4	5.3	1.4	0.58	1.7	0.08	6.7	3.5	520	2
I-23	11-06-90 (1400)	<4	7.3	1.1	0.58	1.7	0.06	7.1	4.5	430	2
I-24	12-02-90 (1030)	<4	6.3	0.93	0.74	1.7	0.06	6.2	3.8	500	1
R-1	11-13-90 (1000)	<4	0.78	0.47	1.4	2.2	0.04	5.9	3.0	830	2
R-2	11-13-90 (1400)	<4	0.79	0.36	1.2	2.1	0.04	5.0	2.9	1,500	1
R-5	11-16-90 (1300)	<4	1.4	0.65	1.3	2.1	0.07	7.4	4.6	810	2
R-6	11-14-90 (1100)	<4	1.2	0.51	1.3	2.3	0.05	6.2	3.3	970	2
R-9	11-15-90 (0900)	<4	3.0	0.75	1.5	1.8	0.06	5.7	4.6	1,600	1
R-11	11-15-90 (1300)	<4	1.7	0.59	1.3	2.1	0.06	5.4	3.0	940	1
Quality assurance/quality control samples											
I-1	12-03-90 (1010)	<4	4.5	0.79	0.74	1.7	0.08	6.1	3.8	720	1
I-7	11-08-90 (1000)	<4	4.4	0.91	1.6	1.7	0.06	7.4	2.7	950	2

Table 22.—Concentrations of selected constituents in bottom sediment: fall 1990—Continued

Site number	Bismuth (Bi) (ppm)	Cadmium (Cd) (ppm)	Cerium (Ce) (ppm)	Chromium (Cr) (ppm)	Cobalt (Co) (ppm)	Copper (Cu) (ppm)	Europium (Eu) (ppm)	Gallium (Ga) (ppm)	Gold (Au) (ppm)	Iron (Fe) (%)
Less than 0.062 millimeter size fraction										
I-1	<10	<2	76	30	8	17	<2	11	<8	1.9
I-2	<10	<2	54	24	8	13	<2	12	<8	1.9
I-3	<10	<2	78	33	12	20	<2	17	<8	2.7
I-4	<10	<2	220	51	10	18	<2	11	<8	2.7
I-6A	<10	<2	91	33	12	22	<2	19	<8	2.9
I-7	<10	<2	86	24	12	27	<2	18	<8	2.9
I-17	<10	<2	96	29	10	20	<2	16	<8	2.4
I-20	<10	<2	84	28	9	31	<2	15	<8	2.3
I-21	<10	<2	78	34	12	36	<2	19	<8	3.3
I-22	<10	<2	72	53	11	29	<2	17	<8	2.8
I-23	<10	<2	77	45	11	34	<2	18	<8	3.0
I-24	<10	<2	72	37	10	27	<2	15	<8	2.9
R-1	<10	<2	76	28	9	27	<2	14	<8	2.1
R-2	<10	<2	200	43	9	15	<2	12	<8	2.8
R-5	<10	<2	88	31	11	28	<2	18	<8	2.8
R-6	<10	<2	93	29	9	21	<2	14	<8	2.3
R-9	<10	<2	96	31	10	18	<2	14	<8	2.3
R-11	<10	<2	98	30	8	19	<2	11	<8	2.0
Quality assurance/quality control samples										
I-1	<10	<2	77	23	10	20	<2	14	<8	2.4
I-7	<10	<2	83	24	12	27	<2	17	<8	2.9

Table 22.—Concentrations of selected constituents in bottom sediment: fall 1990—Continued

Site number	Lanthanum (La) (ppm)	Lead (Pb) (ppm)	Lithium (Li) (ppm)	Manganese (Mn) (ppm)	Mercury (Hg) (ppm)	Molybdenum (Mo) (ppm)	Neodymium (Nd) (ppm)	Nickel (Ni) (ppm)	Niobium (Nb) (ppm)	Scandium (Sc) (ppm)	Selenium (Se) (ppm)
Less than 0.062 millimeter size fraction											
I-1	40	15	21	790	0.02	<2	31	12	5	6	0.8
I-2	29	15	21	1,300	0.02	3	25	10	4	6	37
I-3	42	18	28	830	0.04	2	34	16	7	9	1.9
I-4	110	18	16	740	0.02	<2	91	12	<4	7	0.3
I-6A	50	20	26	580	0.04	<2	40	14	6	10	1.5
I-7	45	19	22	500	0.02	<2	37	12	7	9	5.0
I-17	52	18	21	1,200	0.02	<2	41	12	9	7	0.5
I-20	46	17	21	450	<0.02	<2	36	11	<4	7	1.6
I-21	43	25	26	930	0.04	<2	36	14	9	10	0.5
I-22	40	24	36	830	0.04	<2	34	20	6	10	6.0
I-23	43	44	35	890	0.04	<2	34	16	11	10	4.5
I-24	40	32	27	480	0.02	<2	33	16	8	8	5.5
R-1	40	15	20	660	<0.02	<2	34	12	<4	6	0.1
R-2	110	20	17	580	<0.02	<2	88	10	<4	7	0.1
R-5	49	19	21	390	0.02	<2	40	13	9	8	0.3
R-6	50	25	20	580	<0.02	<2	42	11	<4	7	0.2
R-9	52	16	19	630	0.02	<2	44	10	<4	6	0.4
R-11	52	20	19	460	0.02	<2	44	10	<4	6	0.3
Quality assurance/quality control samples											
I-1	40	18	26	940	0.04	<2	32	13	6	8	1.0
I-7	44	16	22	500	0.02	<2	36	11	8	9	5.1

Table 22.—Concentrations of selected constituents in bottom sediment: fall 1990--Continued

Site number	Silver (Ag) (ppm)	Strontium (Sr) (ppm)	Tantalum (Ta) (ppm)	Thorium (Th) (ppm)	Tin (Sn) (ppm)	Titanium (Ti) (ppm)	Vanadium (V) (ppm)	Ytterbium (Yb) (ppm)	Yttrium (Y) (ppm)	Zinc (Zn) (ppm)	Uranium (U) (ppm)
Less than 0.062 millimeter size fraction											
I-1	<2	530	<40	11	<5	0.31	47	2	19	61	<100
I-2	<2	1,500	<40	9	<5	0.20	42	2	14	57	<100
I-3	<2	1,000	<40	13	<5	0.26	66	2	19	76	<100
I-4	<2	230	<40	45	<5	0.71	66	4	35	42	<100
I-6A	<2	350	<40	12	<5	0.32	76	2	22	66	<100
I-7	<2	590	<40	9	<5	0.37	75	2	19	68	<100
I-17	<2	300	<40	15	<5	0.40	53	2	21	59	<100
I-20	<2	900	<40	11	<5	0.31	54	2	18	54	<100
I-21	<2	500	<40	13	<5	0.35	79	2	21	96	<100
I-22	<2	340	<40	12	<5	0.30	110	2	21	100	<100
I-23	<2	440	<40	13	<5	0.33	83	2	21	150	<100
I-24	<2	420	<40	11	<5	0.31	72	2	20	150	<100
R-1	<2	160	<40	12	<5	0.32	49	2	16	48	<100
R-2	<2	170	<40	44	<5	0.68	72	4	38	41	<100
R-5	<2	290	<40	12	<5	0.36	73	2	21	69	<100
R-6	<2	220	<40	15	<5	0.39	56	2	22	86	<100
R-9	<2	380	<40	16	<5	0.42	58	3	24	49	<100
R-11	<2	230	<40	18	<5	0.39	54	3	24	65	<100
Quality assurance/quality control samples											
I-1	<2	590	<40	11	<5	0.30	55	2	21	85	<100
I-7	<2	580	<40	10	<5	0.38	75	2	19	70	<100

Table 22.--Concentrations of selected constituents in bottom sediment: fall 1990--Continued

Site number	Date (time)	Holmium (Ho) (ppm)	Calcium (Ca) (%)	Magnesium (Mg) (%)	Sodium (Na) (%)	Potassium (K) (%)	Phosphorus (P) (%)	Aluminum (Al) (%)	Arsenic (As) (ppm)	Barium (Ba) (ppm)
Less than 2 millimeter size fraction										
I-1	12-03-90 (1000)	<4	1.1	0.19	1.0	2.3	0.03	4.1	2.6	830
I-2	11-07-90 (1600)	<4	9.6	0.48	0.80	1.5	0.06	4.3	2.4	600
I-3	11-09-90 (1300)	<4	5.8	0.87	0.57	1.8	0.06	6.4	4.1	740
I-4	12-03-90 (1600)	<4	0.39	0.06	0.95	2.5	0.01	3.6	2.9	1,000
I-6A	11-08-90 (1600)	<4	5.4	1.0	0.76	1.8	0.06	8.1	4.7	890
I-7	11-08-90 (1000)	<4	2.6	0.54	1.7	2.0	0.05	6.4	2.9	1,100
I-17	11-07-90 (1000)	<4	0.70	0.28	1.1	2.5	0.03	4.7	1.5	850
I-20	11-07-90 (1300)	<4	3.3	0.44	0.97	2.4	0.04	5.1	2.2	760
I-21	11-06-90 (0900)	<4	3.7	0.79	1.1	1.9	0.05	6.7	3.4	610
I-22	11-06-90 (1600)	<4	3.9	1.0	0.77	1.9	0.06	6.3	4.4	610
I-23	11-06-90 (1400)	<4	6.5	1.0	0.59	1.8	0.06	7.0	2.6	430
I-24	12-02-90 (1030)	<4	3.8	0.62	0.94	2.0	0.04	5.3	3.2	590
R-1	11-13-90 (1000)	<4	0.23	0.07	1.1	2.8	0.01	3.9	2.6	880
R-2	11-13-90 (1400)	<4	0.36	0.09	1.2	2.4	0.02	3.8	5.9	900
R-5	11-16-90 (1300)	<4	1.0	0.32	1.4	2.5	0.03	5.9	3.4	1,000
R-6	11-14-90 (1100)	<4	0.42	0.12	1.1	2.7	0.02	4.1	2.4	890
R-9	11-15-90 (0900)	<4	1.2	0.15	1.3	2.0	0.02	4.2	4.1	1,100
R-11	11-15-90 (1300)	<4	0.78	0.18	1.2	2.5	0.03	4.3	3.0	990
Quality assurance/quality control samples										
I-1	12-03-90 (1010)	<4	1.7	0.36	0.98	2.2	0.04	4.8	3.0	800
I-7	11-08-90 (1000)	<4	2.4	0.51	1.7	2.2	0.04	6.2	2.4	1,000

Table 22.—Concentrations of selected constituents in bottom sediment: fall 1990—Continued

Site number	Beryllium (Be) (ppm)	Bismuth (Bi) (ppm)	Cadmium (Cd) (ppm)	Cerium (Ce) (ppm)	Chromium (Cr) (ppm)	Cobalt (Co) (ppm)	Copper (Cu) (ppm)	Europium (Eu) (ppm)	Gallium (Ga) (ppm)
Less than 2 millimeter size fraction									
I-1	<1	<10	<2	39	9	4	5	<2	7
I-2	1	<10	<2	45	18	7	11	<2	11
I-3	2	<10	<2	66	31	10	16	<2	15
I-4	<1	<10	<2	40	3	3	2	<2	7
I-6A	2	<10	<2	93	33	12	23	<2	20
I-7	1	<10	<2	63	15	9	16	<2	14
I-17	1	<10	<2	45	11	5	9	<2	10
I-20	1	<10	<2	55	16	7	17	<2	12
I-21	2	<10	<2	71	29	11	29	<2	17
I-22	1	<10	<2	64	43	10	23	<2	14
I-23	2	<10	<2	75	43	12	33	<2	18
I-24	1	<10	<2	55	25	8	18	<2	13
R-1	<1	<10	<2	28	3	3	3	<2	6
R-2	<1	<10	<2	36	5	3	3	<2	7
R-5	1	<10	<2	56	14	7	16	<2	13
R-6	<1	<10	<2	41	6	4	5	<2	8
R-9	<1	<10	<2	36	6	4	5	<2	9
R-11	<1	<10	<2	44	8	5	6	<2	10
Quality assurance/quality control samples									
I-1	1	<10	<2	48	16	6	10	<2	9
I-7	1	<10	<2	62	14	9	15	<2	14

Table 22.—Concentrations of selected constituents in
bottom sediment: fall 1990—Continued

Site number	Gold (Au) (ppm)	Iron (Fe) (%)	Lan- tha- num (La) (ppm)	Lead (Pb) (ppm)	Lith- ium (Li) (ppm)	Manga- nese (Mn) (ppm)	Mer- cury (Hg) (ppm)	Molyb- denum (Mo) (ppm)	Neo- dym- ium (Nd) (ppm)	Nick- el (Ni) (ppm)	Nio- bium (Nb) (ppm)
Less than 2 millimeter size fraction											
I-1	<8	0.74	24	11	11	220	0.04	<2	16	5	<4
I-2	<8	1.5	26	12	17	910	0.04	3	21	8	<4
I-3	<8	2.3	36	17	23	620	0.04	<2	29	14	<4
I-4	<8	0.46	23	12	6	200	<0.02	<2	17	2	<4
I-6A	<8	2.9	52	19	27	550	0.04	<2	41	14	8
I-7	<8	2.0	34	13	15	370	<0.02	<2	28	8	<4
I-17	<8	1.0	25	13	11	450	0.04	<2	19	6	<4
I-20	<8	1.5	32	14	14	280	0.04	<2	24	7	5
I-21	<8	2.8	40	22	23	690	0.04	<2	31	13	8
I-22	<8	2.4	35	25	30	650	0.04	3	27	17	6
I-23	<8	2.8	42	39	33	810	0.10	<2	36	16	9
I-24	<8	2.1	30	25	19	360	0.04	<2	23	10	5
R-1	<8	0.43	17	15	6	220	0.04	<2	9	3	<4
R-2	<8	0.52	21	13	8	200	0.02	<2	12	3	<4
R-5	<8	1.7	33	12	12	280	0.02	<2	28	7	5
R-6	<8	0.64	24	19	8	250	0.02	<2	18	3	<4
R-9	<8	1.1	21	11	8	340	0.06	<2	16	4	<4
R-11	<8	0.87	24	15	10	300	0.04	<2	19	4	<4
Quality assurance/quality control samples											
I-1	<8	1.2	27	13	15	410	0.04	<2	18	7	<4
I-7	<8	1.9	34	15	15	370	0.02	<2	26	7	<4

Table 22.—Concentrations of selected constituents in bottom sediment: fall 1990—Concluded

Site number	Scandium (Sc) (ppm)	Selenium (Se) (ppm)	Silver (Ag) (ppm)	Strontium (Sr) (ppm)	Tantalum (Ta) (ppm)	Thorium (Th) (ppm)	Tin (Sn) (ppm)	Titanium (Ti) (ppm)	Vanadium (V) (ppm)	Terbium (Yb) (ppm)	Yttrium (Y) (ppm)	Zinc (Zn) (ppm)	Uranium (U) (ppm)
Less than 2 millimeter size fraction													
I-1	2	0.3	<2	240	<40	6	<5	0.11	18	1	9	23	<100
I-2	5	29	<2	1,000	<40	6	<5	0.16	34	1	11	43	<100
I-3	8	1.5	<2	660	<40	10	<5	0.22	54	2	16	64	<100
I-4	<2	0.1	<2	140	<40	6	<5	0.07	8	<1	6	9	<100
I-6A	11	1.4	<2	340	<40	13	<5	0.32	77	2	22	69	<100
I-7	5	2.9	<2	500	<40	7	<5	0.24	48	1	13	45	<100
I-17	3	0.2	<2	180	<40	5	<5	0.16	22	<1	9	26	<100
I-20	4	0.8	<2	480	<40	7	<5	0.20	32	1	12	35	<100
I-21	9	0.4	<2	400	<40	11	<5	0.32	69	2	18	82	<100
I-22	8	5.7	<2	300	<40	8	<5	0.26	88	2	17	87	<100
I-23	10	3.3	<2	400	<40	13	<5	0.32	79	2	20	140	<100
I-24	6	4.4	<2	300	<40	7	<5	0.23	54	1	14	100	<100
R-1	<2	0.1	<2	130	<40	<4	<5	0.05	7	<1	4	10	<100
R-2	<2	<0.1	<2	130	<40	<4	<5	0.11	12	<1	7	11	<100
R-5	4	0.2	<2	290	<40	9	<5	0.19	39	1	12	38	<100
R-6	<2	0.1	<2	150	<40	6	<5	0.07	13	<1	7	35	<100
R-9	<2	0.1	<2	270	<40	6	<5	0.11	18	<1	9	20	<100
R-11	2	0.1	<2	180	<40	5	<5	0.12	20	<1	9	35	<100
Quality assurance/quality control samples													
I-1	4	0.4	<2	310	<40	5	<5	0.15	28	1	12	43	<100
I-7	5	2.9	<2	480	<40	7	<5	0.23	46	1	13	43	<100

Table 23.--Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990

[Site number, see fig. 7 and table 3; concentrations are in micrograms per gram, dry weight; <, less than]

Site number	Date	Organism	Aluminum (Al)	Antimony (Sb)	Arsenic (As)	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Chromium (Cr)	Cobalt (Co)	Copper (Cu)	Iron (Fe)
Plant samples													
I-1	06-26-90	Potamogeton	961	<5.00	3.06	149	<0.100	25.8	<0.100	1.52	1.45	3.67	966
I-2	06-26-90	Chara	199	<5.00	.666	38.2	<1.100	13.4	.116	.624	.617	1.12	284
I-3	06-26-90	Chara	96.9	6.62	2.26	110	<1.100	9.16	<1.100	.984	1.24	.790	331
I-6A	06-26-90	Chara	<3.00	<5.00	4.38	61.2	<1.100	5.00	<1.100	.995	3.06	.774	491
I-6B	06-26-90	Chara	782	<5.00	3.59	165	<1.100	9.63	<1.100	1.76	1.26	1.77	945
I-10	06-26-90	Potamogeton	551	<5.00	3.06	23.8	<1.100	100	<1.100	.909	1.00	1.48	1,290
I-11	06-26-90	Potamogeton	1,070	<5.00	13.2	261	<1.100	208	.162	1.02	3.07	4.37	4,040
I-12	06-26-90	Potamogeton	180	<5.00	1.44	51.5	<1.100	160	<1.100	.820	.587	1.35	180
I-13	06-28-90	Chara	5,300	<5.00	7.75	932	.238	11.3	.362	2.92	3.75	16.5	4,230
I-16	06-27-90	Chara	1,340	<5.00	2.95	35.7	<1.100	14.5	<1.100	2.57	2.86	2.21	1,500
I-18	06-27-90	Potamogeton	1,640	<5.00	2.75	204	<1.100	207	<1.100	1.75	1.64	5.04	1,810
I-20	06-26-90	Chara	377	<5.00	<.35	29.4	<1.100	11.3	<1.100	.618	<.500	1.07	264
I-21	07-09-90	Coontail	609	<5.00	2.80	86.5	<1.100	12.6	<1.100	1.88	1.31	3.56	1,220
I-22	07-10-90	Coontail	3,460	<5.00	6.05	33.4	<1.100	7.61	.245	2.13	3.37	81.4	1,690
I-23	07-10-90	Pondweed	1,560	<5.00	4.07	10.8	<1.100	5.24	.332	2.74	1.11	12.5	1,040

Table 23.--Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990--Continued

Site number	Lead (Pb)	Magnesium (Mg)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)	Nickel (Ni)	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
Plant samples											
I-1	2.17	4,860	2,460	<0.05	<0.500	1.88	2.52	1,960	<5.00	3.82	12.5
I-2	<.35	1,780	832	<.05	<.500	<.500	9.90	1,810	2.74	<5.00	.791
I-3	<.35	2,630	4,320	<.05	<.500	2.01	3.13	2,110	<5.00	.593	5.96
I-6A	.444	2,640	4,970	<.05	<.500	.938	1.33	1,290	<5.00	<.500	7.46
I-6B	1.61	4,070	6,930	<.05	<.500	1.27	1.20	703	7.22	2.13	10.4
I-10	3.61	8,520	1,470	<.05	1.08	1.16	<.5	1,700	<5.00	1.76	11.7
I-11	2.52	3,490	565	<.05	2.63	2.23	1.00	277	6.98	7.14	17.2
I-12	1.27	6,410	174	<.05	<.500	1.09	1.01	174	<5.00	.999	17.7
I-13	6.03	5,670	223	<.05	<.500	3.59	1.48	559	6.00	9.76	38.3
I-16	1.23	2,410	6,580	<.05	.535	1.67	<.5	1,730	<5.00	1.93	9.93
I-18	1.33	3,300	152	<.05	2.39	1.48	.820	189	<5.00	7.89	28.2
I-20	.435	2,050	271	<.05	<.500	<.500	1.16	2,700	<5.00	.725	3.74
I-21	2.03	1,690	338	<.05	<.500	1.57	<.6	572	<6.00	5.12	15.4
I-22	2.52	741	514	<.05	.919	2.96	5.10	324	<6.00	7.53	39.9
I-23	1.37	1,250	159	<.05	<.500	1.69	<.6	45.0	6.21	4.13	74.4

Table 23.--Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990--Continued

Site number	Date	Organism	Aluminum (Al)	Antimony (Sb)	Arsenic (As)	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Cobalt (Co)	Chromium (Cr)	Copper (Cu)	Iron (Fe)
Invertebrate samples													
I-1	06-28-90	Hemiptera/Odonata	114	<5.00	0.501	16.9	<0.100	2.64	0.735	0.721	<0.500	12.9	185
I-2	06-28-90	Hemiptera/Odonata	288	<5.00	.304	4.45	<0.100	1.82	<0.100	<0.500	<0.500	15.7	422
I-3	06-26-90	Odonata	71.9	<5.00	.482	2.54	<0.100	2.19	<0.100	<0.500	<0.500	20.3	117
I-6A	02-28-90	Hemiptera/Odonata	221	<5.00	.567	13.3	<0.100	1.50	<0.100	<0.500	<0.500	14.2	225
I-6B	06-28-90	Hemiptera/Odonata	143	<5.00	<.3	3.30	<0.100	1.70	.166	<0.500	.585	20.0	277
I-10	06-27-90	Coleoptera/Odonata	239	<5.00	.988	19.8	<0.100	3.76	<0.100	<0.500	<0.500	139	336
I-12	06-28-90	Hemiptera	206	<5.00	.855	27.9	<0.100	2.24	.142	<0.500	.563	9.45	231
I-13	06-28-90	Hemiptera	394	<5.00	.913	94.0	<0.100	<1.50	.389	<0.500	.636	34.6	397
I-16	06-27-90	Coleoptera/Odonata	321	<5.00	.517	3.77	<0.100	8.56	.295	.618	<0.500	64.8	403
I-16	06-27-90	Gastropoda	194	<5.00	1.25	5.94	<0.100	1.06	<0.100	.661	.612	6.50	427
I-20	06-27-90	Odonata	1,900	<5.00	1.18	19.1	<0.100	6.91	.401	1.38	.979	19.9	1,310
I-21	07-09-90	Gastropoda/Odonata	3,920	<5.00	4.77	33.1	<0.100	8.43	.190	3.99	2.28	89.5	2,020
I-22	07-10-90	Crayfish	19.0	<5.00	2.06	38.0	<0.100	3.44	<0.100	.541	.842	100	202
I-22	07-10-90	Odonata	1,830	<5.00	.832	12.2	<0.100	5.11	.293	.907	2.19	12.4	1,030
I-23	07-10-90	Crayfish	9.78	<5.00	1.26	931	<0.100	2.34	.118	<0.500	.643	74.3	266

Table 23.--Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990--Continued

Site number	Lead (Pb)	Magnesium (Mg)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)	Nickel (Ni)	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
I-1	0.884	1,220	58.1	0.116	<0.500	0.670	4.42	65.1	<5.00	<0.500	112
I-2	.540	1,360	28.1	<.05	<.500	<.500	32.3	118	<.500	<.500	97.1
I-3	1.05	770	59.2	.128	<.500	<.500	8.75	21.8	<.500	<.500	62.5
I-6A	.835	1,360	109	.126	<.500	<.500	3.00	32.3	<.500	<.500	95.9
I-6B	.536	1,620	59.0	.114	<.500	.605	10.2	61.4	<.500	<.500	115
I-10	.499	1,190	69.3	<.05	.554	<.500	1.44	26.7	<.500	.853	100
I-12	.206	1,150	27.7	.227	<.500	<.500	1.81	16.0	<.500	.642	105
I-13	3.10	1,540	56.3	.628	<.500	<.50	3.12	24.8	<.500	.992	164
I-16	25.4	2,480	150	<.05	.646	1.03	.517	88.4	<.500	<.500	353
I-16	.922	344	865	<.05	<.500	<.500	.359	378	<.500	<.500	9.22
I-20	1.92	1,430	68.6	<.05	<.500	1.66	9.62	457	<.500	2.23	70.2
I-21	3.26	963	630	<.05	<.500	2.61	1.12	307	<.500	9.39	43.7
I-22	.249	1,120	244	<.05	<.500	.920	11.1	437	<.500	1.09	50.7
I-22	1.16	1,390	163	<.05	<.500	1.04	17.4	58.0	<.500	3.82	27.1
I-23	.542	718	282	.435	<.500	<.500	.611	430	<.500	.677	43.4

Invertebrate samples

Table 23.--Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990--Continued

Site	Date	Organism	Aluminum (Al)	Antimony (Sb)	Arsenic (As)	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Cobalt (Co)	Chromium (Cr)	Copper (Cu)	Iron (Fe)
Amphibian samples													
I-1	06-28-90	Waterdog	245	<5.00	0.768	19.5	<0.100	1.77	<0.100	0.547	0.764	4.07	271
I-2	06-26-90	do.	170	<5.00	.647	4.20	<0.100	1.86	<0.100	<0.500	.558	5.40	284
I-3	06-26-90	do.	124	<5.00	.652	13.1	<0.100	3.35	<0.100	<0.500	.584	7.24	196
I-6A	06-26-90	do.	257	<5.00	1.12	10.5	<0.100	2.00	<0.100	<0.500	<0.500	5.76	476
I-6B	06-26-90	do.	123	<5.00	.557	9.31	<0.100	1.55	<0.100	<0.500	.723	2.43	213
I-11	06-27-90	do.	188	<5.00	.833	18.8	<0.100	<1.50	<0.100	<0.500	.669	5.36	312
I-12	06-27-90	do.	155	<5.00	1.22	14.8	<0.100	2.00	<0.100	<0.500	.710	3.14	221
I-13	06-28-90	do.	974	<5.00	.813	36.0	<0.100	<1.50	<0.100	.746	1.21	6.19	803
I-21	07-09-90	Tadpole	<2.00	<5.00	5.14	296	1.48	48.1	.700	21.0	28.1	24.6	<10.0
Amphibian samples													
I-1	0.250	1,440	90.4	0.102	<0.500	<0.500	<0.500	5.24	421	<5.00	<0.500	<0.500	66.4
I-2	<.2	1,290	16.3	<.05	<.500	<.500	<.500	51.3	240	<.500	<.500	<.500	74.3
I-3	.296	1,260	98.2	.056	<.500	<.500	<.500	23.5	194	<.500	<.500	<.500	70.8
I-6A	.421	1,060	55.9	<.05	<.500	<.500	<.500	14.7	90.4	<.500	<.500	<.500	51.9
I-6B	.239	1,430	42.0	<.05	<.500	<.500	<.500	4.22	109	<.500	<.500	<.500	65.2
I-11	.208	1,170	12.0	<.05	<.500	<.500	<.500	3.83	112	<.500	<.500	<.500	72.0
I-12	.343	1,350	13.9	.099	<.500	<.500	<.500	2.40	133	<.500	<.500	<.500	67.8
I-13	.813	1,370	35.9	.330	<.500	<.500	<.500	3.71	137	<.500	<.500	1.82	75.4
I-21	16.8	5,440	1,040	<.05	1.71	13.1	2.53	8.89	132	67.3	107		

Table 23.--Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990--Continued

Site number	Date	Species	Aluminum (Al)	Antimony (Sb)	Arsenic (As)	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Cobalt (Co)	Chromium (Cr)	Copper (Cu)	Iron (Fe)
Fish samples													
Mosquitofish, killifish, and fathead minnow													
I-16	06-27-90	Mosquitofish	268	<5.00	<0.3	5.46	<0.100	<1.50	<0.100	<0.500	0.905	17.8	321
I-16	06-27-90	Killifish	17.5	<5.00	<0.3	2.64	<1.00	<1.50	<1.00	<0.500	.756	6.87	113
I-20	06-26-90	Mosquitofish	54.9	<5.00	<0.3	5.25	<1.00	<1.50	<1.00	<0.500	.794	7.28	122
I-20	06-26-90	Killifish	214	<5.00	<0.3	9.71	<1.00	<1.50	<1.00	<0.500	.805	7.64	263
I-21	07-09-90	Mosquitofish	514	<5.00	<0.3	10.4	<1.00	1.49	<1.00	<0.500	1.83	6.25	488
I-21	07-09-90	Fathead minnow	1,980	<5.00	.813	19.1	<1.00	3.69	<1.00	.881	181	6.06	1,790
I-22	07-10-90	Mosquitofish	218	<5.00	<0.3	9.43	<1.00	.846	<1.00	<0.500	1.45	5.62	266
I-22	07-10-90	Fathead minnow	693	<5.00	.563	14.6	<1.00	1.33	<1.00	<0.500	2.04	3.68	953
I-23	07-10-90	Mosquitofish	56.9	<5.00	<0.3	13.5	<1.00	<0.500	<1.00	<0.500	1.45	6.35	168
Carp and flannelmouthed sucker													
I-21	07-09-90	Flannelmouthed sucker	175	<5.00	0.335	6.70	<0.100	0.841	<0.100	<0.500	1.70	2.14	298
I-22	07-10-90	Carp	235	<5.00	<0.3	5.65	<1.00	1.15	<1.00	<0.500	1.78	4.85	399
I-22	07-10-90	Flannelmouthed sucker	59.4	<5.00	<0.3	1.21	<1.00	<0.500	<1.00	<0.500	1.57	1.82	127
I-23	07-10-90	Carp	35.6	<5.00	<0.3	24.6	<1.00	.739	<1.00	<0.500	1.77	3.95	172
I-23	07-10-90	Flannelmouthed sucker	204	<5.00	<0.3	7.66	<1.00	.546	<1.00	<0.500	.823	<0.500	352

Table 23.--Concentrations of selected constituents in plant, invertebrate, amphibian, and fish samples collected from ponds and wetlands: summer 1990--Concluded

Site Number	Lead (Pb)	Magnesium (Mg)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)	Nickel (Ni)	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
Fish samples											
Mosquitofish, killifish, and fathead minnow											
I-16	0.855	1,420	221	<0.05	<0.500	<0.500	0.914	171	<5.00	<0.500	85.5
I-16	<.2	1,280	104	<.05	<.500	<.500	<.3	170	<5.00	<.500	105
I-20	<.2	1,360	23.7	<.05	<.500	<.500	15.5	317	<5.00	<.500	164
I-20	.240	1,130	45.3	<.05	<.500	<.500	13.6	333	<5.00	<5.00	170
I-21	.702	1,560	37.9	<.05	<.500	<.500	1.90	167	<6.00	.840	144
I-21	1.45	1,410	80.6	.062	<.500	1.30	2.29	125	<6.00	3.13	112
I-22	.325	1,660	49.6	<.05	<.500	<.500	27.2	172	<6.00	.525	164
I-22	1.31	1,670	54.2	<.05	<.500	.691	41.7	131	<6.00	1.84	116
I-23	.358	1,570	62.1	.203	<.500	<.500	3.77	129	<6.00	<.500	158
Carp and flannelmouthed sucker											
I-21	0.522	1,490	33.0	<0.05	<0.500	<0.500	2.00	173	<6.00	<0.500	77.5
I-22	.325	1,530	22.5	<.05	<.500	<.500	28.5	175	<6.00	.700	25.0
I-22	<.2	1,260	19.2	<.05	<.500	<.500	35.1	75.8	<6.00	<.500	66.7
I-23	1.62	1,950	32.2	.397	<.500	<.500	2.24	341	<6.00	<.500	182
I-23	1.26	1,010	50.3	.260	<.500	<.500	2.32	71.7	<6.00	<.500	78.3

Table 24.--Concentrations of selected constituents in composite samples of whole-body fish from the San Juan River: spring and fall 1990

[River reach, see fig. 8 and table 4; concentrations are in micrograms per gram, dry weight; wet weight = dry weight x (1 minus percent moisture content expressed as a decimal); <, less than; --, not determined]

River reach	Date	Percent moisture	Aluminum (Al)	Antimony (Sb)	Arsenic (As)	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Chromium (Cr)	Cobalt (Co)	Copper (Cu)	Iron (Fe)
Common carp - spring sampling period													
A	04-18-90	71.5	110	<5.00	<0.3	14.2	<0.100	0.649	0.443	0.877	<0.500	5.82	227
C	04-19-90	73.1	78.4	<5.00	<.3	8.91	<.100	<.500	<.150	.749	<.500	5.39	192
D	04-24-90	69.8	32.2	<5.00	<.3	3.21	<.100	<.500	.400	<.500	<.500	4.91	153
E	04-25-90	70.9	39.7	<5.00	<.3	9.30	<.100	<.500	.311	.783	<.500	2.70	117
F	04-26-90	72.3	112	<5.00	<.3	8.74	<.100	<.500	.597	.635	<.500	5.53	225
G	05-02-90	67.0	150	<5.00	<.3	10.4	<.100	<.500	.374	.614	<.500	5.68	262
Common carp - fall sampling period													
A	11-07-90	70.2	44.1	--	<0.3	6.16	<0.100	<0.500	0.265	3.57	--	4.42	163
B	11-03-90	71.0	7.79	--	<.3	5.70	<.100	<.500	<.100	.541	--	3.65	78.9
C	11-04-90	65.6	14.2	--	<.3	8.89	<.100	<.500	<.100	1.06	--	3.66	54.4
D	11-08-90	71.0	24.0	--	<.3	7.40	<.100	<.500	.177	.728	--	4.10	140
E	11-02-90	68.2	14.1	--	<.3	5.93	<.100	<.500	.380	.603	--	3.83	80.1
F	11-06-90	74.9	25.8	--	<.3	9.50	<.100	<.500	.693	.952	--	5.53	149
G	11-05-90	75.9	<5.00	--	<.3	3.58	<.100	<.500	<.100	.512	--	4.87	62.0
Flannelmouthed sucker - spring sampling period													
A	04-18-90	65.2	50.9	<5.00	<0.3	6.09	<0.100	<0.500	<0.150	0.548	<0.500	4.22	98.4
C	04-19-90	65.7	242	6.01	<.3	10.6	<.100	<.500	<.150	.659	<.500	2.67	105
D	04-24-90	66.8	102	<5.00	<.3	6.27	<.100	.552	<.150	<.500	<.500	2.37	151
E	04-25-90	66.1	59.2	<5.00	<.3	6.16	<.100	<.500	<.150	.641	<.500	2.94	131
F	04-26-90	64.0	82.1	<5.00	<.3	6.94	<.100	<.500	<.150	.586	<.500	2.33	163
G	05-02-90	65.0	102	<5.00	.338	8.18	<.100	<.500	<.150	<.500	<.500	3.32	168

Table 24.--Concentrations of selected constituents in composite samples of whole-body fish from the San Juan River: spring and fall 1990--Continued

River reach	Lead (Pb)	Magnesium (Mg)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)	Nickel (Ni)	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
Common carp - spring sampling period											
A	0.888	1,350	11.4	0.669	<0.800	<0.800	5.49	172	<5.00	0.742	201
C	6.27	1,260	11.4	.359	<0.800	<0.800	2.87	118	<5.00	<.500	242
D	.466	941	7.49	.208	<0.800	<0.800	2.78	35.6	<5.00	.574	233
E	.850	1,340	13.7	.283	<0.800	<0.800	2.82	155	<5.00	<.500	233
F	.690	1,220	11.9	.357	<0.800	<0.800	3.51	108	<5.00	<.500	326
G	1.17	1,110	12.4	.203	<0.800	<0.800	3.76	103	<5.00	.633	249
Common carp - fall sampling period											
A	1.43	976	10.9	0.651	<0.800	0.816	4.52	63.5	--	<0.500	290
B	<.2	854	7.89	.284	<0.800	<0.800	2.75	87.6	--	<.500	229
C	.275	1,060	13.9	.193	<0.800	<0.800	2.29	174	--	<.500	198
D	.388	968	10.0	.277	<0.800	<0.800	2.69	109	--	<.500	141
E	.374	854	7.17	.247	<0.800	<0.800	2.79	79.2	--	<.500	179
F	1.34	1,240	8.00	.407	<0.800	<0.800	3.80	129	--	<.500	245
G	.560	969	4.56	.543	<0.800	<0.800	2.52	54.5	--	<.500	62.8
Flannelmouthed sucker - spring sampling period											
A	0.509	916	34.3	0.569	<0.800	<0.800	2.30	48.5	<5.00	<.500	48.9
C	.339	1,040	23.8	.448	<0.800	<0.800	2.17	64.0	<5.00	<.500	55.7
D	.567	795	15.1	.245	<0.800	<0.800	1.41	25.2	<5.00	<.500	43.4
E	2.67	849	17.8	.216	<0.800	<0.800	1.79	33.6	<5.00	<.500	48.4
F	1.42	826	22.5	.222	<0.800	<0.800	1.93	53.8	<5.00	<.500	51.4
G	.576	986	12.1	.139	<0.800	<0.800	1.97	42.8	<5.00	.617	42.0
Flannelmouthed sucker - fall sampling period											
A	1.36	924	35.9	0.731	<0.800	<0.800	2.89	64.0	--	<0.500	47.1
B	.422	558	1.16	.774	<0.800	<0.800	2.57	7.17	--	<.500	82.5
C	<.2	714	10.7	.612	<0.800	<0.800	2.28	34.7	--	<.500	43.1
D	.736	1,170	30.8	.166	<0.800	<0.800	1.56	114	--	<.500	54.8
E	1.06	411	4.18	.263	<0.800	<0.800	1.27	13.7	--	<.500	84.8
F	.645	877	18.8	.461	<0.800	<0.800	2.07	70.2	--	<.500	47.7
G	.418	678	7.55	.203	<0.800	<0.800	2.14	30.9	--	<.500	39.2

Table 24.--Concentrations of selected constituents in composite samples of whole-body fish from the San Juan River: spring and fall 1990--Continued

River reach	Date	Percent moisture	Aluminum (Al)	Antimony (Sb)	Arsenic (As)	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Chromium (Cr)	Cobalt (Co)	Copper (Cu)	Iron (Fe)
Flannelmouthed sucker - fall sampling period													
A	11-07-90	70.1	120	--	<0.3	9.96	<0.100	<0.500	<0.100	0.767	--	2.08	185
B	11-03-90	58.8	<5.00	--	<.3	1.18	<.100	<.500	<.100	<.500	--	1.69	33.2
C	11-04-90	67.7	34.3	--	<.3	3.82	<.100	<.500	<.100	<.500	--	2.40	86.4
D	11-08-90	71.1	50.8	--	<.3	10.1	<.100	<.500	<.100	1.08	--	1.99	53.0
E	11-02-90	50.4	17.4	--	.390	1.75	<.100	<.500	.111	<.500	--	1.48	45.5
F	11-06-90	68.6	98.7	--	<.3	7.54	<.100	<.500	.106	.591	--	1.89	132
G	11-05-90	68.4	46.7	--	<.3	4.04	.129	<.500	.152	.545	--	2.53	106
Brown trout - spring sampling period													
A	04-18-90	73.4	62.9	<5.00	<0.3	4.41	<0.100	<0.500	<0.150	0.732	<0.500	9.53	171
C	04-19-90	72.2	73.3	8.29	<.3	3.10	<.100	<.500	<.150	.573	<.500	3.01	125
Brown trout - fall sampling period													
A	11-07-90	68.1	7.45	--	<0.3	1.67	0.114	<0.500	0.121	0.795	--	6.43	57.6
Channel catfish - spring sampling period													
E	04-25-90	69.6	278	7.80	<0.3	7.84	<0.100	3.33	0.223	0.781	<0.500	1.97	361
F	04-26-90	70.9	145	<5.00	<.3	4.32	<.100	.873	<.150	.645	<.500	2.79	224
G	05-02-90	71.1	306	<5.00	<.3	12.8	<.100	2.56	<.150	1.44	<.500	1.58	432
Channel catfish - fall sampling period													
E	11-02-90	77.6	10.8	--	<0.3	0.844	<0.100	<0.500	0.111	0.555	--	1.72	65.3
F	11-06-90	70.4	13.4	--	<.3	1.65	<.100	<.500	.151	.543	--	1.49	67.9
G	11-05-90	71.4	58.9	--	<.3	2.71	<.100	<.500	<.100	.635	--	2.57	111

Table 24.--Concentrations of selected constituents in composite samples of whole-body fish from the San Juan River: spring and fall 1990--Concluded

River reach	Lead (Pb)	Magnesium (Mg)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)	Nickel (Ni)	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
Brown trout - spring sampling period											
A	0.537	1,140	24.4	0.372	<0.800	<0.800	8.29	41.5	<5.00	<0.500	100
C	.269	905	12.6	.028	<0.800	<0.800	3.09	32.5	<5.00	<0.500	79.1
Brown trout - fall sampling period											
A	0.344	1,060	6.86	0.501	<0.800	<0.800	8.25	37.0	--	<0.500	84.3
Channel catfish - spring sampling period											
E	0.797	856	26.5	0.442	<0.800	<0.800	1.79	49.8	<5.00	0.578	53.5
F	1.43	964	19.4	.214	<0.800	<0.800	1.99	52.3	5.71	.725	64.6
G	1.96	1640	51.3	.245	<0.800	<0.800	1.92	210	<5.00	1.07	84.7
Channel catfish - fall sampling period											
E	<0.2	708	4.83	0.187	<0.800	<0.800	1.72	35.9	--	<0.500	47.5
F	1.06	894	7.50	.309	<0.800	<0.800	1.89	79.5	--	<0.500	57.9
G	.955	899	7.70	.162	<0.800	<0.800	2.58	85.0	--	<0.500	60.4

Table 25.—Concentrations of selected constituents in individual edible-portion fish samples from the San Juan River: 1990

[River reach, see fig. 8 and table 4; concentrations are in micrograms per gram, dry weight. Species: Ch. catfish, channel catfish; %, percent; —, not determined; <, less than detection level]

River reach	Species	Weight (grams)	Percent moisture	Aluminum	Antimony	Arsenic	Barium	Beryllium
A	Carp	304.0	65.30	6.26	<5.00	<0.30	1.03	<0.10
A	do.	323.0	68.40	<5.00	<5.00	<0.30	2.54	<0.10
A	do.	249.0	70.70	<5.00	<5.00	<0.30	1.86	<0.10
A	do.	248.0	76.90	<5.00	<5.00	<0.30	6.60	<0.10
A	do.	242.0	76.00	<5.00	<5.00	<0.30	1.03	<0.10
B	do.	--	69.50	<3.00	<5.00	<0.30	2.37	<0.10
B	do.	303.0	71.00	<2.00	<5.00	<0.30	2.21	<0.10
B	do.	--	75.10	15.70	<5.00	<0.30	3.15	<0.10
B	do.	--	73.80	38.40	<5.00	<0.30	3.48	<0.10
B	do.	320.0	71.30	<2.00	<5.00	<0.30	4.46	<0.10
D	do.	454.0	76.30	<2.00	<5.00	<0.34	3.83	<0.10
D	do.	468.0	72.00	<2.00	<5.00	<0.30	9.14	<0.10
D	do.	673.0	71.70	9.21	<5.00	<0.30	5.18	<0.10
D	do.	369.0	73.80	19.70	<5.00	<0.32	1.25	<0.10
D	do.	482.0	71.70	<2.00	<5.00	<0.30	2.57	<0.10
E	Ch. catfish	255.0	75.80	2.23	<5.00	<0.30	<0.50	<0.10
E	Ch. catfish	142.0	72.60	<2.00	<5.00	<0.30	<0.50	<0.10
E	Ch. catfish	170.0	72.30	<2.00	<5.00	<0.30	<0.50	<0.10
E	Carp	198.0	76.40	<5.00	<5.00	<0.30	2.15	<0.10
E	Ch. catfish	198.0	76.50	<2.00	<5.00	<0.30	<0.50	<0.10
E	Ch. catfish	142.0	78.70	<2.00	<5.00	<0.30	<0.50	<0.10
E	Carp	283.0	77.10	38.60	<5.00	<0.30	3.13	<0.10
E	do.	255.0	75.70	<5.00	<5.00	<0.30	2.43	<0.10
E	do.	283.0	75.70	<5.00	<5.00	<0.30	2.47	<0.10
E	do.	224.0	76.50	<5.00	<5.00	<0.30	3.63	<0.10
G	do.	170.0	73.40	<5.00	<5.00	<0.30	2.16	<0.10
G	do.	255.0	75.10	<5.00	<5.00	<0.30	7.16	<0.10
G	Ch. catfish	511.0	68.70	<2.00	<5.00	<0.30	<0.50	<0.10
G	Carp	198.0	72.00	<5.00	<5.00	<0.30	3.91	<0.10
G	Ch. catfish	709.0	72.30	<2.00	<5.00	<0.30	<0.50	<0.10
G	Carp	156.0	74.60	46.00	<5.00	<0.30	4.54	<0.10
G	Carp	198.0	72.50	<5.00	<5.00	<0.30	2.30	<0.10
I	Ch. catfish	198.0	71.00	<2.00	<5.00	<0.30	<0.50	<0.10
I	Ch. catfish	142.0	71.00	13.30	<5.00	<0.30	<0.50	<0.10
I	Ch. catfish	198.0	73.50	<2.00	<5.00	<0.30	<0.50	<0.10
I	Ch. catfish	170.0	71.30	<2.00	<5.00	<0.30	<0.50	<0.10
I	Ch. catfish	170.0	73.10	41.00	<5.00	<0.30	1.29	<0.10

Table 25.--Concentration of selected constituents in individual edible-portion fish samples from the San Juan River: 1990--Continued

River reach	Species	Boron	Cadmium	Chromium	Cobalt	Copper	Iron	Lead
A	Carp	<0.50	<0.150	0.755	<0.500	2.410	55.0	<0.200
A	do.	<0.50	<0.150	0.776	<0.500	2.370	55.1	0.346
A	do.	<0.50	<0.150	0.915	<0.500	2.020	60.5	<0.200
A	do.	0.61	<0.150	0.674	<0.500	3.030	51.0	0.621
A	do.	<0.50	<0.150	0.736	<0.500	3.370	61.0	<0.200
B	do.	<1.50	<0.100	0.515	<0.500	2.240	34.1	<0.200
B	do.	<0.50	<0.100	1.590	<0.500	2.250	46.8	0.255
B	do.	<1.50	<0.100	0.554	<0.500	2.940	54.6	0.598
B	do.	<1.50	<0.100	<0.500	<0.500	2.590	81.3	<0.200
B	do.	0.52	<0.100	1.700	<0.500	3.660	55.0	0.345
D	do.	<0.50	<0.100	0.650	<0.500	3.190	58.8	0.620
D	do.	<0.50	<0.100	1.370	<0.500	2.590	57.5	0.912
D	do.	<0.50	<0.100	1.120	<0.500	2.540	63.7	0.355
D	do.	<0.50	<0.100	0.923	<0.500	3.450	86.0	0.565
D	do.	<0.50	<0.100	1.120	<0.500	2.180	42.7	0.250
E	Ch. catfish	<0.50	<0.100	1.080	<0.500	2.270	19.3	<0.200
E	Ch. catfish	<0.50	<0.100	1.250	<0.500	2.080	19.8	1.110
E	Ch. catfish	<0.50	<0.100	<0.500	1.010	2.110	17.5	0.469
E	Carp	0.70	<0.150	<0.500	0.654	3.230	67.6	0.377
E	Ch. catfish	<0.50	<0.100	<0.500	0.989	5.000	24.0	0.240
E	Ch. catfish	<0.50	<0.100	<0.500	1.550	1.220	22.7	<0.200
E	Carp	5.50	<0.150	0.612	1.040	3.540	139.0	0.239
E	do.	<0.50	0.170	<0.500	0.822	3.170	63.8	<0.200
E	do.	<0.50	<0.150	<0.500	0.874	3.070	89.9	0.525
E	do.	<0.50	0.168	<0.500	0.792	2.770	70.7	0.387
G	do.	<0.50	<0.150	<0.500	0.765	3.680	70.6	0.248
G	do.	0.55	<0.150	<0.500	0.931	1.650	62.3	0.868
G	Ch. catfish	<0.50	<0.100	<0.500	0.833	1.660	18.9	<0.200
G	Carp	<0.50	<0.150	<0.500	0.881	2.630	65.3	<0.200
G	Ch. catfish	<0.50	<0.100	<0.500	0.913	1.680	26.6	0.375
G	Carp	2.56	<0.150	<0.500	0.848	2.960	140.0	0.559
G	Carp	<0.50	<0.150	<0.500	0.549	4.150	77.5	0.268
I	Ch. catfish	0.68	<0.100	<0.500	1.210	1.830	22.0	<0.200
I	Ch. catfish	<0.50	<0.100	<0.500	1.340	0.846	56.4	0.327
I	Ch. catfish	<0.50	<0.100	<0.500	1.170	1.370	21.8	0.404
I	Ch. catfish	<0.50	<0.100	<0.500	0.916	1.590	19.6	0.472
I	Ch. catfish	<0.50	<0.100	<0.500	1.650	2.520	65.1	0.329

Table 25.--Concentration of selected constituents in individual edible-portion fish samples from the San Juan River: 1990--Continued

River reach	Species	Manganese	Mercury	Molybdenum	Nickel	Selenium	Silver	Strontium
A	Carp	0.977	0.814	<0.80	<0.80	3.05	<1.50	8.82
A	do.	1.870	0.890	<0.80	<0.80	4.18	<1.50	29.30
A	do.	1.750	1.290	<0.80	<0.80	2.55	<1.50	12.70
A	do.	3.980	0.924	<0.80	<0.80	3.25	<1.50	73.70
A	do.	1.200	1.040	<0.80	<0.80	3.25	<1.50	9.85
B	do.	3.080	0.527	<0.50	<0.50	3.49	<1.50	45.00
B	do.	3.490	0.381	<0.50	<0.50	2.19	<1.50	76.30
B	do.	3.340	1.050	<0.50	<0.50	3.86	<1.50	50.20
B	do.	2.960	1.170	<0.50	<0.50	4.39	<1.50	21.40
B	do.	5.450	0.656	0.58	<0.50	3.28	<1.50	82.50
D	do.	3.790	0.324	<0.50	<0.50	2.02	<1.50	51.40
D	do.	7.960	0.308	<0.50	<0.50	2.03	<1.50	95.10
D	do.	8.720	0.635	<0.50	<0.50	1.99	<1.50	93.40
D	do.	1.610	0.835	<0.50	<0.50	3.77	<1.50	14.50
D	do.	2.660	0.408	<0.50	<0.50	3.16	<1.50	42.80
E	Ch. catfish	1.260	0.702	<0.50	<0.50	1.03	<1.50	2.04
E	Ch. catfish	2.420	0.359	<0.50	<0.50	1.20	<1.50	5.55
E	Ch. catfish	1.470	0.387	<0.50	<0.50	0.91	<1.50	4.38
E	Carp	2.510	0.980	<0.80	<0.80	3.18	<1.50	26.50
E	Ch. catfish	2.920	0.720	<0.50	<0.50	1.15	<1.50	12.60
E	Ch. catfish	1.180	0.386	<0.50	<0.50	1.38	<1.50	6.40
E	Carp	3.590	0.533	<0.80	<0.80	4.06	<1.50	39.50
E	do.	2.410	0.906	<0.80	<0.80	2.68	<1.50	37.10
E	do.	2.940	0.518	<0.80	<0.80	2.45	<1.50	18.20
E	do.	4.370	1.090	<0.80	<0.80	4.06	<1.50	44.30
G	do.	2.100	0.444	<0.80	<0.80	3.52	<1.50	18.70
G	do.	6.280	0.317	<0.80	<0.80	4.93	<1.50	83.60
G	Ch. catfish	0.659	0.516	<0.50	<0.50	0.54	<1.50	0.78
G	Carp	3.460	0.885	<0.80	<0.80	3.89	<1.50	57.40
G	Ch. catfish	1.450	1.350	<0.50	<0.50	1.41	<1.50	11.90
G	Carp	4.570	0.580	<0.80	<0.80	5.71	<1.50	53.40
G	Carp	2.470	0.372	<0.80	<0.80	3.28	<1.50	25.30
I	Ch. catfish	1.350	0.945	<0.50	0.68	1.05	<1.50	4.21
I	Ch. catfish	3.420	0.369	<0.50	<0.50	1.24	<1.50	8.03
I	Ch. catfish	2.670	0.727	<0.50	<0.50	1.12	<1.50	11.70
I	Ch. catfish	1.850	0.328	<0.50	<0.50	1.28	<1.50	14.80
I	Ch. catfish	6.370	0.563	<0.50	<0.50	1.60	<1.50	29.80

Table 25.--Concentration of selected constituents in individual edible-portion fish samples from the San Juan River: 1990--Concluded

River reach	Species	Tin	Vanadium	Zinc
A	Carp	<5.00	<0.50	89.00
A	do.	<5.00	<0.50	70.60
A	do.	<5.00	<0.50	94.30
A	do.	<5.00	<0.50	117.00
A	do.	<5.00	<0.50	102.00
B	do.	<5.00	<0.50	50.30
B	do.	<6.00	<0.50	93.60
B	do.	<5.00	<0.50	83.20
B	do.	<5.00	<0.50	60.90
B	do.	<6.00	<0.50	87.90
D	do.	<6.00	<0.50	66.90
D	do.	<6.00	<0.50	105.00
D	do.	<6.00	<0.50	63.00
D	do.	<6.00	<0.50	69.40
D	do.	<6.00	<0.50	71.60
E	Ch. catfish	<6.00	<0.50	49.60
E	Ch. catfish	<6.00	<0.50	35.60
E	Ch. catfish	<6.00	< 0.50	37.50
E	Carp	<5.00	0.59	77.90
E	Ch. catfish	<6.00	<0.50	62.60
E	Ch. catfish	<6.00	<0.50	35.70
E	Carp	<5.00	<0.50	115.00
E	do.	<5.00	<0.50	70.10
E	do.	<5.00	<0.50	56.30
E	do.	<5.00	<0.50	87.00
G	do.	<5.00	<0.50	66.90
G	do.	<5.00	0.51	94.50
G	Ch. catfish	<6.00	<0.50	20.50
G	Carp	<5.00	0.84	100.00
G	Ch. catfish	<6.00	<0.50	44.40
G	Carp	<5.00	0.50	83.00
G	Carp	9.39	<0.50	91.50
I	Ch. catfish	<6.00	<0.50	41.30
I	Ch. catfish	<6.00	<0.50	42.80
I	Ch. catfish	<6.00	<0.50	30.70
I	Ch. catfish	<6.00	<0.50	27.30
I	Ch. catfish	<6.00	<0.50	70.10

Table 26.--Concentrations of selected constituents in livers
and kidneys of bird samples: spring 1990

[Site number, see fig. 7 and table 3; concentrations are in micrograms per gram, dry weight; I/C, individual or composite sample--number in parentheses is number in composite sample; species: G.W. teal, green-winged teal; R.W. blackbird, red-winged blackbird; Y.H. blackbird, yellow-headed blackbird; <, less than]

Site number	Date	Species	I/C	Weight (grams)	Magnesium (Mg)	Aluminum (Al)	Antimony (Sb)
Adult birds							
I-1,2,3	05-22-90	Mallard	I	38.5	580	<2.00	<5.00
I-1,2,3	05-22-90	Mallard	I	29.5	675	<2.00	<5.00
I-1,2,3	06-07-90	G.W. teal	I	16.0	764	<2.00	<5.00
I-1,2,3	06-12-90	Coot	I	15.0	770	<2.00	<5.00
I-1,2,3	06-07-90	Killdeer	C(3)	10.7	893	<2.00	<5.00
I-1,2,3	06-07-90	R.W. blackbird	C(6)	14.0	822	9.71	<5.00
I-6	05-21-90	Mallard	I	29.0	767	<2.00	<5.00
I-6	05-21-90	Mallard	I	29.0	916	<2.00	<5.00
I-6	06-05-90	Killdeer	C(3)	12.0	777	<2.00	<5.00
I-6	06-05-90	Y.H. blackbird	C(3)	12.0	853	2.45	<5.00
I-9	05-23-90	Mallard	I	33.0	801	3.02	<5.00
I-9	06-05-90	Avocet	I	10.0	946	13.9	<5.00
I-9	06-05-90	Avocet	I	11.0	841	22.0	<5.00
I-10	05-23-90	Mallard	I	33.0	612	<2.00	<5.00
I-10	05-24-90	Mallard	I	27.0	899	3.61	<5.00
I-10	06-12-90	Coot	I	30.0	648	<2.00	<5.00
I-10	06-12-90	Coot	I	16.0	749	<2.00	<5.00
I-10	06-05-90	Avocet	I	11.0	973	26.3	<5.00
I-10	06-05-90	Avocet	I	12.0	816	6.11	<5.00
I-10	06-05-90	Avocet	I	13.0	775	<2.00	<5.00
I-10	06-05-90	Killdeer	C(2)	9.0	844	5.25	<5.00
I-10	06-05-90	Killdeer	C(2)	9.0	940	<2.00	<5.00

Table 26.--Concentrations of selected constituents in livers
and kidneys of bird samples: spring 1990--Continued

Site number	Arsenic (As)	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Chromium (Cr)	Cobalt (Co)	Copper (Cu)
Adult birds								
I-1,2,3	<0.3	<5.00	<0.100	4.83	1.27	0.662	<0.500	91.6
I-1,2,3	<.3	<.500	<.100	3.01	3.51	.511	<.500	140
I-1,2,3	<.3	<.500	<.100	.726	.647	<.500	<.500	69.9
I-1,2,3	<.3	<.500	<.100	5.59	1.25	1.73	<.500	31.8
I-1,2,3	<.3	<.500	<.100	1.76	4.80	.573	<.500	22.8
I-1,2,3	.309	<.500	<.100	1.19	1.18	<.500	<.500	22.7
I-6	<.3	<.500	<.100	2.63	6.00	.624	<.500	70.2
I-6	.329	.518	<.100	3.54	1.98	.726	<.500	62.9
I-6	<.3	<.500	<.100	.997	2.67	.931	<.500	23.6
I-6	<.3	<.500	.378	1.19	.815	1.11	<.500	30.0
I-9	<.3	<.500	<.100	2.51	2.60	.705	<.500	66.6
I-9	<.3	6.31	.842	5.06	9.33	1.77	1.44	19.4
I-9	<.3	4.67	<.100	7.33	13.6	.851	<.500	17.5
I-10	<.3	.581	<.100	2.36	2.40	<.500	<.500	43.9
I-10	<.3	.797	<.100	5.36	3.07	.809	<.500	24.6
I-10	.356	.542	<.100	2.37	6.80	.647	<.500	11.4
I-10	.329	2.84	<.100	4.81	.305	.582	<.500	38.0
I-10	.308	1.47	<.100	3.65	11.7	44.6	<.500	29.8
I-10	<.3	3.16	<.100	3.42	6.86	1.94	<.500	20.9
I-10	<.3	11.0	<.100	2.52	6.38	.634	<.500	20.9
I-10	<.3	1.02	<.100	1.18	3.97	.529	<.500	18.2
I-10	<.3	1.29	<.100	.914	3.55	.553	<.500	21.2

Table 26.--Concentrations of selected constituents in livers
and kidneys of bird samples: spring 1990--Continued

Site number	Iron (Fe)	Lead (Pb)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)	Nickel (Ni)
Adult birds						
I-1,2,3	6,220	0.265	12.8	0.409	8.60	<0.800
I-1,2,3	3,470	.280	13.3	.427	3.09	<.800
I-1,2,3	749	<.2	12.6	.908	3.27	<.800
I-1,2,3	6,530	.337	12.8	.103	10.4	<.800
I-1,2,3	1,710	<.2	19.3	1.28	4.15	<.800
I-1,2,3	1,350	<.2	7.10	.185	3.32	<.800
I-6	3,400	.289	14.8	.881	2.36	<.800
I-6	3,760	.319	34.8	1.56	3.56	<.800
I-6	722	<.2	16.8	1.25	3.59	<.800
I-6	1,430	<.2	8.41	.657	3.27	<.800
I-9	3,170	.314	17.7	.236	3.65	<.800
I-9	4,920	<.2	22.2	.704	4.97	4.31
I-9	3,350	.428	18.9	1.33	3.01	<.800
I-10	2,400	.216	11.3	.151	2.27	<.800
I-10	6,720	.781	17.0	.379	6.29	<.800
I-10	1,490	<.2	7.72	.363	3.77	<.800
I-10	528	.240	20.3	.362	2.02	<.800
I-10	4,400	.992	18.7	1.18	3.94	<.800
I-10	3,630	.250	19.1	1.27	5.13	<.800
I-10	2,760	.288	14.6	1.42	3.11	<.800
I-10	960	<.2	14.0	.567	2.57	<.800
I-10	905	.499	15.6	.738	2.82	<.800

Table 26.--Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990--Continued

Site number	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
Adult birds					
I-1,2,3	23.0	0.639	<5.00	<0.500	92.9
I-1,2,3	19.7	.669	<5.00	<.500	96.0
I-1,2,3	39.3	<.500	<5.00	<.500	104
I-1,2,3	21.6	1.28	<5.00	<.500	136
I-1,2,3	103	.612	<5.00	<.500	99.7
I-1,2,3	42.9	.635	<5.00	<.500	83.4
I-6	25.0	.601	<5.00	<.500	126
I-6	16.0	4.91	<5.00	<.500	189
I-6	31.2	<.500	<5.00	<.500	84.8
I-6	14.1	7.37	<5.00	<.500	93.3
I-9	22.0	<.500	<5.00	<.500	118
I-9	12.5	1.51	<5.00	1.69	133
I-9	15.3	2.28	<5.00	.985	104
I-10	2.84	<.500	<5.00	<.500	96.4
I-10	12.5	.879	<5.00	<.500	120
I-10	2.74	.681	<5.00	.607	88.9
I-10	5.93	16.0	<5.00	.529	114
I-10	9.34	1.63	<5.00	.544	144
I-10	20.3	.822	<5.00	<.500	119
I-10	19.5	2.34	<5.00	<.500	124
I-10	10.8	1.00	<5.00	<.500	80.7
I-10	16.4	1.49	<5.00	<.500	87.6

Table 26.--Concentrations of selected constituents in livers
and kidneys of bird samples: spring 1990--Continued

Site number	Date	Species	I/C	Weight (grams)	Magnesium (Mg)	Aluminum (Al)	Antimony (Sb)	Arsenic (As)
Adult birds								
I-10	06-12-90	Blackbird	C(7)	9.0	856	<2.00	<5.00	<0.3
I-12	06-05-90	Mallard	I	39.0	730	<2.00	<5.00	<.3
I-16	06-08-90	Cinnamon teal	I	15.0	820	6.55	<5.00	<.3
I-16	06-08-90	Killdeer	C(3)	12.0	873	<2.00	<5.00	.667
I-17	06-08-90	Cinnamon teal	I	19.0	808	<2.00	<5.00	<.3
I-17	06-08-90	Cinnamon teal	I	10.0	759	<2.00	<5.00	<.3
I-17	06-08-90	Killdeer	I	12.0	863	<2.00	<5.00	<.3
I-17	06-08-90	Killdeer	C(2.5)	9.50	827	4.55	<5.00	<.3
I-17	06-08-90	R.W. blackbird	C(4)	8.0	880	<2.00	<5.00	<.3
I-20	06-12-90	Mallard	I	32.0	863	<2.00	<5.00	.483
I-20	06-12-90	Mallard	I	66.0	429	<2.00	<5.00	<.3
I-20	06-12-90	R.W. blackbird	C(6)	12.0	786	<2.00	<5.00	<.3
I-21	06-13-90	Mallard	I	34.0	685	8.72	<5.00	<.3
I-21	06-14-90	Cinnamon teal	I	13.5	784	41.4	<5.00	<.3
I-21	06-14-90	Cinnamon teal	I	16.0	852	4.01	<5.00	<.3
I-21	06-14-90	Cinnamon teal	I	20.0	875	3.06	<5.00	<.3
I-21	06-13-90	Killdeer	C(3)	12.0	798	15.2	<5.00	<.3
I-21	06-13-90	R.W. blackbird	C(5)	12.0	816	14.9	<5.00	<.3
I-23	06-06-90	Coot	I	15.0	798	21.8	<5.00	<.3
I-23	06-06-90	Coot	I	17.0	663	6.69	<5.00	.586
I-23	06-06-90	Coot	I	11.0	550	6.11	<5.00	<.3
I-23	06-06-90	Coot	I	9.0	751	7.14	<5.00	.338
I-23	06-06-90	Coot	I	17.0	863	14.1	<5.00	.325
I-23	06-06-90	R.W. blackbird	C(6)	9.0	869	3.26	<5.00	<.3

Table 26.--Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990--Continued

Site number	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Chromium (Cr)	Cobalt (Co)	Copper (Cu)
Adult birds							
I-10	<0.500	<0.100	2.47	0.766	0.611	<0.500	24.5
I-12	<.500	<.100	2.78	3.01	.810	<.500	30.8
I-16	<.500	<.100	1.50	5.45	<.500	<.500	59.2
I-16	<.500	<.100	<.500	5.07	<.500	<.500	25.2
I-17	<.500	<.100	<.500	2.37	<.500	<.500	42.1
I-17	<.500	<.100	2.21	9.27	.733	<.500	227
I-17	.504	<.100	<.500	1.53	<.500	<.500	24.4
I-17	<.500	<.100	<.500	1.48	<.500	<.500	22.6
I-17	<.500	<.100	.779	.743	<.500	<.500	27.8
I-20	.500	<.100	2.89	3.44	.586	<.500	137
I-20	<.500	<.100	1.42	.903	<.500	<.500	264
I-20	<.500	<.100	1.00	1.24	<.500	<.500	24.8
I-21	.759	.544	2.72	6.17	.985	.760	200
I-21	.666	<.100	6.58	2.12	.793	<.500	89.8
I-21	<.500	<.100	5.68	2.16	.650	<.500	28.9
I-21	.687	<.100	2.34	2.02	.686	<.500	17.3
I-21	.858	<.100	1.19	10.3	<.500	.629	24.0
I-21	<.500	<.100	1.65	1.32	.536	<.500	24.8
I-23	.933	<.100	6.47	.414	.780	<.500	57.8
I-23	<.500	<.100	3.44	.619	.545	<.500	34.2
I-23	<.500	<.100	2.58	.421	<.500	<.500	19.6
I-23	.910	<.100	9.72	.238	.882	<.500	32.7
I-23	1.43	<.100	10.2	.680	1.08	<.500	54.0
I-23	<.500	<.100	1.07	1.16	<.500	.611	12.7

Table 26.--Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990--Continued

Site number	Iron (Fe)	Lead (Pb)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)
Adult birds					
I-10	2,690	0.229	6.18	0.524	4.02
I-12	2,620	.246	15.5	1.15	3.76
I-16	2,550	.346	32.0	1.78	3.10
I-16	904	<.5	28.4	1.32	2.72
I-17	851	.336	25.9	1.13	2.36
I-17	2,750	.269	18.7	2.69	8.35
I-17	607	.329	20.6	1.05	2.20
I-17	792	<.2	18.0	1.60	2.82
I-17	977	<.2	7.12	.401	3.29
I-20	1,980	.385	28.9	1.66	4.37
I-20	920	<.2	10.7	<.02	1.87
I-20	974	<.5	5.83	.144	2.60
I-21	2,100	1.08	13.1	.930	4.40
I-21	8,790	.966	19.7	1.78	7.05
I-21	4,990	.615	11.0	.320	3.20
I-21	1,110	.490	14.7	.144	2.47
I-21	771	1.11	17.6	.858	3.20
I-21	1,300	.778	7.58	.224	2.95
I-23	5,900	.856	20.2	.133	2.74
I-23	3,660	1.11	16.8	.233	3.35
I-23	1,240	.464	24.5	<.02	1.35
I-23	10,500	.606	17.7	.0849	6.72
I-23	13,100	.947	71.3	.0320	7.66
I-23	800		8.07	<.02	3.05

Table 26.--Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990--Continued

Site number	Nickel (Ni)	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
Adult birds						
I-10	<0.800	9.54	1.70	<5.00	<0.500	77.8
I-12	<.800	17.9	.611	<5.00	<.500	133
I-16	<.800	8.98	1.68	<5.00	<.500	113
I-16	<.800	15.1	1.20	<5.00	<.500	94.6
I-17	<.800	7.68	2.32	<5.00	<.500	85.0
I-17	<.800	26.4	.666	<5.00	<.500	141
I-17	<.800	14.4	2.14	<5.00	<.500	88.5
I-17	<.800	19.2	4.32	<5.00	<.500	90.5
I-17	<.800	11.2	<.500	<5.00	<.500	86.5
I-20	<.800	25.9	.974	<5.00	<.500	124
I-20	<.800	3.82	<.500	<.500	<.500	70.5
I-20	<.800	4.80	.928	<5.00	<.500	79.9
I-21	2.75	15.9	.830	<5.00	.505	126
I-21	<.800	16.4	1.39	<5.00	<.500	115
I-21	<.800	12.4	<.500	<5.00	<.500	101
I-21	<.800	20.8	1.39	<5.00	<.500	93.1
I-21	<.800	22.7	.906	<5.00	<.500	116
I-21	<.800	6.49	.922	<5.00	<.500	83.8
I-23	<.800	5.92	1.50	<5.00	.761	174
I-23	<.800	12.0	.711	<5.00	2.31	124
I-23	<.800	3.83	1.08	<5.00	<.500	195
I-23	<.800	4.12	.753	<5.00	.520	273
I-23	<.800	9.47	4.21	<5.00	.869	154
I-23	<.800	8.94	1.48	<5.00	<.500	92.6

Table 26.--Concentrations of selected constituents in livers
and kidneys of bird samples: spring 1990--Continued

Site number	Date	Species	I/C	Weight (grams)	Aluminum (Al)	Antimony (Sb)	Arsenic (As)
Juvenile birds							
I-6	06-05-90	Mallard	C(2)	7.3	6.11	<5.00	<0.3
I-9	06-05-90	Mallard	C(2)	8.0	8.91	<5.00	<.3
I-10	06-05-90	Mallard	C(2)	25.0	28.2	<5.00	<.3
I-10	06-05-90	Mallard	I	29.0	46.8	<5.00	<.3
Eggs							
I-6	06-05-90	Mallard	I	30.0	<2.00	<5.00	<0.3
I-9	06-05-90	Avocet	I	26.5	<2.00	<5.00	<.3
I-10	06-05-90	Avocet	I	26.4	<2.00	<5.00	<.3
I-10	06-05-90	Avocet	C(2)	9.0	<2.00	<5.00	<.3
I-11	06-05-90	Avocet	I	27.8	<2.00	<5.00	<.3
I-12	06-13-90	Avocet	C(2)	43.0	<2.00	<5.00	<.3
I-16	06-11-90	Killdeer	C(2)	8.0	<2.00	<5.00	<.3
I-17	06-08-90	Killdeer	I	5.0	<2.00	<5.00	<.3
I-21	06-14-90	Cinnamon Teal	C(3)	18.5	<2.00	<5.00	<.3
I-23	06-06-90	Coot	I	23.0	<2.00	<5.00	<.3
I-23	06-06-90	Coot	I	22.5	<2.00	<5.00	<.3
I-23	06-06-90	Coot	I	20.7	<2.00	<5.00	<.3
I-23	06-06-90	Coot	I	22.7	<2.00	<5.00	<.3

Table 26.—Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990—Continued

Site number	Barium (Ba)	Beryllium (Be)	Boron (B)	Cadmium (Cd)	Chromium (Cr)	Cobalt (Co)	Copper (Cu)
Juvenile birds							
I-6	0.545	<0.100	1.22	0.105	0.671	<0.500	46.9
I-9	1.23	<.100	1.66	<.100	.827	<.500	12.1
I-10	4.18	<.100	1.25	<.100	.686	<.500	19.2
I-10	1.53	<.100	3.42	<.100	.657	<.500	11.2
Eggs							
I-6	12.9	<0.100	0.855	<0.100	<0.500	<0.500	4.71
I-9	43.6	<.100	2.57	<.100	.954	<.500	4.82
I-10	5.52	<.100	.789	<.100	<.500	<.500	5.03
I-10	48.4	<.100	.866	<.100	.633	<.500	3.21
I-11	25.3	<.100	1.40	<.100	<.500	<.500	4.08
I-12	8.47	<.100	1.14	<.100	<.500	<.500	4.33
I-16	6.67	<.100	<.500	<.100	1.30	<.500	1.60
I-17	4.33	<.100	1.14	<.100	<.500	<.500	3.48
I-21	16.0	<.100	.892	<.100	<.500	<.500	4.66
I-23	3.90	<.100	2.24	<.100	<.500	<.500	4.46
I-23	6.91	<.100	1.98	<.100	<.500	<.500	4.26
I-23	1.29	<.100	1.40	<.100	<.500	<.500	4.80
I-23	5.16	<.100	1.45	<.100	<.500	<.500	3.80

Table 26.--Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990--Continued

Site number	Iron (Fe)	Lead (Pb)	Magnesium (Mg)	Manganese (Mn)	Mercury (Hg)	Molybdenum (Mo)
Juvenile birds						
I-6	715	<0.2	1,050	20.3	0.348	2.34
I-9	1,700	<.2	977	16.7	.446	3.14
I-10	1,300	.273	991	20.1	.0398	3.25
I-10	3,610	.445	924	18.7	.164	4.21
Eggs						
I-6	127	<0.2	516	4.73	0.345	<0.800
I-9	163	.349	521	3.22	.407	<.800
I-10	119	<.2	484	2.26	.399	<.800
I-10	189	<.2	306	3.65	<.02	<.800
I-11	135	.332	475	1.58	.311	<.800
I-12	161	<.2	420	2.95	.449	<.800
I-16	138	<.2	305	4.47	<.02	<.800
I-17	187	<.2	553	2.77	<.02	<.800
I-21	237	<.2	246	6.06	<.02	<.800
I-23	149	.620	680	3.30	<.02	<.800
I-23	116	<.2	800	2.96	<.02	<.800
I-23	85.4	<.2	613	7.56	.0884	1.20
I-23	123	<.2	588	6.22	.0699	<.800

Table 26.--Concentrations of selected constituents in livers and kidneys of bird samples: spring 1990--Concluded

Site number	Nickel (Ni)	Selenium (Se)	Strontium (Sr)	Tin (Sn)	Vanadium (V)	Zinc (Zn)
Juvenile birds						
I-6	<0.800	28.2	2.47	<5.00	<0.500	118
I-9	<.800	5.79	1.22	<5.00	<.500	104
I-10	<.800	21.4	8.12	<5.00	<.500	161
I-10	<.800	9.83	1.69	<5.00	<.500	119
Eggs						
I-6	<0.800	17.6	79.0	<5.00	<0.500	66.0
I-9	<.800	2.64	26.0	<5.00	<.500	62.0
I-10	<.800	3.63	19.7	<5.00	<.500	46.4
I-10	<.800	2.95	22.2	<5.00	<.500	68.1
I-11	<.800	3.76	12.6	<5.00	<.500	47.8
I-12	<.800	2.91	17.4	<5.00	<.500	60.2
I-16	<.800	2.77	15.9	<.500	<.500	51.7
I-17	<.800	2.08	60.1	<.500	<.500	68.4
I-21	<.800	4.83	23.0	<5.00	<.500	93.7
I-23	<.800	2.37	34.3	<.500	<.500	81.1
I-23	<.800	2.48	43.1	<.500	<.500	77.5
I-23	<.800	1.87	13.5	<.500	<.500	60.9
I-23	<.800	1.65	23.8	<.500	<.500	64.3

Table 27.—Concentrations of pesticides in water and bottom-sediment samples: 1990

[Site number: see fig. 7 and table 3; $\mu\text{g/L}$, micrograms per liter; tot rec, total recoverable; $\mu\text{g/kg}$, micrograms per kilogram; <, less than; --, not determined]

Site number	Date	Time	Ala-chlor, total recoverable ($\mu\text{g/L}$) (77825)		Ame-tryne total ($\mu\text{g/L}$) (39630)		Cyan-azine total ($\mu\text{g/L}$) (81757)		Metola-chlor, water, whole, tot rec ($\mu\text{g/L}$) (82612)		Metri-buzin, water, whole, tot rec ($\mu\text{g/L}$) (39056)		Prome-tryne total ($\mu\text{g/L}$) (39057)		Propa-zine total ($\mu\text{g/L}$) (39024)		Sima-zine total ($\mu\text{g/L}$) (39055)		Sime-tryne total ($\mu\text{g/L}$) (39054)		Tri-fluralin, total rec ($\mu\text{g/L}$) (39030)		
			<	total	<	total	<	total	<	total	<	total	<	total	<	total	<	total	<	total	<	total	<
I-1	06-19-90	1600	<0.10	<0.10	4.9	2.3	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-2	05-17-90	1000	<0.10	<0.10	1.0	0.10	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-4	05-17-90	1100	<0.10	<0.10	1.0	0.10	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-6	06-19-90	1330	<0.10	<0.10	0.10	<0.10	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-8	06-20-90	0900	<0.10	<0.10	0.10	<0.10	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-8	06-20-90	0910	<0.10	<0.10	0.10	<0.10	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-10	06-19-90	1200	<0.10	<0.10	0.10	<0.10	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-13	06-19-90	0930	<0.10	<0.10	<0.10	<0.10	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.10	<0.1	<0.1	<0.1	<0.10	<0.1

Triazine herbicides in water

Table 27.--Concentrations of pesticides in water and bottom-sediment samples: 1990--Continued

Site number	Date	Time	2,4-D, 2,4-DP, 2,4,5-T, total (µg/L)		Dicamba (Mediben) (Banvel D), total (µg/L)		Picloram (Torodon) (Amdon), total (µg/L)		Silvex, total (µg/L)
			(39730)	(82183)	(39740)	(82052)	(39720)	(39760)	
Chlorophenoxy acid herbicides in water									
I-1	06-19-90	1600	0.02	<0.01	<0.01	0.12	<0.01	<0.01	<0.01
I-2	05-17-90	1000	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-4	05-17-90	1100	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-6	06-19-90	1330	0.03	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-8	06-20-90	0900	0.02	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-8	06-20-90	0910	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
I-10	06-19-90	1200	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10
I-13	06-19-90	0930	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10	<0.10

Table 27.--Concentrations of pesticides in water and bottom-sediment samples: 1990--Continued

Site number	Date	Time	Carbamate insecticides in water				Aldi-carb sulfone (µg/L)	Aldi-carb sulfide (µg/L)	Carbo-furan, total (µg/L)	3-hydroxy-carbo-furan, total (µg/L)	1-naphthol, total (µg/L)	Oxamyl, total (µg/L)
			Carb-aryl (Sevin) (µg/L)	Metho-myl (µg/L)	Pro-pham (µg/L)	Aldi-carb (µg/L)						
I-1	08-06-90	0800	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	
	08-06-90	0805	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	
I-2	08-04-90	1700	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	
I-3	08-22-90	0900	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	
I-4	08-06-90	0900	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	
I-7	08-05-90	1000	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	
I-12	08-21-90	1300	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	
I-13	08-05-90	1200	<0.50	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	

Table 27.--Concentrations of pesticides in water and bottom-sediment samples: 1990--Continued

Site number	Date	Time	Chloropyrifos, total ($\mu\text{g/L}$) (39040)	Def, total ($\mu\text{g/L}$) (39011)	Disys-ton, total ($\mu\text{g/L}$) (39570)	Diazinon, total ($\mu\text{g/L}$) (82614)	Fonofos (Dyfonate), total ($\mu\text{g/L}$) (39398)	Mala-thion, total ($\mu\text{g/L}$) (39530)	Methyl para-thion, total ($\mu\text{g/L}$) (39600)	Methyl thi-on, total ($\mu\text{g/L}$) (39540)	Phor-ate, total ($\mu\text{g/L}$) (39023)	Ethyl tri-thion, total ($\mu\text{g/L}$) (39786)
Organophosphate compound insecticides in water												
I-1	08-06-90	0800	--	<0.01	<0.01	--	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
	08-06-90	0805	--	<0.01	<0.01	--	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-2	08-04-90	1700	--	<0.01	<0.01	--	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-3	08-22-90	0900	<0.01	<0.01	<0.01	0.0	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-4	08-06-90	0900	--	<0.01	<0.01	--	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-7	08-05-90	1000	--	<0.01	<0.01	--	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01
I-12	08-21-90	1300	<0.01	<0.01	<0.01	0.0	<0.01	<0.01	0.14	<0.01	0.61	<0.01
I-13	08-05-90	1200	<0.01	<0.01	<0.01	0.0	<0.01	<0.01	<0.01	<0.01	<0.01	<0.01

Table 27.--Concentrations of pesticides in water and bottom-sediment samples: 1990--Continued

Site number	Date	Time	Chlor-dane, total		DDD, total		DDE, total		DDT, total		Di-eldrin, total		Endo-sulfan, total		Hepta-chlor, total	
			in bot-tom ma-terial (µg/kg) (39333)	in bot-tom ma-terial (µg/kg) (39351)	in bot-tom ma-terial (µg/kg) (39363)	in bot-tom ma-terial (µg/kg) (39368)	in bot-tom ma-terial (µg/kg) (39373)	in bot-tom ma-terial (µg/kg) (39383)	in bot-tom ma-terial (µg/kg) (39389)	in bot-tom ma-terial (µg/kg) (39413)						
Organochlorine compound pesticides in bottom sediment																
I-1	12-03-90	1000	<0.1	<1.0	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-2	11-07-90	1600	<0.1	<1.0	<0.1	0.4	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-7	11-08-90	1000	<0.1	<1.0	<0.1	0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-7	11-08-90	1000	<0.1	<1.0	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-17	11-07-90	1000	<0.1	<1.0	<0.1	0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-20	11-07-90	1300	<0.1	<1.0	0.2	0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-21	11-06-90	0900	<0.1	1.0	0.1	0.3	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-22	11-06-90	1600	<0.1	1.0	0.1	0.2	0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-23	11-06-90	1400	<0.1	1.0	0.2	0.3	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1
I-24	12-02-90	1030	<0.1	2.0	0.1	0.4	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1

Table 27.--Concentrations of pesticides in water and bottom-sediment samples: 1990--Concluded

Site number	Date	Hepta-chlor epoxide, total in bottom material (µg/kg) (39423)	Lindane total in bottom material (µg/kg) (39343)	Methoxy-chlor, total in bottom material (µg/kg) (39481)	Mirex, total in bottom material (µg/kg) (39758)	PCB, total in bottom material (µg/kg) (39519)	PCN, total in bottom material (µg/kg) (39251)	Perthane in bottom material (µg/kg) (81886)	Toxaphene, total in bottom material (µg/kg) (39403)
Organochlorine compound pesticides in bottom sediment									
I-1	12-03-90	<0.1	<0.1	<1.0	<0.1	<1	<1.0	<1.00	<10
I-2	11-07-90	<0.1	<0.1	<1.0	<0.1	<1	<1.0	<1.00	<10
I-7	11-08-90	<0.1	<0.1	<0.1	<0.1	<1	<1.0	<1.00	<10
I-7	11-08-90	<0.1	<0.1	<0.1	<0.1	<1	<1.0	<1.00	<10
I-17	11-07-90	<0.1	<0.1	<0.1	<0.1	<1	<1.0	<1.00	<10
I-20	11-07-90	<0.1	<0.1	<0.1	<0.1	<1	<1.0	<1.00	<10
I-21	11-06-90	<0.1	<0.1	<0.1	<0.1	<1	<1.0	<1.00	<10
I-22	11-06-90	<0.1	<0.1	<0.1	<0.1	<1	<1.0	<1.00	<10
I-23	11-06-90	<0.1	<0.1	<0.1	<0.1	<1	<1.0	<1.00	<10
I-24	12-02-90	<0.1	<0.1	<1.0	<0.1	<1	<1.0	<1.00	<10

Table 28.--Concentrations of organochlorine compounds in composite whole-body flannelmouthed sucker samples: 1990

[River reach, see fig. 8 and table 4; number of individual fish in composite sample; concentrations are in micrograms per gram wet weight; ND, nondetected]

River reach	Weight (grams)	Number of fish	Moisture (percent)	Lipid (percent)	Percent		HCB	a-BHC	r-BHC	b-BHC	s-BHC	Oxychlor-dane		Hepta-chlor epoxide		r-Chlordane	t-Nonachlor	Toxa-PCB's, o,p'-DDE	
					HC	a-BHC						r-BHC	b-BHC	s-BHC	o,p'-DDE				Hepta-chlor epoxide
A	3,220	5	68.0	13.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
C	5,273	5	71.0	10.7	ND	ND	ND	ND	ND	ND	ND	ND	0.01	0.02	ND	ND	ND	0.16	ND
D	4,691	5	66.5	15.1	ND	ND	ND	ND	ND	ND	ND	ND	0.01	0.02	ND	ND	ND	0.21	ND
E	3,261	5	70.0	12.1	ND	ND	ND	ND	ND	ND	ND	ND	0.01	0.02	ND	ND	ND	0.20	ND
F	3,218	5	65.5	16.5	ND	ND	ND	ND	ND	ND	ND	ND	0.01	0.01	ND	ND	ND	0.17	ND
G	3,444	5	66.5	14.2	ND	ND	ND	ND	ND	ND	ND	ND	0.01	0.01	ND	ND	ND	0.14	ND

River reach	a-Chlor-dane	p,p'-DDE	Dieldrin	o,p'-DDD	Endrin	Cis-Nonachlor	o,p'-DDT	p,p'-DDD	p,p'-DDT	Mirex
A	ND	0.02	ND	ND	ND	ND	ND	ND	ND	ND
C	0.02	0.08	ND	ND	ND	ND	ND	0.02	0.02	ND
D	0.03	0.06	ND	ND	ND	ND	ND	0.02	0.02	ND
E	0.02	0.07	ND	ND	ND	ND	ND	0.02	0.02	ND
F	0.02	0.04	ND	ND	ND	ND	ND	0.02	0.01	ND
G	0.02	0.03	ND	ND	ND	ND	ND	0.01	0.01	ND

Table 29.--Concentrations of organochlorine compounds in individual bird carcass samples: 1990

[Site number, see fig. 7 and table 3; species: Cassin's k-bird, Cassin's kingbird; Y.H. blackbird, yellow-headed blackbird; Eastern k-bird, eastern kingbird; ND, nondetected; concentrations are in micrograms per gram wet weight]

Site number	Species	Weight (grams)	Percent moisture	Lipid (percent)	HCB	a-BHC	r-BHC	b-BHC	s-BHC	Oxychlor-dane	Hepta-chlor epoxide	r-Chlor-dane	t-Non-achlor	Toxa-phene
I-1,2,3	Killdeer	38.0	70.0	2.74	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-1,2,3	do.	39.0	70.5	3.66	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-1,2,3	do.	40.0	70.5	3.68	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-16	do.	50.0	71.0	2.16	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-16	do.	44.0	67.5	7.70	ND	ND	ND	ND	0.01	ND	ND	ND	ND	ND
I-17	do.	47.0	72.2	1.78	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-17	do.	40.0	71.0	4.28	ND	ND	ND	ND	0.01	ND	ND	ND	ND	ND
I-19	Cassin's k-bird	18.0	68.0	4.32	ND	ND	ND	ND	0.01	ND	ND	ND	0.01	ND
I-17	Cassin's k-bird	20.0	72.0	2.32	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-6	Mallard duckling	32.0	76.5	3.06	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-6	Mallard duckling	23.0	80.5	2.00	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-6	Killdeer	40.0	71.0	3.68	ND	ND	ND	ND	0.01	ND	0.01	ND	ND	ND
I-6	Killdeer	39.0	69.5	4.68	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-6	Killdeer	35.0	71.5	2.74	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-6	Y.H. blackbird	10.0	78.5	3.08	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-9	Mallard duckling	14.0	75.5	2.36	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-10	Mallard duckling	82.0	77.0	1.42	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-10	Mallard duckling	84.0	79.5	1.58	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-10	Mallard duckling	101.0	77.0	1.98	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-9	Mallard duckling	14.0	78.0	1.75	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-10	Killdeer	41.0	68.0	5.78	0.01	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-10	Killdeer	42.0	71.2	4.16	ND	ND	ND	ND	0.01	ND	0.01	ND	ND	ND
I-10	Killdeer	47.0	70.8	3.28	0.01	ND	ND	0.01	ND	0.01	ND	ND	ND	ND
I-9,10,11,12	Cassin's k-bird	19.0	71.6	2.22	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Table 29.—Concentrations of organochlorine compounds in individual bird carcass samples: 1990—Continued

Site number	Species	Weight (grams)	Percent moisture	Lipid (percent)	HCB	a-BHC	r-BHC	b-BHC	s-BHC	Oxychlor-dane	Heptachlor epoxide	r-Chlor-dane	t-Nonachlor	Toxaphene
I-9,10,11,12	Cassin's k-bird	20.0	72.6	2.78	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-9,10,11,12	Cassin's k-bird	20.0	70.8	4.24	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-9,10,11,12	Cassin's k-bird	18.0	72.0	2.36	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-10	Coot	149.0	72.8	3.14	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-21	Killdeer	48.0	70.2	3.24	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-21	Killdeer	42.0	70.8	4.46	ND	ND	ND	ND	ND	0.01	ND	ND	ND	ND
I-21	Killdeer	42.0	68.8	4.42	ND	ND	ND	ND	ND	0.01	ND	ND	ND	ND
I-21	Cassin's k-bird	18.0	69.5	4.10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-21	Eastern k-bird	21.0	69.5	4.45	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-23	Eastern k-bird	20.0	72.5	2.25	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
I-23	Eastern k-bird	21.0	66.5	2.25	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Table 29.--Concentrations of organochlorine compounds in individual bird carcass samples, 1990--Continued

Species	PCB's (total)	o, p' -DDE	a-Chlordane	P, p'- DDE	Dieldrin	o, p'- DDD	Endrin	Cis- nonachlor	o, p'- DDT	P, p'- DDD	P, p'- DDT	Mirex
Killdeer	ND	ND	ND	1.7	ND	ND	ND	ND	ND	ND	ND	ND
do.	ND	ND	ND	0.52	ND	ND	ND	ND	ND	ND	ND	ND
do.	ND	ND	ND	0.10	ND	ND	ND	ND	ND	ND	ND	ND
do.	ND	ND	ND	0.96	ND	ND	ND	ND	ND	ND	ND	ND
do.	ND	ND	ND	0.82	ND	ND	ND	ND	0.01	ND	ND	ND
do.	ND	ND	ND	0.09	ND	ND	ND	ND	ND	ND	ND	ND
do.	ND	ND	ND	2.3	ND	ND	ND	ND	ND	ND	ND	ND
Cassin's k-bird	ND	ND	ND	0.19	ND	ND	ND	ND	ND	ND	ND	ND
Cassin's k-bird	ND	ND	ND	0.04	ND	ND	ND	ND	ND	ND	ND	ND
Mallard duckling	ND	ND	ND	0.01	ND	ND	ND	ND	ND	ND	ND	ND
Mallard duckling	ND	ND	ND	0.01	ND	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	0.95	0.01	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	0.38	ND	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	1.1	ND	ND	ND	ND	ND	ND	ND	ND
Y.H. blackbird	ND	ND	ND	0.05	ND	ND	ND	ND	ND	ND	ND	ND
Mallard duckling	ND	ND	ND	0.02	ND	ND	ND	ND	ND	ND	ND	ND
Mallard duckling	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Mallard duckling	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Mallard duckling	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Mallard duckling	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	1.0	ND	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	1.4	ND	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	2.4	ND	ND	ND	ND	ND	ND	ND	ND
Cassin's k-bird	ND	ND	ND	0.09	ND	ND	ND	ND	ND	ND	ND	ND
Cassin's k-bird	ND	ND	ND	0.16	ND	ND	ND	ND	ND	ND	ND	ND
Cassin's k-bird	ND	ND	ND	0.03	ND	ND	ND	ND	ND	ND	ND	ND
Cassin's k-bird	ND	ND	ND	0.17	ND	ND	ND	ND	ND	ND	ND	ND
Coot	ND	ND	ND	0.03	ND	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	0.18	ND	ND	ND	ND	ND	ND	ND	ND

Table 29.--Concentrations of organochlorine compounds in individual bird carcass samples, 1990--Concluded

Species	PCB's (total)	o, p' -DDE	a-Chlordane	p, p' DDE	Dieldrin	o, p' DDD	Endrin	Cis- nonachlor	o, p' DDT	p, p' DDD	p, p' DDT	Mirex
Killdeer	ND	ND	ND	1.0	ND	ND	ND	ND	ND	ND	ND	ND
Killdeer	ND	ND	ND	1.6	ND	ND	ND	ND	ND	ND	ND	ND
Cassin's k-bird	ND	ND	ND	0.16	ND	ND	ND	ND	ND	ND	ND	ND
Eastern k-bird	ND	ND	ND	0.12	ND	ND	ND	ND	ND	ND	ND	ND
Eastern k-bird	ND	ND	ND	0.06	ND	ND	ND	ND	ND	ND	ND	ND
Eastern k-bird	ND	ND	ND	0.13	ND	ND	ND	ND	ND	ND	ND	ND

Table 30.--Cholinesterase enzyme activity in brain tissue and blood serum of birds: 1990

[Analytical results are in micromoles of acetylthiocholine iodide hydrolyzed per minute per gram of tissue, wet weight for brain tissue, and milliunits of acetylthiocholine iodide hydrolyzed per milliliter for blood serum; site number, see fig. 7 and table 3; ChE, cholinesterase]

Site number	Brain tissue			ChE	Site number	Blood serum		
	Date collected	Species	ChE			Date collected	Species	ChE
I-1,2,3	6-07-90	Mallard	7.6	I-1,2,3	6-12-90	Mallard	708.0	
I-1,2,3	6-07-90	do.	8.6	I-20	6-12-90	do.	518.0	
I-20	6-12-90	do.	11.1	I-20	6-12-90	do.	667.0	
I-20	6-12-90	do.	10.5	I-12	6-13-90	do.	660.0	
I-6	6-12-90	do.	10.3	I-21	6-13-90	do.	718.0	
I-10	6-12-90	do.	11.5	I-6	5-21-90	do.	824.0	
I-10	6-13-90	do.	11.4	I-10	5-23-90	do.	537.0	
I-21	6-13-90	do.	11.3	I-9	5-23-90	do.	608.0	
I-1,2,3	5-22-90	do.	6.7	I-16	6-11-90	Cinnamon teal	634.0	
I-6	5-21-90	do.	10.3	I-17	6-08-90	do.	555.0	
I-12	5-23-90	do.	8.5	I-21	6-14-90	do.	519.0	
I-10	5-24-90	do.	9.3	I-21	6-14-90	do.	824.0	
I-9	5-23-90	do.	8.9	I-21	6-14-90	do.	488.0	
I-3	6-12-90	American coot	22.4	I-16	6-11-90	do.	19.4	
I-10	6-12-90	do.	22.5	I-16	6-11-90	do.	24.2	
I-23	6-06-90	do.	24.5	I-17	6-08-90	do.	17.5	
I-23	6-06-90	do.	22.9	I-21	6-14-90	do.	19.0	
I-23	6-06-90	do.	20.7	I-21	6-14-90	do.	19.1	
I-23	6-06-90	do.	23.1	I-21	6-14-90	do.	18.5	
I-3	6-07-90	Green-winged teal	12.8					
I-2	6-07-90	Killdeer	16.1					
I-2	6-07-90	Killdeer	19.5					
I-3	6-07-90	Killdeer	16.9					
I-17	6-08-90	Killdeer	17.6					
I-17	6-08-90	Killdeer	18.1					

Table 30.--Cholinesterase enzyme activity in brain tissue and blood serum of birds: 1990--Concluded

Site number	Brain tissue			ChE	Site number	Blood serum		
	Date collected	Species	ChE			Date collected	Species	ChE
I-17	6-08-90	Killdeer	18.5					
I-6	6-05-90	do.	22.3					
I-6	6-05-90	do.	17.8					
I-10	6-05-90	do.	16.7					
I-10	6-05-90	do.	17.8					
I-10	6-05-90	do.	21.4					
I-21	6-13-90	do.	19.1					
I-21	6-13-90	do.	22.7					
I-21	6-13-90	do.	16.9					